



ME00P3

Mineral Exploration Code of Practice



Industry Safety and Mines



INDUSTRY SAFETY AND MINES

Mineral Exploration Code of Practice

EDITION 3 — JUNE 1995

While every care has been taken in the preparation of this report, no warranty is given as to the correctness of the information and no liability is accepted for any statement or opinion or for any error or omission. No reader should act or fail to act on the basis of any material contained herein. Readers should consult professional advisers. As a result the Crown in Right of the State of Tasmania and its employees, contractors and agents expressly disclaim all and any liability (including all liability from or attributable to any negligent or wrongful act or omission) to any persons whatsoever in respect of anything done or omitted to be done by any such person in reliance whether in whole or in part upon any of the material in this report.

CONTENTS

INTRODUCTION	4
Acknowledgements	4
EXPLORATION PROCEDURES — INFORMATION FOR EXPLORERS	5
EXPLORATION LICENCES — GENERAL INFORMATION	6
Duty of Care	13
Appointment of manager	13
Land available for exploration	14
National Estate — an explanation	15
Gaining approvals for exploration	16
Mineral Exploration Working Group	17
Archaeological study guidelines	19
Protection of Aboriginal heritage	19
Ownership of minerals	19
LAND CLASSIFICATION IN TASMANIA	20
MINERAL EXPLORATION CODE OF PRACTICE — EXPLORATION GUIDELINES	25
Cutting and use of grid lines	27
Tracks	32
Rehabilitation of tracks	45
Drill pads — environmental considerations	51
Costeans and pits	57
Rehabilitation and revegetation	61
Use of helicopters and helipads	63
<i>Helipad Safety</i>	65
<i>Embarking, Disembarking</i>	66
<i>Loading and Unloading</i>	67
<i>Flying</i>	69
<i>Hand Signals</i>	71
Camping	73
Plant diseases and weeds	75
<i>Phytophthora</i>	75
<i>Weeds</i>	77
Protocol with private landowners	79

Introduction

The Industry Safety and Mines Division of Tasmania Development and Resources rigorously enforces a policy of responsible and careful exploration, requiring all proposed exploration activities to be approved, in writing, before work commences. Conditions under which the exploration work may proceed are decided on a site-by-site basis, usually after consultation with other Government departments.

The purpose of this Code is to provide an outline of the current procedures which must be followed to obtain exploration approvals, and at the same time to give useful, practical information on the expected standards of exploration activities. The Code also details the controls and monitoring procedures which are currently in place.

Most mineral exploration activity in the State is low impact; reconnaissance mapping, stream sediment and soil sampling, grid cutting, and geophysical surveys all have a minimal disturbance on the environment, but are the necessary precursors to more detailed work.

Once an anomaly has been found by these low-impact methods, drilling or costeaning, sometimes involving the construction of access tracks, follows. This is the part of exploration which is the most visible. In the past, some access tracks have been pushed into areas nowadays considered to be sensitive. Community standards and expectations have changed greatly over the past twenty years, and past activities should not be judged using the standards of today. Exploration, especially in the first phases, is now expected to be of low impact, leaving little trace of activity.

Extensive liaison networks are in place, and there is regular consultation with land managers such as staff from Forestry Tasmania and the Department of Environment and Land Management.

Earthworks must be rehabilitated on the completion of the exploration programme unless the works are specifically required by an incoming explorer. In this case, the new explorer must accept responsibility for the tracks and drill pads left open for their use.

This Code gives detailed information on various earthmoving activities to allow these to be done in the best possible way. Other issues of importance to the explorer, such as protocol with private landowners and the need to prevent the spread of weeds and fungal diseases, is also documented. We envisage that the Code will provide explorers with a useful 'ready reference' guide to questions relating to all aspects of exploration.

ACKNOWLEDGEMENTS

In compiling this and the previous two editions of the Code of Practice helpful discussions have been held with a number of people, all of whom have made valuable contributions with their comments and ideas. I would especially like to

thank Pavel Ruzicka, Andrew Reeves, John Pemberton and Rod Hargreaves (Tasmania Development and Resources); Ron Neve (Forestry Tasmania); Tim Duckett; Jeff Randell and Ray Duraj (Billiton Australia); Brad Cartwright and Bill Bourke (Department of Environment and Land Management); Phil Uttley (RGC); Phil Jones; Ken Morrison; Lindsay Newnham; and Hans Rae, Fergus Fitzgerald and Colin Leatherborrow (Pasminco Australia Limited).

The final version of the Code (and several drafts) was produced by Michael Dix of the Division's Publications Section, using our Desktop Publishing facility. Forestry Tasmania kindly allowed the use of a number of diagrams from its *Forest Code of Practice*, diagrams of Huon Pine, Celery Top Pine and King Billy Pine from pamphlets on native trees, and the map on the distribution of *Phytophthora*. Sue Backhouse and J. B. Kirkpatrick kindly permitted reproduction of line drawings and descriptions of Cheshunt Pine and Deciduous Beech from their book *Native Trees of Tasmania*. Most of the remaining diagrams were drawn by Colin Abel. The information on weeds was updated by Dr Alan Harradine of the Department of Primary Industry and Fisheries.

Information on ABF-42 was taken from the Safety Data Sheet supplied by the manufacturer (Chemsearch Australia), and from a handout supplied by the Parks and Wildlife Service. The information on sodium hypochlorite comes from the Safety Data Sheet for that chemical, from data supplied by the Health Department, and from the *Dieback Hygiene Manual* of the West Australian Department of Conservation and Land Management. Additional information on the use of ABF-42, from the Registrar of Pesticides and the Parks and Wildlife Service draft *Phytophthora hygiene manual for the World Heritage Area* has been included in Editions 2 and 3.

The information and diagrams in the chapter on helicopters comes from material supplied by Helicopter Resources, and from a pocketbook on helicopter safety procedures prepared by Tim Rudman (Parks and Wildlife Service) and Tony Mount (Forestry Tasmania). Text and diagrams from this book are used with permission, and are gratefully acknowledged.

The text of the first edition of this Code was widely circulated amongst Government departments and other organisations (Tasmanian Chamber of Mines; Combined Environment Groups). Useful suggestions made by individuals during this process have been incorporated in the Code.

THIRD EDITION

In compiling this Third Edition I would like to acknowledge the assistance given by David Gatehouse, who contributed greatly to this revision. Photographs have been provided by David Gatehouse and Hans Rae (Pasminco Exploration).

Exploration Procedures — Information for Explorers

The following pages contain general information relating to the issues of exploration licences and approval of exploration works. This section also contains explanations of matters such as the Register of the National Estate, RAPs and Deferred Forest, which are all of use to the explorer.

EXPLORATION LICENCES

The Exploration Licence is the principal title for exploration in Tasmania. The following procedures are from the *Mining Act 1929*. When the *Mineral Resources Development Act* is passed some of these procedures may change.

APPLICATIONS

An application for an exploration licence may be made by:

- one or more persons over the age of 18 years;
- one or more bodies corporate;
- or a combination of these.

An application form is available to assist applicants. Should the form not be used, it is essential that an application include the following information:

- details of current holdings;
- names and qualifications of staff;
- estimated expenditure for the first two years of the licence;
- an outline of the exploration programme to be carried out.

It is not necessary for the applicant to mark out the proposed area of the exploration licence.

When the Director proposes to recommend to the Minister for Mines that a licence be issued, the applicant will be required to advertise details of the application in a newspaper circulating in the district of the application. The advertisement must be in the prescribed form and must include a map showing the location of the area.

An objection to an application may be lodged by any person who claims an estate or interest in the land. This includes a landowner, tenant, lessee or holder of an exploration licence for other mining products. Objections must be on the prescribed form available from Industry Safety and Mines, must be accompanied by the prescribed fee, and must be received by the Director of Mines no later than 30 days after the advertisement of the application.

Fees for Issue of an Exploration Licence are:

- | | |
|--|-----------|
| (a) Oil | \$1200.00 |
| (b) Any other mining product | \$300.00 |

PRIORITY OF APPLICATIONS

A moratorium period of two months applies when ground is released from an exploration licence by surrender, revocation, or reduction in area, or when a licence ceases to apply to mining products that had been the subject of the licence.

During the moratorium period an application may be made for an exploration licence or mining lease for the area and mining products that were subject to the former exploration licence.

Applications received during this period will have equal priority, and will take priority over subsequent applications.

ETA (Exploration Tender Area) SYSTEM

Industry Safety and Mines offers a service to subscribers advising them of areas available for application during a moratorium period. ISM accepts no responsibility for the accuracy of such information.

For an annual subscription of \$100.00, subscribers receive details of land surrendered or relinquished from exploration licences, together with maps and advice of the closing date of the moratorium period.

TRANSFER OF APPLICATIONS

An application may be transferred by completing the prescribed form and payment of a fee of \$50.00.

AREA OF LICENCES

Exploration licences for minerals or stone are not to exceed 250 km². Coal, oil and shale licences are not to exceed 500 km².

TERM OF LICENCE

An exploration licence is issued for 12 months, and is renewable.

PERIOD OF TENURE

Licence tenure is limited to a maximum of ten years. During the first five years of tenure the size of the licence must be reduced to no more than 50% of the original area.

Renewals will not be granted after the ten year term except in the following circumstances:

Where a discovery is made in the final years of the tenure of a licence, an extension may be granted for sufficient time to allow the discovery to be evaluated. The area of the extended licence will be limited to that necessary to give security of title to the discovery.

ANNUAL RENTAL

Rents for Exploration Licences are:

- | | |
|---|---------|
| (a) Oil — for each square kilometre per year— | |
| (i) for each of the first 3 years | \$1.00 |
| (ii) for each subsequent year | \$1.50 |
| (b) Other Mining Products — for each square kilometre per year— | |
| (i) for each of the first 5 years | \$15.00 |
| (ii) for each subsequent year | \$30.00 |

RIGHTS OF A LICENCE HOLDER

Only one exploration licence may be issued for the same mineral products on the same land. Within the area of the licence, the holder has an exclusive right to a mining lease in respect of the mining products specified in the licence.

The holder has the right to object to the issue of an exploration licence or a mining lease for other mining products in the area of the licence.

A miner's right or prospector's licence may only be used within the area of an exploration licence with the consent of the holder of the exploration licence.

CONDITIONS

A licence is issued subject to such conditions as the Minister may apply. A performance deposit is required to ensure compliance with all conditions of the licence. The amount of the deposit is determined by the size of the area, the programme to be carried out, and the environmental sensitivity of the area.

EXPENDITURE COMMITMENT

- (1) Unless otherwise specified as a condition of the licence, the following minimum expenditure applies:
- First two years at \$200 per km² per annum
 - Next two years at \$500 per km² per annum
 - Next two years at \$1 000 per km² per annum
 - Next two years at \$2 000 per km² per annum
 - Last two years at \$5 000 per km² per annum

The minimum expenditure commitment is \$5000 per annum.

- Over-expenditure in one year may be carried forward for one year only to offset under-expenditure.
- Under-expenditure in one year is to be made up the next year, together with that year's commitment.
- Licence holders not satisfying expenditure commitments in successive years will be required to show cause why all or part of a licence should not be revoked.
- A licence holder may apply to the Director of Mines to waive or reduce expenditure commitments.
- Reported expenditure must be itemised.
 - Only actual costs incurred in exploration work are to be included.
 - Administration costs, including licence fees, should not exceed 10 per cent of annual expenditure.

EXPLORATION ON PRIVATE LAND

Explorers wishing to explore on, or use access through private land, should contact the landowner and discuss their exploration plans well in advance of the programme commencement date. The *Mining Act 1929* requires that the owner or occupier of the land be given three days notice in writing, stating that work is to commence. However, explorers should take special pains to contact the landowner and discuss plans on a personal basis before sending, or delivering, the formal notice.

REPORTING REQUIREMENTS

Full details of reporting requirements are given in the brochure *Guidelines for Reporting on Exploration Licences* available from Industry Safety and Mines.

Interim Reports

Interim reports must include a statutory declaration of expenditure, an itemised breakdown of expenses, and a brief resumé of work in progress and completed.

Interim reports should be submitted on the form *Interim Report of Exploration* for the six months ending 30 June and 31 December.

Annual Reports

An annual report should be a full technical report detailing all exploration undertaken and results obtained during the year.

Final Reports

The final report should be a complete summary of exploration carried out on the area of the licence to be relinquished, plus details of work on that area which has not previously been reported. It should include a list of previous reports and their contents, and details of rehabilitation carried out on the area.

The final report must be lodged prior to the expiry date of the licence. Where a part only of a licence area is relinquished and no final report is submitted for the relinquished part, all reports relevant to the relinquished area will be released for public examination.

Failure to lodge a final report by the expiry date will result in the forfeiture of a portion of the performance deposit.

RESEARCH

A complete record must be submitted where research is undertaken on a licence area and is attributed to exploration activity and expenditure.

DISCOVERY

The Director of Mines is to be notified immediately on discovery of significant mineralisation.

CONFIDENTIALITY

All reports submitted to Industry Safety and Mines remain confidential until:

- a period of five years has elapsed from the date when the report was due to be submitted; or
- a licence expires, is relinquished, or is cancelled; or
- the area to which a report relates is no longer held by the licensee,

whichever occurs first, unless otherwise negotiated with Industry Safety and Mines.

RENEWAL OF LICENCE

The licence holder should apply for renewal at least thirty days prior to the expiry date. **Failure to make application prior to the expiry date will result in the licence being terminated.**

An application for renewal should be made on the form *Application for Renewal of an Exploration Licence*, and should be accompanied by:

- the licence document;
- the fee of \$600.00 for an Oil Licence or \$300.00 for any other Mining Product Licence;
- the annual rent;
- an annual report of exploration activity;
- a proposed work programme for the forthcoming year;
- where a licence is due for reduction or is voluntarily reduced, a plan showing the area to be relinquished.

If the area of the licence is to be reduced, the licence holder should give the Department at least two months notice, and must submit a final report on the relinquished area. *If a final report is not provided prior to the renewal date, the Department may release all reports pertinent to the relinquished area for public examination.*

TRANSFER

A licence may be transferred with the approval of the Minister. An application must be made on the prescribed form and be accompanied by a fee of \$100.00.

SURRENDER

A licence may be surrendered at any time with the approval of the Minister. An application for surrender must be made on the prescribed form and be accompanied by a \$50.00 fee. A surrender takes effect when approved by the Minister.

An application for surrender will not be approved until all reports, including the final report, have been lodged and disturbed areas have been rehabilitated to a satisfactory standard.

CHANGES TO THE LICENCE

The area of the licence, or the number of mining products for which the holder is authorised to explore, may be reduced with the consent of the Minister.

The area of the licence may be increased, and additional commodities included in the licence, either by:

- (1) the consent of the Minister; or
- (2) application for an exploration licence in respect of the additional area or commodities.

REGISTRATION OF LICENCES

All applications, grants, transfers of applications, changes in area, changes in mining products, approvals of transfers, approvals of surrenders, and revocations will be registered.

Where a moratorium period applies, there will be no registration of applications for exploration licences during that period.

APPROVAL AND REGISTRATION OF DEALINGS

All dealings in exploration licences must be approved by the Minister and registered.

A dealing, in this context, is an agreement 'by which a legal or equitable interest in or affecting an existing or future exploration licence or retention licence is or may be created, assigned, affected or dealt with directly or indirectly.'

This includes joint venture agreements, farm-in and farm-out agreements, options, compensation agreements, over-ride royalty agreements and the like.

An application for approval may be made by a party to the agreement and must be:

- made on the prescribed form;
- accompanied by a copy of the instrument;
- accompanied by the prescribed fee of \$50.00.

EXPLORATION LICENCE SCHEDULES

All exploration licences are issued subject to at least three schedules which contain the standard licence conditions. These are:

- **Schedule A:** Standard conditions outlining operational and reporting requirements.
- **Schedule B:** Cut line specifications and fire precaution regulations.
- **Schedule D:** Non-exclusive licence — exploration reports, which enables Industry Safety and Mines to reproduce and copy exploration reports once they are placed on open file.

Schedule C contains conditions relating the drilling for petroleum onshore, and is not applied to every licence.

MONITORING AND PENALTIES

Regular field inspections are made by officers of Industry Safety and Mines, and on occasions joint inspections are made with officers from other agencies to ensure that conditions placed on the work programme are being observed. Penalties imposed for breaches of conditions can include the forfeit of bond monies and/or the licence.

SENSITIVE AREAS

Exploration activities proposed in Protected and Conservation Areas, and other areas considered to be 'sensitive', must be approved by the Mineral Exploration Working Group, which consists of representatives from Industry Safety and Mines, the Department of Environment and Land Management, and Forestry Tasmania. Other departments and interested bodies are consulted on individual projects where required.

SCHEDULE "A" (Revised February 1995)

Conditions of Exploration Licences under the *Mining Act 1929*

Operational:

1. The licensee shall conduct operations so as not to disturb the environment except in so far as this may be necessary to undertake the programme of exploration required by this licence.

Specific written approval is required from Industry Safety and Mines for any of the following activities:

- Track construction, repair or restoration whether or not the activity includes moving earth and cutting vegetation including 'one pass' traverses off formed roads by either tracked or wheeled vehicles.
- Drilling activity, whether or not drill pad construction, involving stripping to bare earth, clearing or flattening of vegetation, is required.
- Helipad construction.
- Costeaming and pitting.
- Augering either by hand or machine.
- Cutting of grids.
- Stream-sediment sampling.
- Movement of heavy machinery, either wheeled (cranes, rigs and trucks etc.) or tracked (dozers, excavators, backhoes, traxcavators, rigs, bombardiers etc.) on to a licence. This may include access through other licences.

Conditions imposed on such works must be strictly observed.

2. Proposed programmes should be submitted at least one month before work is planned to commence to allow time for field inspections to be arranged if required.

Industry Safety and Mines will contact other Government agencies as required to seek their advice in order to set conditions on a site specific basis.

Work programmes must not be sent to other agencies other than via Industry Safety and Mines.

3. Work is to be planned to avoid, insofar as practicable, the need to construct tracks and drillpads in wet weather.
4. On the completion of exploration, all works (tracks, helipads, drill pads, costeams etc.) are to be rehabilitated to the satisfaction of the Director of Mines.
5. The licensee shall observe the provisions of Section 35 of the *Mines Inspection Act 1968*, with regard to notification of bore holes, preservation of cores and disposal thereof.

6. At the termination of the licence or at any time at the option of the licensee all drill core and samples required by the Director of Mines shall be delivered in core boxes 1000 millimetres long and either 400 or 200 millimetres wide to the Department's Core Store at Mornington at the cost of the licensee unless the Director of Mines notifies the licensee in writing that such core or samples are not required. Where companies are still using stocks of old core boxes (1050 × 470 mm for example) these will be accepted by the Department.

7. The licensee shall observe any instructions which may be given by the Director of Mines with a view of minimising or preventing damage to public or private property, and conform to the provisions of the Mineral Exploration Code of Practice, as revised from time to time, for all operations.

8. The licensee shall not light any fires without the approval of the State Fire Commission or the relevant District Forester when on State Forest. When on land reserved under the *National Parks and Wildlife Act 1970* or the *Crown Lands Act 1976*, the approval of the Secretary of Parks and Wildlife Service is required. Precautions are to be taken with fuel storage to minimise the risk of fire. The licensee, agent and/or employees during exploration activities shall be responsible for the immediate suppression of non-permit fires arising from those activities.

9. The licensee shall notify the relevant District Forester of Forestry Tasmania before entering on a State Forest and shall comply with the reasonable requirements of such officer in operations on any such State Forest. Any commercial forest produce which is cut down (with approval) during exploration must either be paid for at current rates or removed for salvage.

The licensee shall allow unhindered access for forestry operations and Forestry Tasmania officers during work in State Forest.

10. The licensee shall notify the relevant Parks and Wildlife Service Ranger or Property Officer before work commences in land reserved under either the *National Parks and Wildlife Service Act 1970* or the *Crown Lands Act 1976* (where such lands have been brought back under the *Mining Act 1929*).

11. Where any Aboriginal artefacts or objects of historic interest are discovered, operations shall be conducted so as not to damage or interfere with such site or object, and the licensee shall report details of such discovery to the Secretary, Parks and Wildlife Service and shall otherwise observe the provisions of the *Aboriginal Relics Act 1975*.

SCHEDULE "A" (continued)

There may be a requirement for archaeological inspections to be conducted prior to approval for works being granted in some areas.

12. The licensee shall not interfere in any way with native fauna or bird life.
 13. Where investigations are to be undertaken in sensitive areas (such as coastal areas, Conservation or Protected areas) all exploration proposals must first be assessed by the Mineral Exploration Working Group.
 14. All waste, rubbish and other materials produced or used during the exploration and related works are to be removed from the licence area or, if approval is so granted, buried on site.
 15. All licence holders must ensure that field officers are fully aware of all conditions and schedules applying to the licence. A copy of the licence is provided by Industry Safety and Mines for this purpose.
 16. The Minister reserves the right to suspend operations immediately if weather conditions and/or the operation are causing unnecessary damage to roadways and tracks.
- Reporting:**
1. An interim report must be lodged quarterly with the Director of Mines, Hobart (i.e. 31 March, 30 June, 30 September and 31 December).
 2. This statement shall include a statement of expenditure and a brief progress report of operations. The interim report shall be lodged within 14 days of the above due dates.
3. The licensee shall furnish the Director of Mines, Hobart, with an Annual Report detailing all investigations undertaken during the term of the licence **one month** prior to the licence renewal date. This shall include detailed reports, plans, sections, analyses, metallurgical investigations and feasibility and other studies. All plans must include transparencies unless the Director of Mines advises in writing that such are not required.
 4. All information furnished to the Director of Mines under this licence will be held in confidence for official purposes:
 - (a) during a period of five years from the date on which such information was furnished to the Director of Mines; or
 - (b) until the areas to which the reports relate are no longer lawfully held under the *Mining Act 1929*;
 whichever shall occur first, unless otherwise negotiated with Industry Safety and Mines.
 - Copyright of lodged material will transfer from the author to Industry Safety and Mines once the data are transferred into the ISM Open File library.
 5. **One month** prior to relinquishment of any part of the area described in the schedule hereto, the licensee shall furnish a report containing all information relating to such unless the Director of Mines advises, in writing, that such report is not required.

SCHEDULE "B" **(Revised December 1990)**

Cut Line Specifications and Fire Precaution Regulations

CUT LINE SPECIFICATIONS

1. Access to cut-lines from established tracks will be discreet, to reduce the possibility of subsequent misuse.
2. Markers to indicate commencement of access tracks will be minimal, and will be removed when activities are suspended.
3. Cut lines will not exceed one metre in width.
4. Clearing will be kept to a minimum; trees will not be blazed.
5. Unless imperative, no live saplings over 15 cm in diameter will be felled.
6. Track-cutters must recognise and avoid cutting the following native species: Huon Pine, King William Pine, Cheshunt Pine, Celery Top Pine and Deciduous Beech.
7. Fire must not be used for track making.
8. Non-biodegradable track markers will be removed when work is completed.
9. On completion, all introduced debris will be removed including cans, bottles, paper, fabric etc.

FIRE PRECAUTION REGULATIONS

Exploration managers will ensure that **during a fire permit period**, persons occupying permanent and semi-permanent camp sites, drilling sites, or work sites using, servicing or refuelling earth-moving equipment shall have the sites equipped with the following fire-fighting tools:

- a serviceable knapsack pump filled with not less than 10 litres of water or a powder-type fire extinguisher of not less than one kilogram capacity;
- a slash hook;
- a fire rake or grubbing-hoe;
- a receptacle containing not less than 180 litres of water.

Track cutting teams using chainsaws, and persons on work sites where chainsaws, power augers, generators or other petrol engines are frequently used, will maintain within sensible reach a serviceable knapsack pump filled with not less than 10 litres of water, or a powder-type fire extinguisher of not less than one kilogram capacity.

All premises used as kitchens or as sites for storing fuel or storing, servicing or refuelling engines will be:

- cleared to bare earth;
- surrounded by a firebreak sufficient to isolate the premises from the surrounding vegetation.

SCHEDULE "C"

Schedule of Onshore Petroleum Exploration and Production Requirements

Copies are available on request.

SCHEDULE "D" (December 1994)

Non-exclusive Licence — Exploration Reports

1. Licence to use reports

- (a) In respect of reports prepared by or on behalf of the holder and submitted to the Director pursuant to Schedule A of this licence or otherwise, the holder hereby grants to the Minister, by way of a non-exclusive licence, copyright therein, to publish, print, adapt and reproduce the work in any form and for the full duration of the copyright, subject to a period of confidentiality as outlined in sub-clause (2).
- (b) The non-exclusive licence to do acts comprised in the copyright granted hereunder is a consent to disclosure of the information contained in the copyright material.

2. Confidentiality

- (a) All exploration reports submitted in accordance with the conditions of this title will be kept confidential for a period of five years from the due date of the report, or while the title is in force, whichever is of the shorter duration, except in cases where:
 - (i) The holder has agreed that specific reports may be made non-confidential.
 - (ii) Reports deal exclusively with exploration conducted on areas that have ceased to be part of the title.
- (b) Confidentiality of reports will be continued beyond the termination of a title in cases where an application for renewal of that title was lodged during the currency of the title, provided that a period of no more than five years has elapsed since the due date of a report concerned. An application for an amalgamated exploration licence would be treated in the same way as an application for renewal for the purpose of this sub-section.
- (c) The maintenance and continuation of the period of confidentiality under sub-clauses (a) and (b) above is subject to the holder submitting a report on all exploration conducted in the parts of the tenement that have been relinquished. Such reports will be made public.
- (d) The Director may extend the period of confidentiality in respect of reports beyond the time(s) stipulated in sub-clauses (a) and (b) hereof.

3. Terms of the non-exclusive licence

The terms of the non-exclusive copyright licence granted under sub-clause (1)(a) are:-

- (a) The Director may sub-licence others to publish, print, adapt and reproduce but not on-licence the copyright in a report.
- (b) The Director and any sub-licensee will acknowledge the holder's and any identifiable consultant's ownership of copyright in reports in any reproduction of reports, including storage of reports onto an electronic database.
- (c) The holder does not warrant ownership of all copyright works contained in any report and the holder will use best endeavours to identify those parts of the report for which the holder owns the copyright.
- (d) There is no royalty payable by the Minister for the licence.

DUTY OF CARE

RESPONSIBILITY OF EMPLOYERS

Employers have a duty of care to provide a safe workplace for their employees. An employer must provide such information, instruction, training and supervision as may be necessary to ensure the health and safety of employees whilst at work.

RESPONSIBILITY OF MANAGERS

- Managers have a duty of care to all their employees and support staff including contractors. This includes:
 - Ensuring plant and equipment are in good working order and are safe to operate.
 - Making arrangements to ensure that where persons operate, the working place is safe.

- Ensuring that persons are adequately trained to perform their duties in a safe manner.
- Providing adequate supervision, instruction and information to ensure operations are carried out safely.
- Making safe any hazard (such as old, unprotected shafts) on the Exploration Licence which may come to his/her notice for the protection of the public as well as the workers

RESPONSIBILITY OF EMPLOYEES

- Every person employed on an EL must take reasonable steps to ensure that the machinery used by him/her and his/her place of work are safe.
- Every person employed on an EL has a duty of care to prevent other persons from being exposed to any danger of which he/she may be aware.

APPOINTMENT OF MANAGER

The *Mines Inspection Act 1968* requires that a manager be appointed to be responsible for the work conducted on an exploration licence. A manager is only required if work is being conducted **on the ground**.

An EL is clearly not being worked if the only exploration work carried out is by means of aerial surveys.

When no work is being carried out on an EL, the manager has no responsibility with regard to the Act.

A manager may be appointed for part only of a mine or, with the consent of the Chief Inspector of Mines, several mines (i.e. a manager may be appointed for that part of an EL where work is being carried out or for several parts of that EL or for several EL's or parts thereof).

The Chief Inspector may object to the person appointed as manager. This is highly unlikely if the appointee is a supervising geologist or the like.

The manager may appoint one or more persons to assist him in the day-to-day supervision of operations. This person may be the contractor and/or his nominee. An Inspector of Mines must be notified of this appointment.

The keeping of a Record Book by managers is mandatory. Record Books are legal documents which only inspectors, managers, or persons appointed by managers to assist them can sign.

LAND AVAILABLE FOR EXPLORATION

Exploration Licences are marked out according to the Australian Map Grid, in 1 km² blocks. There are, however, a number of land categories which are not included in the licence, and are not available for exploration.

Land which is **EXCLUDED** from the licences includes:

- All forms of mining tenements and water licence, including leases, water licences, easement licences, special and exploration licences, prospectors licences, miners rights, permits to enter, owners consents and owners rights which were in lawful possession or marked out prior to the date of application.
- Land exempt from the provisions of the *Mining Act 1929*, such as 'Exempt Areas', which are declared usually to allow for geological assessment of an area by Industry Safety and Mines.
- Fossicking areas: the top two metres of land which is set aside as a Fossicking Area will be excluded. Land beneath this depth will be included. Fossicking Areas will be formally declared under the new *Mineral Resources Development Act*.
- Land reserved under the *National Parks and Wildlife Act 1970*, having the status of State Reserve and in practical terms not being subject to the *Mining Act 1929*:
 - State Reserves
 - National Parks
 - Historic Sites
 - Nature Reserves
 - Aboriginal Sites
 - Game Reserves
- Land reserved under the *Aboriginal Relics Act 1975*, such as Protected Archaeological Sites.
- Public and municipal reserves under the *Crown Lands Act 1976*, such as:
 - State Recreation Areas
 - Coastal Reserves
 - River Reserves
 - Lakeside Reserves
 - Some roadways (such as highways)
 - Crown Reserves for conservation purposes, e.g. Mt Nelson Signal Station Reserve
 - Crown Reserves such as cemeteries.
 - Crown Reserves for construction materials and water (Crown ballast pits, quarry reserves, water reserves etc.).

Any of these public and municipal reserves can be brought back under the Mining Act to allow for exploration if a sufficiently good case can be made. This is generally relatively straightforward when explorationists require access to Crown gravel and quarry reserves and ballast pits, but is not common in any of the other categories which have usually been set aside for conservation purposes. Any exploration which was permitted in any of these areas would have to be first approved by the Mineral Exploration Working Group.

- Forest Reserves: these can be brought back under the Mining Act to allow for exploration if a good case for this can be made. Any exploration which was permitted would need to be first approved by the Mineral Exploration Working Group.
- HEC vested lands, which cover lakes, dam sites and work areas.
- Commonwealth land.
- Land around lighthouses, Telecom installations and land leased to the Commonwealth for military purposes such as the Stony Head Artillery Range and the Buckland Military Training Area.

The following land categories are **INCLUDED** in an Exploration Licence:

- Crown Land (if uncommitted).
- Crown Reserves (if not proclaimed. Technically speaking these are still uncommitted Crown Land, and are known as 'notary' reserves).
- State Forest (if brought back under the Mining Act after dedication of forest).
- Deferred Forest Land
- HEC vested lands (except lakes, dam sites, work areas).
- Private property.
- Conservation Areas (except the Central Plateau Conservation Area).
- Protected Areas (if brought back under the Mining Act after being proclaimed).
- Forest Reserves (if brought back under the Mining Act after being proclaimed).
- Wildlife Sanctuaries: some have management plans which specifically prohibit exploration; in others approval for exploration is not likely to be given. Usually excluded from licences by agreement with the applicant.
- Muttonbird Reserves: approval for exploration not likely to be given; usually excluded from the licence application by agreement with the applicant.

NATIONAL ESTATE — AN EXPLANATION

As there appears to be a fair amount of confusion between the terms 'National Estate', 'World Heritage' and 'National Park', an explanation of what National Estate actually means is given below. The Australian Heritage Commission maintains a 'Register of the National Estate'. There are three classes of entries in the register: nominations, interim listings and registered entries. 'Nominations' are entries of areas nominated for the register, as outlined by the person nominating the entry. 'Interim Listings' are nominations which are presently being considered, and 'Registered Entries' are those nominations which have been assessed and accepted onto the register.

How places are registered

Anyone can nominate a place or item to be considered for registration. Each nomination is assessed by Commission staff, who may refer the nomination for comment to expert panels, government agencies, or voluntary expert bodies. The final decision on what is placed on the register is made by the Commission. In deciding whether or not a nomination will be accepted, the Commission examines only the significance of the place in National Estate terms.

Issues such as current or planned use, management, or ownership of the place are not considered.

Once the Commission has accepted a nomination, this is advertised by notices in the Press and in the Commonwealth Gazette. Anyone may lodge an objection to that proposal within three months of publication of the notice.

The Heritage Commission is required to give 'due consideration' to any objections received. If the significance of the place is brought into question, an independent expert or body will be engaged to assess the information. Objectors are given an opportunity to state their case to these experts, and to examine and comment upon the assessor's report. The Commission considers all this information before making a final decision.

Effects of Registration

The Register has a direct protective role **only** in relation to actions proposed by the **Commonwealth** which might adversely affect the National Estate.

There are no direct legal constraints on owners of private property, or on State or local governments, caused by the entry of that property in the Register of the National Estate. Thus the Commission has no power to direct private owners or State or local governments with respect to their actions that might affect a place in the Register, and may not acquire property entered in the Register.

The entry of a place on the Register does not automatically entitle the public access to that place.

Whilst works by private owners, and State and local governments may not be directly controlled by the Australian

Heritage Commission, there are still some activities which would be affected. Works which require Commonwealth approval, for example, may not be approved. The Act requires that Commonwealth Ministers, and Commonwealth Authorities must "ensure that their own actions and those of their departments and authorities do not adversely affect the national estate values of places in the Register unless there are no feasible and prudent alternatives and, if there are no such alternatives, unless all reasonable measures are taken to minimise the effect. The Minister's actions to achieve these ends must be consistent with any relevant laws."

Further, before a Minister, department or authority takes any action that might significantly affect the national estate value of a place in the Register, they must inform the Commission and give reasonable opportunity to consider the proposed action. The statement of significance for each place in the Register provides the basis for the Commission's conservation advice to Commonwealth Ministers and bodies.

This means that activities in National Estate areas which do not require any input from the Commonwealth are not affected by the National Estate status. For example, a patch of forest may be cleared and used within the State as firewood or fence posts; but should the clearing be for woodchips for export, then the Commonwealth must be approached for an export permit, which, if not granted, would have an effect on the proposed activity.

Purpose of the Register

- To provide a comprehensive list of all places in Australia which have heritage value.
- To educate Australians, by means of this list, about the natural and cultural history of their country.
- To give all decision-makers, inside and outside government, objective information to help them make better decisions.
- To ensure as far as possible that Commonwealth decisions and actions related to listed places are taken as thoughtfully and carefully as possible.

The Commission's functions as listed in the Act, and the provisions of Section 30 of the Act, make it quite clear that the Commission's only decisive powers relate to the entry of places in the Register of the National Estate. Other functions of the Commission are advisory, educational or research oriented.

Decisions on whether Commonwealth actions which might adversely affect a place in the Register proceed, are modified, or do not proceed, remain with the Commonwealth proponent. The Commission's role is to ensure, as far as it is able, that such decisions are taken in the light of the National Estate significance of the place involved.

GAINING APPROVALS FOR EXPLORATION

APPLICATIONS

When submitting an application, or a renewal for an exploration licence, the applicant is asked to supply Environmental Impact Information (on the green EII forms provided) and an outline of the proposed work programme.

All EL applications are circulated to the Department of Environment and Land Management and the relevant land management agency for information and comment. Agencies can flag areas likely to be of interest should activities involving ground disturbance be proposed.

Quite often, the applicant will only have a conceptual plan of the exploration proposed, with actual details of the programmes still to be worked out.

WORK PROGRAMME

When the details are known, and plans of where grids are required, which access is to be used, which targets are to be drilled, etc., the explorer should send in either a completed EII work programme (pink) form or a letter outlining the proposed programme. A legible piece of chart at a suitable scale showing the location of the proposed activity must be included.

On receipt of a work programme the Department checks the following:

- Land status (to ensure activity is on land included within exploration licence and is not on a mining lease, or a reserve category which is excluded from the licence).
- Reserve proposals (RAP's, any other proposed reserves).
- Vegetation type (Rainforest/Huon Pine/King Billy/Heath).
- Any other significant features which have been flagged at the application stage:
 - archaeologically interesting areas or sites;
 - populations of rare plants or animals;
 - forestry plantations, grazing leases, forest licences;
 - licences from the Department of Environment and Land Management for any purpose.

The Department frequently produces maps showing the areas of environmental concern and the proposed works. These maps are given to the explorer to enable compliance with conditions relating to the work.

INSPECTIONS

Virtually no earthworks (unless they are upgrading of existing tracks or minor extensions of a currently used track) are approved until a site inspection has been made of the location. Inspections are difficult to arrange at short notice. Please submit your plans which may require field inspections at least three weeks prior to your planned starting date, whenever possible.

Following the field inspection, which is often made jointly with field officers from other Departments, approval is given in writing stating the conditions under which the work is to be done. A copy of these conditions is provided to the relevant District Forester, if the area is in State Forest, or other relevant land manager. Conditions of individual exploration activities are made available to persons having a bona fide interest in the work.

CONDITIONS

Conditions on all exploration licence activities are imposed in effect by the Minister for Mines. The paperwork is done by Industry Safety and Mines as an administrative arrangement.

APPEAL

Explorers can appeal against any work condition considered unreasonable by submitting an appeal, in writing, to the Minister within 14 days of receipt of the approval. Industry Safety and Mines is not a land management agency and the concerns of the relevant land managers must be accommodated in the formulation of appropriate conditions.

On occasions, where there are many people involved, a 'duplicate book' may be used. The terms under which the work is approved are written in this book during the field inspection; these conditions are subsequently sent as a formal letter but in the meantime there can be no misunderstanding between the field visit verbal agreement and receipt of the formal written approval. This is useful where the field inspection is made with one person, who must subsequently relay the instructions to several others.

Frequent field inspections are made during the programme, and on completion, to ascertain any rehabilitation requirements. Bonds are held until any rehabilitation required is completed to the satisfaction of Industry Safety and Mines and the relevant land manager.

MINERAL EXPLORATION WORKING GROUP

PURPOSE

Matters relating to mining and exploration in Conservation and other sensitive areas will be referred to an interdepartmental committee, the Mineral Exploration Working Group (MEWG), for consideration.

The function of the committee is to investigate the impact that any works may have on the historical, archaeological, botanical, zoological or ecological significance of the place, and if need be advise Industry Safety and Mines of conditions to be placed on the activities so that these values are not permanently adversely affected.

MEMBERSHIP

Membership comprises representatives from Industry Safety and Mines, the Department of Environment and Land Management, the Parks and Wildlife Service, and Forestry Tasmania.

AIM OF MEWG

The MEWG may request that studies (archaeological, historical, botanical, etc.) be carried out prior to the work to properly assess the impact of the proposed activities.

Explorers working in such areas may be required to engage a specialist to advise the field crews on field techniques, such as recognition of artefacts and rare species.

Some activities may only be permitted in a modified form; for example access during the early stages of a project may be allowed by helicopter, but not by construction of a track, or other earthworks.

The fundamental aim of the Working Group is to allow the aims of the explorer to be met without compromising the conservation values of the area.

APPLICATIONS AND WORK PROGRAMMES

Exploration licence applications are to be accompanied by a brief outline of the type of work expected to be done if the licence is granted. However explorers are not required, at the application stage, to have a detailed plan of works. Work programmes are therefore independent from applications.

As soon as the exact locations of any proposed grids, drill holes, tracks, costeans or any other works liable to result in environmental disturbance have been decided, the applicant must forward to Industry Safety and Mines a detailed work programme, with locations marked on a legible map of suitable scale, for approval.

Exploration work programmes involving work in Conservation and other sensitive areas will be referred to the MEWG for comment. In Conservation and Protected Areas, Coastal Areas and some Reserves brought back under the Mining Act, all proposed programmes, including those involving only low impact reconnaissance work, will be sent for comment. In other areas only those proposals involving

significant ground disturbance or earthworks (such as extensive gridding, drill pad or track construction) will be circulated. Work is not to commence until the programme has been approved in writing.

Mining lease applications in conservation and other sensitive areas will be sent to the MEWG for comment.

AREAS TO WHICH THESE GUIDELINES APPLY

Conservation Areas	All work
Protected Areas	All work
Reserves brought back under the Mining Act e.g. Forest Reserves, State Recreation Areas	All work
Coastal Areas	All work
RAPs	Ground disturbance
Deferred Forest	Ground disturbance
Areas subject to Tasmanian Aboriginal land claims (as recognised by DELM)	Ground disturbance
Rehabilitation areas (e.g. Greening Australia Project Area, South Mt Cameron)	Ground disturbance
Any other area for which special, natural or cultural features are recorded.	Ground disturbance

RESPONSIBILITIES OF THE EXPLORER — PREPARATION OF WORK PROGRAMMES

The programme submitted for approval shall detail, as accurately as possible, all works proposed which may have environmental impact. The following offer guidance on the content of the programme.

- As the approved programme will constitute the works allowed in the exploration area the programme should be prepared on the basis of a preliminary reconnaissance of the area, which should take particular note of those features which are vulnerable to disturbance, e.g. vegetation, wildlife, scenery, Aboriginal relics, archaeological sites, catchment values, erodable features, access routes, etc.
- The exploration programme shall provide details on the following:
 - The physical extent of exploration works.
 - The methods intended to be employed. Exploration methods should be chosen with care, so as to produce the minimum environmental impact consistent with proper exploration techniques.
 - Where possible the timing of proposed exploration works should be stated.

- The programme should specify how it is proposed to:
 - Gain access to and travel within the exploration area.
 - Accommodate personnel and locate camps within the area.

Where construction of any track, airstrip, camp or other works is envisaged, the locations and specifications for the works should be detailed. Vehicles will not normally be permitted to leave approved tracks or access routes.

- The programme should provide details on:
 - Fire prevention and protection.
 - Road drainage and maintenance.
 - Vehicle use.
 - Where possible the methods of placing and supporting drilling crews and rigs.
- The programme should detail proposals for rehabilitation of damage resulting from exploration activities. Where re-vegetation is proposed it should be noted that species of local provenance should be used unless approval has been given for other species to be employed.
- The exploration programme is to be supported by such maps and drawings as are necessary to make clear what works are proposed.

VARIATIONS TO THE PROGRAMME

The requirements of the explorer may vary as the exploration programme progresses and results come to hand, and as variations to the initial programme are desired. The very

nature of exploration means that an entire programme usually cannot be planned in detail, later work being dependent upon the results of the first phase of exploration activity.

Variations to the approved exploration programme which are likely to have environmental impact, such as re-siting of drill holes, test pits etc., should be submitted to the Director of Mines, who will obtain approval for the variations from the appropriate Managing Authority.

FIELD STAFF

All licence holders must ensure that field officers are fully cognisant with the approved programme and any variations, together with all conditions and schedules applying to the licence. However, the licence holder remains responsible and liable for any rehabilitation and other works required to restore areas.

REHABILITATION

Bonds are held on exploration licences and mining leases to ensure compliance with environmental and rehabilitation obligations. Bonds are not returned until rehabilitation is satisfactory. Bonds will be at least commensurate with the cost of any restoration work which is likely to be needed.

CODE OF PRACTICE

All exploration activities will abide by the Mineral Exploration Code of Practice, and to additional conditions imposed on the work.

ARCHAEOLOGICAL STUDY GUIDELINES

Consideration should be given to having an archaeological study made of an area where earthworks are planned:

- within one kilometre of high water mark;
- within 50 m of streams, waterways, marshes or lakes;
- within 250 m of historic industrial sites, such as old mine workings or timber mills and associated housing and infrastructure sites;
- along old tramways;
- in regions known to be "archaeologically rich".

PROTECTION OF ABORIGINAL HERITAGE

All Tasmanians are bound by the provisions of the *Aboriginal Relics Act 1975*. Sections from this Act which are of particular note to explorers are listed below.

2—(3) For the purposes of this Act, but subject to the following provisions of this section, a relic is —

- (a) any artefact, painting, carving, engraving, arrangement of stones, midden or other object made or created by any of the original inhabitants of Australia or the descendants of any such inhabitants;
- (b) any object, site, or place that bears signs of the activities of any such original inhabitants or their descendants; or
- (c) the remains of the body of such an original inhabitant or of a descendant of such an inhabitant who died before the year 1876 that are not interred in—
 - (i) any land that is or has been, set aside, reserved, or used for the purposes of a burial-ground or cemetery pursuant to any Act, deed, or other instrument; or
 - (ii) a marked grave in any other land.

14—(1) Except as otherwise provided in this Act, no person shall, otherwise than in accordance with the terms of

a permit granted by the Minister on the recommendation of the Director—

- (a) destroy, damage, deface, conceal, or otherwise interfere with a relic;
- (b) make a copy or replica of a carving or engraving that is a relic by rubbing, tracing, casting, or other means that involve direct contact with the carving or engraving;
- (c) remove a relic from the place where it is found or abandoned;
- (d) sell or offer or expose for sale, exchange, or otherwise dispose of a relic or any other object that so nearly resembles a relic as to be likely to deceive or be capable of being mistaken for a relic;
- (e) take a relic, or cause or permit a relic to be taken, out of this State; or
- (f) cause an excavation to be made or any other work to be carried out on Crown land for the purpose of searching for a relic.

20 A person who is guilty of an offence against this Act for which no other penalty is expressly provided elsewhere in this Act is liable to a penalty of \$500 or 6 months imprisonment, or to both such fine and imprisonment.

OWNERSHIP OF MINERALS

Whilst the Crown retains the ownership of minerals found on most of the private land in Tasmania, there are, nevertheless, some exceptions to this. Prior to 1890 the rights to coal and metallic minerals, excluding gold and silver, were usually given with the land being granted, and subsequent sales of the original land grant have not altered these rights. From 1893 the rights to various ores and metals were reserved to the Crown, but as the wording of grants varied from grant to grant until around 1910, the only real way of

ascertaining mineral ownership is to search for the original terms of the land grant. Some landowners have rights to all minerals in the top 50 feet of the land surface, others have rights to all minerals excepting gold and silver, and others have only rights to soil and stone. The terms of the original grant may also be altered by subsequent legislation; in Tasmania the rights to petroleum and atomic substances were reviewed by the Crown in 1962.

Land classification in Tasmania — A guide for explorers

INTRODUCTION

The major Acts under which Crown Land may be reserved in Tasmania are:

- National Parks & Wildlife Act 1970
- Aboriginal Relics Act 1975
- Crown Lands Act 1976
- Forestry Act 1920
- Public Land (Administration and Forests) Act 1991
- Mining Act 1929

Under each of these Acts land may be excluded from the auspices of the *Mining Act 1929*. In practical terms this means land excluded from the operation of the Mining Act is not available for mining or exploration. In addition, Industry Safety and Mines may enter into agreement with an Agency to exclude certain lands from mining tenements without this land being excluded formally from the Mining Act. An example of this is the agreement between Industry Safety and Mines (ISM) and the Hydro-Electric Commission whereby land vested in the HEC by the *HEC Act 1944* remains subject to the Mining Act but certain parts (around dams etc.) are excluded from mining tenements.

Another (unique) example is the agreement with the National Trust to exclude a National Trust Classified Historical Site at Derby from any mining tenement application.

There are additional categories of land not covered by these Acts, such as Private Property and Commonwealth land.

Private Property

This is available for exploration, provided certain protocols are followed. Landowners may object to the issue of an exploration licence over their land and the objection will be heard by a Warden of Mines. Having ownership of the land does not, in itself, constitute a reason for the EL to be disallowed.

A private property bond is held by Industry Safety and Mines to ensure landowners are compensated for any damage not made good by the explorer.

Explorers must give landowners notice in writing three days prior to entry on to the property.

Commonwealth Land

This is excluded from Exploration Licences. This includes, for example, land around lighthouses, Telecom installations (all small areas), as well as the Stony Head Artillery Range and the Buckland Military Training Area.

SHAPE OF EXPLORATION LICENCES

One of the most confusing features relating to exploration licences is the fact that a licence, in plan, may **appear** to cover a certain patch of land. Exploration licences must be

marked out on the AMG metric grid in square kilometres for ease of drafting. The plan may cover some 'excluded' ground which will be specified as such in the written licence document. Explorers are now provided with a small piece of chart showing exclusions, but these are not routinely charted on the ISM licence charts, as most charts are of a scale not suited to showing many small exclusions and these are best noted by description.

MINING ACT 1929

Administered by: Industry Safety and Mines

On-ground Manager: Various

Existing Mining Tenements

Existing mining leases, water licences, easement licences, exploration licences, retention licences, prospectors licences, authority to prospect permits, miners rights, permits to enter, owners consents and owners rights are **EXCLUDED** from exploration licence applications.

Exempt Areas

Areas may be declared 'Exempt' from the Mining Act to allow ISM to carry out geological investigations. These are not generally available for exploration, but access for some work will be considered by ISM.

Licences Over Same Area

Two exploration licences can be held over the same piece of ground for different commodities, e.g. coal and all minerals.

The applicant is provided with a piece of chart showing these exclusions, or areas of overlap with another licence.

Fossicking Areas

At present these have no special status but will probably be declared under the new Mineral Resources Development Act. In the interim these areas (which extend from the land surface to 2 m depth) will be excluded from EL applications. The explorer will be permitted to examine the area in the same way as are the fossickers. Surface access for drilling may be considered on a case-by-case basis. No mechanical excavations (trenching, costeaning) will be permitted.

NATIONAL PARKS & WILDLIFE ACT 1970


Administered by: Parks and Wildlife Service,
Department of Environment and
Land Management

On-ground Manager: Parks and Wildlife Service

Land may be reserved as either a State Reserve, a Conservation Area, or a Game Reserve.

State Reserves (SR)

Land having the status of State Reserve is exempt from the Mining Act for all intents and purposes. Exploration and mining can only occur in a State Reserve if the activity is



authorised in a management plan which has passed both Houses of Parliament. The exception to this is where a State Reserve is declared over an existing mining tenement.

State Reserves include land known as:

- State Reserve
- National Park
- Historic Site
- Nature Reserve
- Aboriginal Site

Where SR declared over existing tenement

There are a number of examples where a State Reserve has been declared over an existing mining tenement. In these cases the tenement holder retains a "private right" under the *National Parks and Wildlife Act 1970*, which allows for the continuance of such rights and privileges as were in existence before the Reserve was declared.

Examples are:

EL 45/86 King Island

An extension to the Lavinia Nature Reserve was declared over part of this tenement in 1988. The licence holder is entitled to continue exploration under the same terms and conditions as were in force prior to the declaration of the Nature Reserve extension. However, mining could only proceed if this activity was provided for in a management plan.

ML 69M/81 Lune River

Mining Lease 69M/81 covers 487 ha and includes Benders Quarry. Around 350 ha of the lease is now included in the South West National Park, and an area of 77 ha is now known as the Marble Hill Conservation Area. According to State legislation, the lessee retained a "private right" to continue operations on the lease under the *National Parks and Wildlife Act 1970*. However both the South West National Park and the Marble Hill Conservation Area also have World Heritage status, which gives the Federal Government some management responsibilities over these areas. In November 1992 the Federal Government exercised powers of the *World Heritage Properties Conservation Act 1975* and closed the quarry.

RL 8709, 8710, 8711 Douglas-Apsley

These retention licences pre-date the Douglas-Apsley National Park and are held for coal. The tenement holder retains the right to explore on these licences, and a procedure for the approval of exploration programmes has been included in the management plan for this area.

Game Reserve (GR)

These are exempt from the provisions of the *Mining Act 1929*.

Conservation Areas (CA)

These are automatically subject to the auspices of the *Mining Act 1929*, unless arrangements are made otherwise. For example, the Central Plateau Conservation Area (CPCA)

was declared over part of the Central Plateau Protected Area (CPPA) and the area of overlap is unavailable for exploration. The CPCA is included in the World Heritage Area (WHA).

In most cases exploration can proceed, under strict environmental guidelines. Proposed work programmes for work in conservation areas (and other areas deemed to be sensitive) are sent to the Mineral Exploration Working Group (MEWG) for comment.

Conservation Areas (CA) include land known as:

- Conservation Area
- Wildlife Sanctuary (WS): these are usually excluded from ELs by agreement with the applicant. The Portland WS has a management plan which specifically prohibits exploration.
- Mutton Bird Reserve: also usually excluded from EL applications by agreement with the applicant.

ABORIGINAL RELICS ACT 1976

Administered by: Parks and Wildlife Service

On-ground Manager: Parks and Wildlife Service

Land reserved under this Act as Protected Archaeological Sites is removed from the auspices of the *Mining Act 1929* and is not included in mining tenements.

CROWN LANDS ACT 1976

Administered by: Department of Environment & Land Management (formerly Department of Environment and Planning)

On-ground Manager: Parks and Wildlife Service

Land is reserved under this Act for a multitude of purposes; some categories are exempt from the *Mining Act* whilst others are not.

Public and municipal reserves declared under this Act are **exempt** from the *Mining Act, 1929* unless they are specifically 'brought back' under the auspices of the Act, either at the time of reservation or later on. For any of these reserves to be 'brought back' under the *Mining Act* the explorer will have to present a convincing case as to why the ground is required.

The Act is **administered** by the Department of Environment and Land Management but all on-ground management is done by the staff of the Parks and Wildlife Service. Land reserved under the Crown Lands Act and **EXCLUDED** from exploration licences is as follows:

- State Recreation Areas
- Coastal Reserves
- River Reserves
- Lakeside Reserves
- Some roadways (such as highways)
- Crown Reserves for conservation purposes, e.g. Mt Nelson Signal Station and Truganinni Reserve, etc.

- Crown Reserves such as cemeteries
- Crown Reserves for construction materials and water, (e.g. Crown ballast pits, quarry reserves, water reserves, etc.)
- Protected Area. Protected areas are exempt when first declared; if not brought back under the Act the land remains excluded from an EL.

In many areas strips of land along the margins of rivers and lakes and on coastlines have been reserved by the Crown, so as to retain access to the foreshore, beach, lake or river. On old charts these strips of land, commonly one chain (20.1 m) or one hundred feet (30.5 m) wide are shown as 'Crown Reservations'. These are subject to the auspices of the *Mining Act 1929*.

On modern maps some of these areas are shown as 'Coastal Reserves' and in some cases (e.g. Ocean Beach) signs have been erected stating 'Coastal Reserve', although the land does not, in all cases, have any formal reserve status. Reserves can only exist officially if gazetted or established under existing legislation or regulations; otherwise these are known as 'notary' reserves, and are included in land available for exploration.

Coastal reserves can be established by proclamation or by Crown Land Order under the *Crown Lands Act 1976* and also by S473A of the *Local Government Act 1962*, which requires land to be set aside for public use when subdivisions are created.

Formal public reserves created by these means are exempt from the provisions of the Mining Act for a depth of 15 metres. Where coastal areas are included in EL applications Industry Safety and Mines has an informal agreement with the Department of Environment and Land Management that access to these areas will be subject to that Department's approval. This is noted on licence documentation. In addition, where coastal land is being managed for conservation purposes (e.g. bird nesting sites, penguin habitats, etc.) but there is no formal reserve, parts may still be excluded from applications.

Land generally **INCLUDED** in Exploration Licences under the *Crown Lands Act 1976*:

- unallocated Crown Land;
- Protected Area (provided it has been brought back under the Act) e.g. the Arthur Pieman Protected Area, Waterhouse Protected Area, part of Central Plateau Protected Area not overlapped by Central Plateau Conservation Area.

PUBLIC LAND (ADMINISTRATION AND FORESTS) ACT 1991; FORESTRY ACT 1920

Administered by: Forestry Tasmania

On-ground Manager: Forestry Tasmania and the Parks and Wildlife Service for some areas of Deferred Forest and some RAPs

Most land managed by Forestry Tasmania is available for exploration.

State Forest

This is included in exploration licences. Most State Forest is Crown Land dedicated as State Forest, but Forestry Tasmania does purchase land and has this dedicated as State Forest. These are, in effect, private property blocks owned by Forestry Tasmania.

Timber Reserves

Used to be included in exploration licences but have been abolished, and are now ordinary State Forest.

Forest Reserves

These are set aside for conservation or recreational purposes and when declared are exempt from the Mining Act. If a case is made a Reserve may be brought back under the Act by agreement with Forestry Tasmania. At this point in time only the Teepookana and Mt Maurice Forest Reserves have been brought back under the Act; all others are excluded from exploration licences. The Mt Victoria Forest Reserve has a management plan which states that the area can be brought back under the Mining Act if required for exploration.

The *Public Land (Administration and Forests) Act 1991* introduced more categories:

Multiple Use Forest Land

This is ordinary State Forest, available for exploration. All the former unallocated Crown Land in these zones is now State Forest.

Deferred Forest Land

Some land has been placed on a Register of Deferred Forest. This does not involve any change in tenure. Some Deferred Forest is State Forest, some is unallocated Crown Land. All is available for exploration. Activities involving earthworks will be sent to the MEWG for comment.

RAPs (Recommended Areas for Protection)

These are areas of either State Forest or unallocated Crown Land chosen as representative areas of different forest communities. Some RAPs are within existing Conservation Areas. The remaining RAPs have been classed as either 'resolved' or 'unresolved'. 'Resolved' means Government agencies are agreed on a tenure which may, at some future time, be declared over the RAP. The agreed tenures will be Conservation Area, Forest Reserve or Forest Reserve subject to the *Mining Act 1929*.

A few very small RAPs will be declared State Reserves. Proposed activities involving ground disturbance in RAPs will be sent to the MEWG for comment. The purpose of the RAPs is to preserve representative portions of all forest types. Other activities are not automatically incompatible with this aim.

HEC ACT 1944

Administered by: Hydro-Electric Commission

On-ground Manager: Hydro-Electric Commission

Most land vested in the HEC is subject to the *Mining Act 1929*. However Industry Safety and Mines has had a long-standing arrangement with the HEC to exclude land

around dams, work sites and power lines from mining tenements. However, this does not mean exploration cannot proceed. The HEC will examine each proposal (for drilling, etc.) on a case-by-case basis and may permit exploration activities which will not affect dam structures, etc.

The remainder of HEC-vested land is included in mining tenements and ISM is the Agency responsible for giving out exploration approvals, with appropriate conditions. On HEC land one condition will be to keep the HEC fully informed of any activities.

MINING (STRATEGIC PROSPECTIVITY ZONES) ACT 1992

Administered by: Industry Safety and Mines

Under this act the status of large parcels of Crown Land within designated Strategic Prospectivity Zones may not be changed without the approval of both houses of Parliament. Should a change in land status made by the State have the effect of revoking a mining lease or an exploration licence, the tenement holder is entitled to compensation. The State is, however, not responsible for actions of the Federal Government which may result in changes in land status, such as the nomination of World Heritage Areas.

The status of parcels of land less than 500 ha in area can be changed with the agreement of Industry Safety and Mines. Some land, such as residential land around towns, is exempt from this act.

Changes in status of land can also be made in extreme circumstances, e.g. if a species of flora or fauna was to become rare, vulnerable or endangered as a result of mining activity, or where an area having cultural or natural heritage value could suffer substantial effects as a result of mining operations. In these cases the Crown may, after a recommendation from the Public Land Use Commission and some Ministers, change the status of that piece of land, and compensation is payable for this action.

NATIONAL ESTATE

Land can be listed on the Register of the National Estate by the Australian Heritage Commission, using the *Australian Heritage Commission Act 1975*. The purpose of the Register is to have an inventory of places or areas in Australia which are of significant heritage value.

Effects of Registration

The Register has a direct protective role **only** in relation to actions proposed by the **Commonwealth** which might adversely affect the National Estate.

There are no direct legal constraints on owners of private property, or on State or local governments, caused by the entry of that property in the Register of the National Estate. Thus the Commission has no power to direct private owners or State or local governments with respect to their actions that might affect a place in the Register.

The Act requires that Commonwealth Ministers and Commonwealth Authorities must "ensure that their own actions and those of their departments and authorities do not adversely affect the national estate values of places in the

Register unless there are no feasible and prudent alternatives and, if there are no such alternatives, unless all reasonable measures are taken to minimise the effect. The Minister's action to achieve these ends must be consistent with any relevant laws".

Effect on Exploration

Industry Safety and Mines keeps an up-to-date record of all National Estate nominations, interim listings and registered entries. Overlap with any interim listings or registered entries is recorded on each EL application. In approving exploration works ISM is mindful of the reasons given for the listing, and conditions placed on work may reflect the need for care in/on a particular site. The fact that a place is listed does not in any way delay the assessment of exploration proposals.

WORLD HERITAGE

Land classed as 'World Heritage' is done so by the Commonwealth Government using the *World Heritage Properties Conservation Act 1975*. This is not a land use, as such. Most of the land classed as World Heritage in Tasmania is also National Park, and so is not open for exploration.

The World Heritage area also covers three Forest Reserves and three Conservation Areas.

The Forest Reserves, which also have the dual status of Conservation Area, are:

- Liffey Forest Reserve
- Drys Bluff Forest Reserve
- Meander Forest Reserve

These Forest Reserves have Management Plans which confirm that these areas are not available for exploration and mining and will not be brought back under the Mining Act.

The three Conservation areas are:

- *Marble Hill Conservation Area:* over Bender's Limestone Quarry, Lune River and entirely covered by ML 69M/81.
- *Adamsfield Conservation area:* Adamsfield, in which exploration is allowed. Exploration works are assessed by the Parks and Wildlife Service and Industry Safety and Mines, and if the planned work is extensive the proposal will be referred by Parks and Wildlife to the WHA Standing Committee and possibly to the WHA Ministerial Council.
- *Central Plateau Conservation Area:* this covers part of the Central Plateau Protected Area, and is not available for exploration.

The Commonwealth Government has a significant input into the management of the WHA and provides funds for this purpose. Any area can, theoretically, be proclaimed a 'property' to which Section 9 of the *World Heritage Properties Conservation Act 1975* applies. The application of 'Section 9' would require that "except with the consent in writing of the (Federal) Minister it is unlawful ... to carry out operations for, or for exploratory drilling in connection with the recovery of minerals on any property to which this section applies". If this happens, the Commonwealth are not legally obliged to compensate the explorer/developer.

Mineral Exploration Code of Practice — Exploration guidelines

The following pages outline the general standard expected of exploration works in Tasmania.

Cutting and use of grid lines

ESTABLISHING CUT LINES

- Cut lines or walking tracks must not exceed one metre in width.
- Access to cut lines must be discreet, to reduce the possibility of subsequent misuse by unauthorised users.
- Cut lines are to be established using hand tools such as macheté, fern hook, axe and chainsaw only.

CUTTING VEGETATION

- For safety reasons, vegetation should be cut close to ground level to avoid dangerous 'spikes' of stumps protruding. Overhanging vegetation should be trimmed to reduce the hazard of protruding branches.
- Unless imperative, no live saplings of any species over 15 cm diameter will be felled.
- Track cutters should recognise and avoid cutting the following native species:

Common Name	Scientific Name
King Billy Pine	<i>Athrotaxis selaginoides</i>
Huon Pine	<i>Lagarostrobos franklinii</i>
Celery Top Pine	<i>Phyllocladus aspleniifolius</i>
Cheshunt Pine ♣	<i>Diselma archeri</i>
Creeping Pine ♣	<i>Microcachrys tetragona</i>
Deciduous Beech ♣	<i>Nothofagus gunnii</i>
Pandani	<i>Richea pandanifolia</i>

♣ These species are usually confined to alpine areas

- Where plants such as manferns (*Dicksonia antarctica*, *Cyathea spp.*) are encountered, individual specimens are not to be decapitated. Fronds may be shaved off one side of the plant to allow access next to the plant.

USE OF PEGS AND TAPE

- Biodegradable tape is preferable to the ordinary plastic type. This tape will last at least two years, but will eventually disintegrate.
- Use only small lengths of tape. 'Streamer' type markers using several metres of tape are not necessary.
- Conspicuous markers such as pegs and tape should be removed wherever possible on completion of the programme, especially from the beginning of grid lines.

- In some sensitive areas — such as alpine areas — cutting should be kept to a minimum. Grids should be pegged and flagged with tape wherever possible. In these areas a special effort should be made to recover pegs and tape on completion of the programme.

USE OF GRID

- Whilst cutting and later using grid, all introduced debris (bottles, cans, paper) is to be removed. **DO NOT LITTER.**
- If changing oil in small, hand carried machinery, waste oil is to be collected and taken to an appropriate disposal area. Used oil must not be dumped in bush while cutting grid.

FIRE PREVENTION

- On all work sites where chainsaws, power augers, and other petrol-driven machinery are used there must be, within sensible reach, a serviceable knapsack filled with not less than 10 litres of water, or a powder-type extinguisher of not less than one kilogram capacity, during a Fire Permit Period.
- In addition to Fire Permit Periods, usually declared by the Tasmania Fire Service over the summer months (when anyone wishing to have a fire outdoors must obtain a permit), there are sometimes days declared as "Total Fire Ban" days. The ban on such days lasts for 24 hours, from midnight to midnight. On occasions such bans may be declared on several subsequent days, depending on weather conditions. On days of Total Fire Ban forest workers are not permitted to use machinery of any kind in State Forest — including chainsaws — due to the risk of starting fires by friction by dragging logs, or from sparks off engines and motors.

Grid cutters should not use chainsaws in the bush on such days. Work should be confined to activities which do not require the use of machinery.

Typically there are only a few days of Total Fire Ban each summer, but should there be so many days of declared Total Fire Ban in any one summer that exploration programmes are seriously disrupted, the explorer should report this in the Annual Report, and if necessary request an extension of time for the delayed fieldwork.



- When using a portable generator, such as for UTEM surveys, be sure to keep the exhaust area clear of leaves and twigs. On the completion of the survey, remove all wires from the grid.

FORESTRY
COMMISSION,
TASMANIA

**FOREST TREE
SERIES**

KING BILLY PINE

(*Athrotaxis selaginoides*)



King Billy pine is a majestic and ageless tree growing in the western, south-west and central plateau rainforests of Tasmania, at medium to high altitudes. It is no longer logged, except for salvage. The timber is easily worked and valued for its durability and light weight.

FORESTRY
COMMISSION,
TASMANIA

FOREST TREE SERIES

HUON PINE (*Lagarostrobos franklinii*)




Art work by Jo Eberhard



This most famous Tasmanian timber has been used for furniture and boatbuilding since the 1820s. A mellow, fine textured timber with a characteristic fragrance, it attains phenomenal age, some trees dating from before the birth of Christ.


**FORESTRY
COMMISSION,
TASMANIA**
**FOREST TREE
SERIES**

CELERY TOP PINE



Mature tree

F. DUNCAN 1985




Foliage



Seedling

Celery-top pine is one of the best known of Tasmania's native coniferous species. The tree, which occurs only in Tasmania, is common in the west of the State and also occurs in isolated patches in the east. It can be easily identified by its distinctive celery-like foliage. The timber is valued for its durability, hard wearing surface, dimensional stability and attractive fine-grained appearance.




RICHEA PANDANIFOLIA
Pandani

This palm-like tree is common in rainforest, most commonly in the understorey. It also extends into the alpine zone, where it forms a squat shrub.



DISELMA ARCHERI
Cheshunt Pine

Throughout most of its range in the alpine and subalpine zones of Tasmania *Diselma Archeri* dominates heath. In the wettest parts of the State the species dominates high altitude rainforest. Cheshunt Pine has a leaf arrangement similar to that of creeping pine (*Microcachrys tetragona*). Fortunately Creeping Pine lives up to its name.



NOTHOFAGUS GUNNII
Tanglefoot, Deciduous Beech

This highly fire-susceptible endemic species is found in subalpine rainforest and alpine heath on the wettest mountains in the State. It rarely exceeds 8 m in height.

These diagrams and descriptions are reproduced with permission from the authors of the book "Native trees of Tasmania" by J. B. Kirkpatrick and Sue Backhouse

Tracks

The most visible evidence of exploration activities would have to be the building of tracks, which if put in the wrong place or not constructed properly can be real eyesores. Properly made and carefully sited tracks will remain visually obscure and environmentally acceptable, while still allowing the explorer access. The single most important feature of track construction is good planning. A well planned road or track will cost less than one which is badly placed and requires frequent maintenance. When planning a track, the maintenance and rehabilitation requirements must also be considered, and included in the cost estimates.

COST-BENEFIT ANALYSIS

Helicopters

Track construction and rehabilitation is very expensive, as well as being environmentally disturbing. The explorer would be wise to always do a brief cost-benefit analysis to compare the costs of helicopter access versus ground access. The results are sometimes quite surprising — especially where access is through steep, heavily-timbered country, or where a long access track is being contemplated.

Industry Safety and Mines encourages companies to use helicopters for access wherever this is practicable. If a very long track, or one in difficult terrain, is proposed, the Department will ask if a cost-benefit analysis has been done, and what the results were, before consideration will be given to the proposed earthworks.

Four-wheel drive ag (quad) bikes

Consideration could be given to the possibility of using four-wheel drive ag (quad) bikes in some situations. These can carry fair-sized loads of gear, and have the advantage of requiring only a well-made walking track to drive on. Operators should be trained in the use of these bikes, and in the safety requirements involved in using bikes on rough bush tracks.

PLANNING

The first step in planning access is to ascertain whether or not the track is really essential. What are the alternatives?

PUBLIC AND OTHER PRE-EXISTING ROADS

- Always use an existing road or track in preference to constructing a new one. This will prevent duplication, avoid unnecessary environmental interference, and reduce costs to those of maintenance of the track.
- Establish the ownership and/or the controlling authority of roads before use, and where appropriate obtain permission (e.g. from HEC, Forestry Tasmania or from private landholder) before use.
- Respect existing roads/tracks; do not aggravate deterioration by use of excessive speed, oversize or overloaded vehicles, or use in extreme weather conditions.

- Do not use tracked vehicles on unsuitable surfaces (such as bitumen).

CONSTRUCTING TRACKS

If no suitable access exists, and the planner determines that a track must be constructed (as opposed to using helicopters for access), then the following points should be considered:

- The volume of traffic, and type of traffic to use the track. How often will the track be used? Once or twice a day? Once a month? Will a drill rig be sledded in? Will heavy, wheeled trucks need access?
- For how long is the access required? For the duration of one drill hole? Many drill holes? For several field seasons?
- Will access be required only in summer? Or is some winter work planned?
- How will future developments affect the track use? Is there any likelihood that at some time in the future the volume of traffic or type of equipment to use the track will change? Will you drill another ten holes if the first one is any good? Bear in mind possible future events which may cause the track to be upgraded or extended.

Once the planner has determined the standard to which the track must be constructed, some estimate should be made of costs, and consideration given to funding. Track building is very expensive, and there are many 'hidden' costs not immediately obvious. A costing must include:

- planning time
- allowance for proper drainage
- cost of pipes and culverts
- cost of maintenance
- cost of rehabilitation

The costs involved in track construction vary enormously according to the site. Tracks in near level, lightly timbered country may cost only \$500–\$600/km; a comparable track in heavily timbered country with high rainfall and many creek crossings could cost \$10,000/km or more.

Ask people who have had local experience in track construction. District Foresters will usually be able to give a rough guide as to the cost of roads in their own district.

CLASS OF TRACK

Forestry Tasmania has designed a classification system for the construction of permanent roads, and this is reproduced below. Most exploration tracks will never be subject to the heavy use many forestry roads experience, and the 'most permanent' type of exploration track ever required is not likely to be greater than a Class 4 road. Frequently, small temporary tracks of a few hundred metres length and required for limited use — drilling one hole for example — may not need to be of this standard.


Road Design — Basic Approach

A guide to road design for permanent roads based on average tonnes per week carted
(Forestry Tasmania)

Characteristics	Road Class			
	Class 1 (Main)	Class 2 (Semi-main)	Class 3 (Spur)	Class 4 (Track)
Function	Primary road in large network (two lane)	Significant feed road (slower two lane)	Terminal road (fast or slow single lane)	Special purpose access road, single lane — low cost
Log Traffic Volume	2500 t/week	1000–2500 t/week	<1000 t/week	very low
Pavement Type	Heavy duty, all weather	Heavy duty, all weather	Can be all or summer only	Usually not metalled
Pavement Width	5.5–6.0 m	5.5 m	3.7–4.0 m	3.7 m
Shoulder Width	0.6–1.0 m	0.6 m	0.5–1.0 m	0.6 m
Desired Maximum Gradients	+5, -8%	+8, -10%	+12, -15%	+15, -15%

LOCATION


- Possible routes for the track or road should be found, firstly using available maps and air photos, then by field inspection. Do not hesitate to investigate the various possibilities or alternative sitings of different parts of the proposed track. Walk the whole length of the proposed route, not just the beginning.
- An assessment should be made of the potential visible impact of different routes, not only from roadways but from local residential sites and vantage points in the neighbourhood.
- Colour contrasts between soil and the underlying material can produce a high visual impact, which is not evident when the soil and underlying material are of the same colour. This visual impact must be taken into account in the planning.
- Learn to recognise and avoid rare or valued tree species.
- Where removal of trees is unavoidable consider routes which minimise tree clearing. Try and mark both sides of the track by tying a 'corridor' of tapes along the proposed route. This will greatly assist the earthmoving contractors in putting the track in neatly.



- To assist in the location of the track, first establish **control points** — such as creek crossings and saddles — then


decide on the required gradient between the control points.

- Avoid poor or difficult ground such as rock outcrops, soaks and swamps. Generally the best track locations will be found on ridge tops or on bottom slopes just above the valley floor. Keep off valley floors, as drainage is generally a problem in these locations. Wet areas, which may not be wet at the time of inspection, can be recognised by the vegetation — tea tree, Ghania (cutting grass) and button grass, and so on.
- Minimise the number of stream crossings.
- Fit the track to the topography so that the earthworks disturbance will be kept to a minimum.
- Try and position tracks along the contour, and avoid sudden changes in gradient. Steep sections of tracks are prone to severe erosion and generally incur high maintenance costs, and must have drainage grips or cross drains put in during construction. On the other hand, also avoid building dead-level tracks, as water will pool on these flat sections and not run off. Where topography permits, locate roads on old benches (provided they are not backslopes of old landslides), ridge tops and flatter slopes.




- Ideally tracks should be built to a grade not less than 1% (so water will run off) but not more than 5% — especially if constructed in erodable soils or clayey areas where traction may be a problem in the wet.
- When developing a new track off an existing roadway ensure the junction is discreet, but is also safe. Traffic must have a clear view at junctions. Junctions located just over the brow of a hill, or round a sharp bend on a main road, should be avoided.
- Where possible, the angle between track and road should be large and the track should include a 'dog leg' in the bush, close to the road, to reduce visibility.
- Tracks constructed parallel to a major watercourse should be some distance from the watercourse; the general rule being the larger the watercourse, the larger the margin of undisturbed vegetation to be left on the banks. All watercourses in Tasmania are protected by streamside reserves, as defined by the Forestry Tasmania. These are:

Watercourse Type	Protection Zone (per bank)	Total Streamside Reserve
Class 1. Rivers and lakes (as named on DELM 1:100 000 topographic series)	40 m	80 m
Class 2. Creeks and streams (carrying permanent running water; catchment exceeds 100 ha)	30 m	60 m
Class 3. Permanent watercourses (catchment 50–100 ha)	20 m	40 m
Class 4. Semi-permanent or ephemeral streams carrying water intermittently	10 m	20 m




- These streamside reserves are recognised as necessary for the protection of water quality. Heavy machinery should not enter these streamside reserves except to cross the streams at defined crossing points.
- Interference with the natural drainage should be kept to a minimum.
- Stream crossings should be at right angles to the stream.




CONSTRUCTION

- As a general rule, precut all fallen logs and saplings greater than 15 cm in diameter before pushing aside with dozer or excavator. Any commercial timber should be set aside for salvage.
- On some occasions, pushing over trees in line with the proposed track may be preferable to cutting. Revegetation on roadsides, where the fallen log, with roots partly intact, forms the roadside verge, is frequently assisted by re-sprouting from the tree trunk. The reason for pre-cutting is to avoid damage to peripheral vegetation from uncontrolled falling of large trees. However, on occasions, careful felling of trees can assist in stabilising the road verge. This is mostly used in the construction of narrow tracks on moderate slopes.




- Remove topsoil and vegetation and store in a long windrow, no higher than 0.5 m alongside track. Make sure topsoil stockpile is out of the way of traffic. Ensure that drains are constructed through the stockpiled soil to allow runoff to escape. If this is not done, the valuable topsoil may be eroded away!
- If a second cut is made with a dozer and subsoil is removed to make a firm road base, store subsoil in a windrow alongside the track, but **do not** pile this on top of the topsoil.

- Do not make the track any wider than necessary. Choose the smallest 'dozer suitable for the job to restrict the width, or use an excavator.



- Tracks made with excavators are frequently more neatly done and require less rehabilitation work, although there are situations where a bulldozer is the more appropriate machine to use. Use excavators wherever possible, in conjunction with a bulldozer if necessary.
- On steep slopes (>30°) some 'benching' will probably be necessary. Use fill from cuts wisely — do **not** push over bank and waste. Compact fill as much as possible to minimise water penetration and to prevent fill washing away.



- When a demand for road building material is anticipated, locate a few good source sites, and develop these systematically. Do not poach fill and surfacing from along the road verges.

- Material can also be obtained by slightly widening the track, and on some occasions this may be preferable to opening up a borrow pit next to the track.
- Design road material pits to be compact, and inconspicuous from the roadway and from neighbouring vantage points, by judicious siting, utilising local landforms, leaving natural screens of vegetation, constructing mounds capped with top soil, and revegetating.
- Limit vegetation clearance to the extraction site, and remove trees with the same reservations as for the track.
- Do not needlessly remove vegetation from either side of roadway.
- Ensure service areas are limited in size and in numbers, and where possible ensure construction service areas, fuel, equipment, vehicle depots and campsites are confined to the future road alignment.
- Do not use creek floors as tracks.

DRAINAGE

- Install proper drainage systems on all tracks. This one point cannot be emphasised enough. A few dollars spent on adequate drainage in the beginning will save much time and money later on in repairing water damage.
- All tracks require cross drains or grips at frequent intervals. On moderately steep slopes, grips every 30 m or even closer will be required. Cross drains function most effectively with a table drain built to channel water into the cross drain. Of all the faults seen in poorly constructed tracks, the lack of cross drains is the most common.
- While the actual spacing of cross drains and table drains is largely determined on a site-specific basis, the following table (adapted from the *Forest Practices Code*, Forestry Tasmania, Hobart) is a guide for drain spacings on a track which would be required for more than one season.

ERODIBILITY FACTOR			
Grade of Track	Low-Medium	High	Very High
1-5%	150 m	120 m	70 m
6-10%	120 m	90 m	40 m
11-15%	95 m	70 m	30 m
16-20%	50 m	35 m	30

The erodibility factor is governed by the soil type and/or parent rock over which the track is constructed. These are:


LOW: dolerite or basalt rock/soils.

MEDIUM: Mathinna Beds and equivalents rock/soils; sandstone, mudstone; non-limestone soils overlying karst.


HIGH: Quartzite; coarse sandstone, thin residual soils derived from limestone and granite in wetter areas.

VERY HIGH: Granite rock/soil in dry areas; fine sandy soils.

- Cross drains are constructed at approximately right angles to the water flow across the track. They should be dish-shaped, about 0.6 m wide and 0.3 m deep. These drains are often damaged by the regular passage of traffic and should be kept in a good state of repair. The drain should be at an angle to best intercept water, and should be on a slight grade (1–3%) to pass the water from one side of the track to the other.




- Table drains should be dish-shaped, at least 300 mm (0.3 m) deep and at least 600 mm (0.6 m) wide. They should be dug on the inside edge (i.e. on the uphill side) of a track and should connect to a properly constructed cross drain.
- Table drains and cross drains should not be “square in cross section” as can easily happen when drains are constructed with a backhoe or excavator. The preferred shape is that of a shallow dish, as this is less easily eroded.




- “Mounds” can also be used to divert water off a track. These are made during track construction by piling up any



available material — gravel, crushed rock, even soil into a long ‘hump’ across the track — rather like a ‘speed hump’ used to force cars to slow down. The hump works by directing water flowing down the track off to one side, into a table drain. These mounds must be carefully maintained. The material to make the mound is obtained by making a long spoon-shaped scrape 1 to 2 m in front of the mound during construction of the track.




- The dimensions of cross drains and table drains must be adequate to cope with the volume of runoff. In easily eroded soils water velocity in these drains should not exceed 0.5 m/sec. In more resistant soils, the velocity should not exceed 1.0 m/sec. When constructing drains try and stick to the same gradients as used in track construction — between 1 and 5% slope wherever possible.
- Where drains cannot cope with the volume of water, they can be lined with rip rap (broken rock), half pipes or concrete interlocking channels.



- Where excessive silt loads are anticipated, or where water quality is an issue, large cross drains and culverts should be constructed in conjunction with a sediment trap — a pond into which the drainage water can collect, and sediment can settle out before flowing on, following the natural drainage channels.




- Culverts and cross drains should be located where the run-off either filters through undisturbed forest soil or into natural drainage channels. If this is not possible the discharge should be directed onto solid ground, not fill.
- Remember to check drains and culverts frequently and **UNBLOCK** where necessary. A blocked culvert can cause massive washouts.
- Culvert pipes should be laid on a very slight grade, not too flat or too steep. This is to minimise silting up of the pipes, which will occur if the pipes are too flat, and to control 'scouring' of the culvert outlet, which will happen if the water flow is concentrated by a pipe. Rip rap (broken rock) should be placed in the discharge area to prevent erosion.
- **DO NOT** fill gully or creek up with rock, and put in pipe near the top and cover with a few centimetres of soil. Pipe must be laid on a solid base. Often the most convenient spot is on the side of a gully. The most important factor in choosing where the pipe is to go is to ensure that the pipes will not move.
- Culvert pipes must be laid straight, on a good foundation, to prevent movement of pipes after laying. Where pipes are joined, care must be taken to have them laid straight. Rubber ring joints or external bands can be used where movement is anticipated.
- The minimum recommended cover over pipes is 0.6 m.



CREEK CROSSINGS

- Some creeks may be crossed by fording. This is generally only suitable when crossings are infrequent. The ford may be made more permanent by concreting the width of the roadway across the creek. This can only be done where creeks have a low summer flow, and where few crossings are envisaged.



- Creek crossings will usually require a culvert to allow the water to run under the road. Small crossings can be made by using a 'nest' of logs, where logs are laid in the creek, parallel to each other, so that the water can flow between the logs. Gravel and fill are usually placed over the collection of logs to complete the road surface.
- Larger creeks will require something more substantial, such as a piped culvert or a log culvert. The size of the pipe will depend on the size of the creek to be crossed. Anticipate winter water flows and install culvert pipes which will cope with the maximum expected water flow. Evaluate the size of the catchment. DO NOT put in a pipe only just capable of taking the summer flow — these will almost certainly wash out.
- Log culverts are made by placing two 'abutment' logs on each bank of the creek, parallel with the creek direction, then putting logs (stringers) across the creek, with their ends resting on the abutment logs. The logs are then covered with gravel or soil.


These are much more substantial structures than 'nests' of logs or piped culverts, and are only required in exploration where rivers have to be crossed.

- During the last 50 metres before a road crosses a Class 1, 2 or 3 watercourse (see page 34), road drainage will be diverted into the surrounding vegetation or sediment traps, and not allowed to continue to the stream unchecked. Where necessary a culvert should be installed to pass drainage from the top side of the road to the lower side, and then diverted into the surrounding vegetation.

- If access is only required for a summer season or so, a temporary bridge which can be lifted into place and taken away again after use could be considered.
- On major creek crossings or minor creeks important for use by spawning fish, use a log culvert or a temporary bridge.

SUMMARY

- Major creek crossings are usually made by either fording or construction of a log bridge. In these cases, steep approaches to the creek crossing must be avoided. Rocks may be placed in the creek bed to form a firm bottom to a ford.
- Direct road drainage off road into vegetation, not into the creek.
- Minimise disturbance in the creek bed.
- Select logs (stringers) strong enough to do the job.



DIFFICULT AREAS

Some terrains are much more prone to scarring than others. Constructing tracks in dunes, alpine areas and buttongrass plains should be avoided if practicable. Tracks in buttongrass country are frequently poorly drained because of thick peat and a lack of gradient. Skirt buttongrass plains wherever possible. When obliged to cross them do so at their narrowest point. The foundation of buttongrass plains is frequently quartz-based gravel, which produces a conspicuous colour contrast with the vegetation when exposed.

Dunes are prone to erosion by wind; tracks which are well built can soon become the domain of unauthorised 4WD and trail bike users, whose abuse of some areas is only too evident. Stabilisation of sand dunes is often dependent upon their precise shape and a fragile vegetation cover. Minor cuttings or limited alteration of dune form can provoke blow-outs in time. When working in dune country, the major requirement is to retain the full vegetation cover. Tracks should not be made unless absolutely essential; grids should be pegged, not cut, wherever possible.

Roading should be avoided in alpine country, in which tracks are difficult to construct and near impossible to restore. Helicopter-assisted drilling should be used in alpine areas wherever possible.

USE OF TRACKS

- Try wherever possible to confine the use of temporary tracks to the summer months.
- Carry a spade in your vehicle and unblock cross drains as required. Keeping water off the surface of tracks will greatly reduce the expenditure required for maintenance.
- Do not wait until tracks fail before doing any maintenance work. Cover patches which may become boggy with tea tree or geotextiles covered with gravel.
- Plan the daily and weekly workloads / crew changes / gear shifts so that these are accomplished with the fewest number of journeys. Trips are frequently unnecessarily duplicated. Plan your time well, choose a suitable vehicle,

and this will minimise both expense and environmental impact on the track.

- Tracks which are required for a number of years should be built to withstand some flooding. Traditional road building incorporates a 'flood interval' component in the design, taking into account that there will be a 'bigger than annual' flood every ten years, a fairly big flood every fifty years, and a huge flood every hundred years. This planning is far in excess of what is required for a humble exploration track but you should consider that your track may be subject to some flooding and plan accordingly.

RE-OPENING OF OLD TRACKS

- Overhanging vegetation should be cut, not pushed out of the way with either excavator or 'dozer.
- Logs across the track must be cut, not simply pushed out of the way.
- Re-open old drainage and be sure to install additional drainage wherever necessary.



Utilise existing access wherever possible.



Any suitable methods available which do not require a track to be constructed?



Actual construction of a track may not always be necessary.

Photographic summary of main points — see text for more detailed information



*Plan the route thoughtfully —
investigate thoroughly.*



Consider the visual impact.



Avoid poor or difficult ground.

Photographic summary of main points — see text for more detailed information



Pre-flag the corridor of the planned route.




Thoroughly clean earthmoving machinery.



Supervise the work.

Photographic summary of main points — see text for more detailed information



Pre-cut any trees fallen across the track route.



Stockpile vegetation and topsoil separate from subsoils — keep peripheral disturbance to a minimum.



Avoid steep gradients and disturbing larger trees.

Photographic summary of main points — see text for more detailed information



Avoid excessive earthworks.



Install adequate drainage and watercourse crossings.



Provide ongoing drainage maintenance.

Photographic summary of main points — see text for more detailed information

Rehabilitation of tracks

PREPARATION OF GROUND

- The use of an excavator with a rock, not a mud bucket, is preferred to a bulldozer in most situations, as an excavator can usually do a neater job.
- Some ripping may be required if the track has been heavily used, or is badly rutted in spots. However most exploration tracks should not need ripping. (Ripping is not needed prior to the replacement of peaty soils).
- Should ripping be required, remember to always:
 - Rip along the contour;
 - Spacing of rip lines should normally be approximately equal to ripping depth;
 - Do not rip when soil conditions are too wet to allow the soil to shatter;
 - A 'winged' ripper type may be more effective in moist soil conditions;
 - If ripping brings large amounts of rock to the surface, discontinue.
- Whilst ripping is commonly done with a bulldozer, excavators are also capable of ripping.
- Pull out culverts (pipes, logs etc.) and re-establish natural drainage pathways.
- Using an excavator replace stockpiled topsoil over the track (after ripping if this was needed) to a depth of 0.3–0.4 m.

TIMING OF WORK

Successful rehabilitation is dependent on the works being done at the correct time of year. Earthworks should be done when the soil is dry enough to move — usually between November and March. Under no circumstances should earthworks be attempted when the soil is wet and waterlogged.

Seeding and fertilising should be done after the replaced soil has been softened by rains. Autumn is the ideal time to seed and fertilise replaced soils (i.e. February to April).

Peat can be replaced at any time.

ESTABLISHING A VEGETATION COVER

- If topsoil has been stockpiled for more than three months consideration should be given to using seeds and fertiliser to encourage vegetation regrowth.
- Seeds collected locally should be used in preference to seeds from elsewhere.
- A suitable fertiliser in most situations is the off-the-shelf 8:4:10, which should usually be spread at the rate of 250 kg/ha. At this rate 1 kg will cover 40 m².
- Other fertilisers may also be suitable in some situations, such as the organic fertiliser OR-90, which is made from waste bark and orange roughly fish waste. The N:K:P ratio is 1.6:0.9:0.2 with 0.3 Mg, and as a fertiliser OR-90 can be spread at a rate of 750 kg/ha. At this rate 3 kg will cover 40m².
- The timing of rehabilitation is important; such work is best done in spring or autumn. Whilst earthworks can be done in summer if necessary, seeding and fertilising should be done the following spring or autumn. Rehabilitation should not be attempted in winter.
- Refer to the chapter on **Rehabilitation and Revegetation** for further details.

OLD TRACKS

- Where tracks are quite old, and there is little soil to be respread, the track can be ripped, and if cut into the side of a hill, the sharp edge can be recontoured. Seeding and fertilising will assist in establishing a vegetation cover.

COSTS OF TRACK REHABILITATION

The actual cost of rehabilitation is dependent on the condition of the site. However, as a very approximate guide, the following figures can be used to give a rough estimate of expected costs:

Assumptions (1995 figures)





- Topsoil stockpiled next to track.
- Earthworks done by 22 tonne excavator, cost \$75 per hour (plus transport to site).
- Excavator operator can restore one kilometre of track every 6 hours; total width of track disturbance 4 metres.
- Only 2 hours/km needed to install drainage.
- If track is compacted, ripping will be required, to a depth of 0.3–0.4 metres.
- D7 bulldozer will rip 1 km in 2 hours, cost of \$90 per hour (plus transport to site).
- Track fertilised with 8:4:10 mix at rate of 100 kg/km of track, or organic fertiliser such as OR-90 at a rate of 300 kg/km of track.

Costs per kilometre of track





Drainage	2 hours of excavator time at \$75/hour	\$150
Soil replacement	6 hours of excavator time at \$75/hour	\$450
Ripping	2 hours of dozer time at \$90/hour	\$180
Fertilising		\$30
Total cost	With ripping	\$810/km
	Without ripping	\$630/km


- To this must be added the cost of the machinery transport to the site, and the planning and supervision time required of the field staff.

TRACK CONSTRUCTION



TRACK REHABILITATION





Thoroughly clean down earthmoving machinery. Where practicable undertake earthworks during drier times of the year.



Rip compacted areas, pull out culverts and re-establish natural drainage patterns.



Replace stockpiled subsoils, followed by topsoil and vegetation.

Photographic summary of main points — see text for more detailed information



Recontour the site, returning to natural profile.



Leave surface irregular, construct spur drains on sloping sites.



Spread fertiliser over site if required.

Photographic summary of main points — see text for more detailed information



Vegetation cover may be restored quickly by using a tea-tree slash cover.



Locally collected seed bulked with sawdust can be applied as another method of revegetation.



On some sites planted seedlings may be appropriate. Follow-up inspection should be undertaken to ensure that the work has been successful.

Photographic summary of main points — see text for more detailed information

Drill Pads: Environmental considerations

- Frequently a small clearing must be made at the site at which a hole is to be drilled, to enable the drilling rig to be manoeuvred into place, and to provide a safe working area around the drilling equipment.
- The drill pad must be large enough to accommodate the drilling rig, compressor, pumps, drilling rods and rack, and often a small shelter for the drillers. Often a small sump must be dug to collect the muddy water produced during drilling. Whilst the drill pad must be of safe working size, do not make the pad any larger than necessary.
- As a general rule, try and locate drill sites in areas which require little or no clearing. When drilling on a grid pattern, for example, the planned location of one hole can be moved without greatly affecting the overall programme. However, if a specific target has been chosen, then the location of the drill site is more limited, and is largely predetermined by the position of the target. If there are no clear spots near the target zone which is to be drilled, then clearing is inevitable.
- Try to avoid locating a drill site directly beneath large, dead trees to avoid the danger of falling limbs. Should this not be possible, the work site must be made safe by cutting dangerous limbs or felling the whole tree.
- When an area must be cleared to make room for a drill pad, there are a number of points to remember which will make rehabilitation easier. Ask yourself how long the site is to be used and what sort of pad will be required. In dry country, tea-tree scrub and the like, removal of the vegetation cover (leaving rootstock in the ground) may suffice to give you a clear working area. The type of rig is also a consideration. Air tracks and small trailer-mounted rigs may be able to manage with just the vegetation removed, although in wetter areas, or where large heavy rigs are needed, a drill pad proper must be constructed.
- Upon completion of a drill hole most of the drill pad can be rehabilitated at the time the rig is moved, leaving vehicle access to the drill collar for later down-hole logging. This minimises the time for which the soil is stockpiled and saves on rehabilitation costs for an excavator at some later date.

CONSTRUCTION

- Pre-cut any timber greater than 150 mm in diameter in the area to be cleared.
- Earthworks, if any are needed, should be done with an excavator.
- Push topsoil and vegetation to one side of the drill pad area. If the drill pad is to remain in place for a long time, and the pad is on a slope, provide drainage along the top side of the pad (the same as for a costean) so that the drill pad and topsoil do not wash away. On a slope, topsoil should be stored on the uphill side of the drill pad.
- Remember that the drill will need a firm base on which to drill. If the ground is not hard enough, construct a small pad with gravel or logs. The base must be firm to prevent the drill moving (by sinking of one of the legs etc.) during drilling.

USE OF A DRILL SITE

- When drilling, place oil absorbent matting or hessian under/around the rig to catch any grease or oil. If the oil in the drill rig is changed on site, take the used oil away for proper disposal. Do not pour oil on to the ground near the drill rig.
- Should hessian or other matting not be available, then any spots of oily soil under or near the rig should be taken away for proper disposal on completion of drilling. We are talking here of a few buckets of earth, no more. If hessian is used no oil should be spilt on to the ground at all.
- Care should be taken when refuelling, replacing hydraulic oils etc., not to spill any of the contents. Fuel pumps, pouring spouts and funnels should always be used.
- Remove all rubbish and equipment from the drill site on completion of work. Provide rubbish drums for drillers.
- Remove all strawbales and residue if used.
- Cap or cover the drill hole. Do not leave an open hole in the ground.
- Drill holes making water should be plugged and sealed off following the completion of any down-hole geophysics.
- The site should be monitored periodically and any invasion of weed species eradicated.

WATER PUMPS

Water pumps should be placed on oil-absorbent material and regularly checked for oil and fuel leaks because of their close proximity to water courses.

SUMPS

Coring a 1000 m deep NQ drill hole will produce 2.5 m³ of rock dust and sediment. Adequate sumps should be used adjacent to all drilling sites in order to minimise the quantity and optimise the quality of water leaving the site, and to trap the drilling sediment.

- Drill pads should be designed with the sump on the downhill side. Drains should be dug to direct any accidental spills into the sump.
- Avoid having muddy water from the drill site directly entering any nearby watercourse by directing water through both straw bales and absorbent matting. Hay should not be used as it contains seeds which may then be introduced as weeds into the exploration area. Straw does not (or should not) contain any seeds.
- In a properly-designed drill pad all material spilt would ideally be caught in the sump. Drains should be constructed so that runoff is always into, and not past, the sump.
- Pump water away from watercourses and allow to drain through vegetation where possible.

- In sensitive areas, where discharge of water should be kept to a minimum, an effort should be made to recycle water. If a sump cannot be dug a tank should be taken onto the site and the water and drilling sediment contained in this. The drilling sediment can be removed at periodic intervals.
- An attempt should be made to contain the return water on drilling programmes not supported by an excavator (e.g. helicopter supported, truck-mounted rig). Small effective sumps can be created using combinations of timber for framing, strong plastic sheeting for lining, in conjunction with straw bales and oil-absorbent matting.
- To avoid the possibility of an unchecked spread of weed species, straw bales should not be used at remote sites or those sites where future monitoring will be rare.

STORAGE OF FUELS

- All fuel drums and other containers should be in a sound condition.
- Oil and diesel stored on site should be contained in a bund.
- A supply of oil absorbent material should be kept on hand to clean up any minor spills.

ACCIDENTAL SPILLS

- Spills of significant quantities of oil or diesel (i.e. more than half a 200 litre drum) require notification to Industry Safety and Mines and also to the Department of Environment and Land Management Oil Pollution Control Officer (telephone 008-005 171). Each large mine has a designated contact officer in liaison with the Department of Environment and Land Management, and notification may also be made using this network.
- Actions which may help clean up such spills include:
 - digging a trench (by hand) just below the spill and filling with oil-absorbent material; this is replaced at frequent intervals.
 - constructing a small dam/s with straw bales in any affected watercourse; placing in a 'sock' of oil-absorbent material to trap oil/diesel; replace 'sock' at regular intervals

DRILLING FLUIDS

- The only additives commonly used during drilling in Tasmanian conditions are substances such as Liquid Polymer, Baroid, and equivalents.
- As a matter of commonsense gloves and safety glasses should be worn when the mud is mixed or handled. The mud should be mixed in a well-ventilated area.
- Liquid Polymer is biodegradable. However if the material in the sump needs to be rendered inactive the manufacturer recommends adding liquid chlorine (such as the product used for domestic swimming pools which is 125 g/litre active chlorine). The liquid chlorine should be added to the sump at the rate of three litres per 1000 litres of sump fluid.

CAPPING DRILL HOLES

- All cored holes must be accurately surveyed and permanently marked so that their location can be readily ascertained.
- All holes, whether cored or otherwise, must be sealed so as to prevent collapse of the surrounding surface.
- All flowing drill holes or boreholes must be permanently sealed to prevent surface discharge of groundwater.
- Where any drill hole or borehole encounters natural or noxious gases, it must be plugged or sealed so as to prevent their escape.
- Where any drill hole or borehole encounters an artesian or sub-artesian flow it must be sealed discretely to prevent contamination of aquifers.
- Most exploration holes in Tasmania are cored, and are usually left open after drilling for later access for geophysical logging. When a hole is no longer required, it must be backfilled or permanently capped.

REHABILITATION


- If the ground is compacted by the use of heavy machinery or prolonged use, then the drill pad should be ripped to loosen the soil. An excavator bucket can usually loosen the compacted areas quite sufficiently. Take care when ripping or loosening not to create large furrows which may become erosion gullies. These can be avoided by being sure to rip along the contour.
- Stockpiled soil and vegetation should be spread over the site. An excavator will be able to do this more neatly than a bulldozer.
- If the soil has been stockpiled for more than three months, consideration should be given to reseedling. This will depend on the location of the site — see chapter on “**Rehabilitation and Revegetation**”.
- Consideration should be given to fertilising respread topsoil which has been stockpiled, whether seeding is done or not. A suitable fertiliser for most situations is the off-the-shelf 8:4:10 mix, which should be applied at the rate of 250 kg/ha. At this rate one kilogram will cover 40 m². The average drill pad, perhaps 15 m × 15 m (225 m²) will require 5 kg of this fertiliser. Organic fertilisers, such as OR-90, may also be suitable. OR-90 should be spread at the rate of 750 kg/ha. At this rate 15 kg will cover an average drill pad. OR-90 is sold in 20 litre bags (current retail cost \$8) which weigh approximately 15 kg. The cost is considerably lower if obtained from the manufacturer.
- If drainage works were put in around the perimeter of a drill site then leave them intact. This will prevent erosion of the newly established vegetation.
- The site should be monitored periodically and further work carried out, if required, to ensure success of the rehabilitation.
- Refer to the chapter on “**Rehabilitation and Revegetation**” for further details.



Any suitable methods which do not require pad construction?



Earthworks may not always be necessary — or possible.



Utilise existing disturbances wherever possible.

Photographic summary of main points — see text for more detailed information



Thoroughly clean down all machinery and equipment.



Stockpile vegetation and topsoil separate from subsoils.



Keep pad size and peripheral disturbance to a minimum.

Photographic summary of main points — see text for more detailed information



Excavate a sump in a suitable location.



Fuel and oil drums etc. are to be in a sound condition and stored appropriately.




Ensure the water pump has no fuel or oil leaks.

Photographic summary of main points — see text for more detailed information



Place oil absorbent products in sump and under rig — replace as required.



Keep the site tidy — remove all rubbish on completion of work.



Cap or cover drill holes, and plug if making water.

Photographic summary of main points — see text for more detailed information

COSTS — DRILL PAD REHABILITATION

□ Restoration of drill pads is largely dependent on the location and size of the pad, and the amount of restoration work needed. However, as a very rough guide, the following figures are given as a generalised approximation of costs where a reasonably large drill pad has been constructed. There will be many cases, of course, where such clearing has not been needed, or a much smaller area has been used.

Assumptions (1995 figures)

- No allowance has been made for the transport of machinery to the site. This is dependent on distance, and must not be forgotten.
- Drill pad 225 m² (0.0225 ha) (15 m × 15 m).

Costs for an average drill pad

Ripping if needed:	1/2 hour dozer or excavator time (minimum hourly rate)	\$90
Soil replacement:	1/2–1 hour excavator time	\$75
Seed (0.05 kg):	should be collected locally	
Fertiliser:	5 kg	\$2–\$8
Placement of seed and fertiliser by hand.		




The time of the person supervising the work must also be considered, as should the cost of floating the excavator to the site and between sites.

Costeans and Pits





- Costeans (meaning trenches) and pits should ideally be located to avoid large trees, but where this is not possible large trees (greater than 150 mm diameter) should be pre-cut and moved to one side for salvage.
- Topsoil (including scrubby vegetation) should be stripped and moved to one side of the costean.
- Topsoil should be stored in a long, narrow pile, no more than 0.6 m high. Piling topsoil into larger heaps does not allow oxygen to reach the centre of the pile, and useful soil organisms die. The soil becomes sterile and loses nutrients. Proper storage of soil is preferable wherever possible.
- Provide proper drainage through windrowed topsoil, which may have to lay for several months before rehabilitation works commence. Topsoil is easily erodible and must be protected from needless erosional loss by installing drainage if required. On a slope, a table drain uphill from the costean will be needed. This will also prevent the costean from filling up with water.
- Subsoil ('spoil') should be placed in a separate pile, not placed on top of the topsoil. One easy method for small costeans is to place the topsoil on one side of the costean and subsoil on the other. When the time comes to refill the costean, the subsoil is replaced first, then covered with the topsoil / vegetation mixture.
- With small costeans, which are filled in on the same day or within a few days of being dug, the storage of topsoil on one side and subsoil on the other is recommended.
- There is no need in these cases to strip topsoil to provide room for subsoil storage. However if the costean is large and will be left open for weeks or months, the topsoil should be stripped to make room for subsoil storage.
- Large costeans should be benched for the safety of workers. There may not be room on one side for the whole of the subsoil, in which case both soil and subsoil can be piled each side of the costean, but in separate piles.
- Bulldozers should never be used to dig trench-type costeans. Excavators and backhoes can do a far neater job. However when a shallow scrape is needed to expose rock for examination (also called a costean) then a bulldozer is the most suitable machine for this job.
- Replace scraped-off soil (if any) when a shallow 'scrape' costean is no longer required.
- Fill in costeans as soon as possible after the programme has finished. Replace subsoil, then spread out topsoil and vegetation.
- Encourage new growth by application of fertiliser and seeds if the site requires such treatment. If soil has been stored for longer than three months, the nutrients will have been depleted and fertilising will certainly be an aid to revegetation. If stored longer than six months, seeding will also be beneficial.
- Refer to the chapter on "**Rehabilitation and Revegetation**" for seeding rates and details on fertiliser types.

- Repairs to be made by 22 tonne excavator, cost \$75 / hour and D7 bulldozer (cost \$90 / hour). Having all work done by an excavator will be cheaper than mobilising two machines.
- Soil to be spread by excavator (which can spread soil over 1 ha in 8 hours); appropriate drainage works to be installed.
- If the pad is compacted, the area must be ripped with a bulldozer or an excavator. A D7 bulldozer can rip one hectare in 3.5 hours, an excavator will take slightly longer.
- Disturbance to be spread with fertiliser 8:4:10 at rate of 250 kg/ha; i.e. 1 kg will cover 40 m². A 225 m² drill pad will require 5 kg. Fertiliser costs about \$18 per 50 kg bag.

CONSTRUCTION OF COSTEANS




REHABILITATION OF COSTEANS




SLOPING SITES

On sloping sites provide drain above costean and soil storage



- topsoil not stripped before soil storage
- topsoil on one side of costean, spoil on other



- topsoil stripped to make room for subsoil storage

Rehabilitation and Revegetation

Rehabilitation is defined as "those activities which seek to improve damaged or degraded lands or to re-establish land that has been destroyed and to bring it back to a form where its biological potential is reinstated" (BRADSHAW, A. D.; CHADWICK, M. J. 1980. *The Restoration of Land*. University of California Press).

TIMING OF WORK

Successful rehabilitation is dependent on the works being done at the correct time of year. Earthworks should be done when the soil is dry enough to move — usually between November and March. Under no circumstances should earthworks be attempted when the soil is wet and waterlogged.

Seeding and fertilising should be done after the replaced soil has been softened by rains. Autumn is the ideal time to seed and fertilise replaced soils (i.e. March to May).

Peat can be replaced at any time.

ESTABLISHING A VEGETATION COVER

Once topsoil has been respread over a prepared disturbed area, a vegetation cover must be established. The viability of the seed and vegetative matter contained in the stockpiled topsoil degenerates dramatically with time. After 3 to 6 months stockpiled soil will have lost much of the regenerative material, and seeding may be needed.

Seeds should ideally be collected from plant populations growing locally, to preserve the integrity of the local gene pool. Seeds, when hand sown, should be bulked with sand or sawdust for ease of sowing.

NURSE CROPS

On large patches of bare ground, the sowing of a 'nurse crop' such as cereal rye (*Cereale secale*) can be beneficial. This is a crops species which will not persist to invade surrounding bush.

Cereal rye can be sown at 15–25 kg/ha as a cover crop, but as a stabilisation crop the seed should be sown at 70–100 kg/ha. The grass protects the soil from erosion, gives shelter to smaller sprouting seeds, and as it dies off a useful mulch is produced. Sowing a mix of native seeds and an annual nurse grass crop can assist in the establishment of a vegetation cover faster than if native seeds are sown alone.

MULCHING

Mulching also aids revegetation on very exposed sites by providing protection from extremes of heat and cold and drying winds to the newly germinated seedlings. Mulches must be chosen carefully and must not contain any weed seeds which may be thereby introduced into the area. Products such as straw, woodchips, shredded bark or OR-90 (when coarsely ground) can all be used as mulches. Straw is commonly spread at 2 to 4 tonnes/hectare. Do not use hay, as this contains seeds, which may become weeds in the area in which the bales are used.

Where erosion is a particular problem, such as on steep slopes, straw or mulch can be held in place by using non-galvanised 0.9 mm wire netting with a 50 mm mesh, stapled down at intervals of 1 to 2 metres.

POTTED SEEDLINGS

Potted seedlings may be used where 'instant' growth is needed, although these are quite expensive, costing from \$2.00 to \$2.75 each. Seedlings usually have to be bagged properly to prevent excessive losses through grazing damage. Field trials have shown that seedlings from sown seed often overtake planted out seedlings after two years or so, as the potted ones suffer some setback on planting out.

Nonetheless potted seedlings are very useful in areas where there may be fierce competition with opportunistic grasses, which prevent seedlings grown from seed from making reasonable progress.

HYDROMULCHING

There is a technique known as 'hydromulching' which is most useful in covering large bare areas. This consists of spraying the bare area with a mix of water, appropriate seeds, fertiliser and mulch, such as paper pulp mixed with indicator dye in a water and glue solution. The mix literally 'sticks' wherever sprayed, and the dye enables the sprayer to see what ground has been covered. The fertiliser and mulch enable the seedlings to get off to a good start. There are a number of firms who now specialise in this field, and will make up seed mixes to suit the site being treated.

TEA-TREE SLASH

One of the cheapest and easiest methods of revegetation, which is appropriate for use over small areas in many parts of Tasmania, is tea-tree slash. Pieces of seed-bearing tea-tree are collected — being careful to trim bushes selectively and not cut all the slash in one small spot — and these are laid over the newly spread topsoil. About one piece of slash per square metre is sufficient. The seeds drop out of the tea-tree, the leaves dry and fall off to form a mulch, and the twigs left act as sun, wind and grazing protection to the small tea-tree seedlings. This is of course not suitable in absolutely every exploration site, but is, nonetheless a good solution to economical revegetation of sites in many cases. Additional seeds and/or fertiliser can be added over the slash.

FERTILISERS

Field trials have shown that native plants do, in fact, respond well to small doses of fertilisers; this is especially evident in the establishment phase. There is some field evidence that the Myrtaceae family do especially well with the addition of small amounts of fertiliser; the Proteaceae do not do so well, and may in fact be hindered. Insect damage has been noted in some trials to be more severe in fertilised plots, due no doubt to the increase in lush new growth which can sustain greater numbers of insects. Grazing damage has also been seen to be greater on fertilised plots than on similar, non-fertilised plots.

On the whole, the use of fertiliser, especially in small amounts, is preferred to non-use. Use one such as the off-the-shelf 8:4:10 or 6:5:5 plus magnesium mix, at a rate of no more than 250 kg/ha. At a rate of 250 kg/ha, one kilogram of fertiliser will cover 40m². One handful (approximately 100 g) will cover four square metres.

Organic fertilisers such as OR-90, which is made from chopped eucalypt bark and orange roughly fish waste milled to a powder, may also have application in some situations.

Optimum Timing for Rehabilitation Works

TREATMENT	MONTH											
	J	F	M	A	M	J	J	A	S	O	N	D
DRAINAGE WORKS	—————											
SOIL STRIPPING	—————			●	●					●		—————
SOIL RESREADING	—————			●	●					●		—————
RIPPING (BEFORE SOIL RESREADING)	—————											
RIPPING (AFTER SOIL RESREADING)	—————			●	●					●		—————
NATIVE SEEDING		●	—————			●	●	●	-	●		
GRASS AND CLOVER SEEDING		●	—————		●					●	-	●
FERTILISING	—————											

————— Optimum time for treatments
 ● ● ● ● Treatments can be undertaken only under favourable conditions

(from DUCKETT, T. A. P. *Rehabilitation guidelines for forest construction*. Forestry Commission, Tasmania)

Use of Helicopters and Helipads

The information in this chapter has mainly been provided by Helicopter Resources. Some information is from a pocketbook on helicopter safety procedures by Tim Rudman (Parks and Wildlife Service) and Tony Mount (Forestry Tasmania).

In some areas of inaccessible terrain, the easiest option will sometimes be to mount a helicopter-assisted drilling programme. Ground parties using chainsaws, machetes and axes cut 'pads' large enough for the helicopter to land safely. All large items of equipment are then brought in for the programme by helicopter, and removed when the work is finished.

The exact costs of helicopter services and the safety requirements, such as size of helipad and the size and direction of the flight path corridor, will vary according to the type of craft used, the nature of the terrain, and the loads which must be carried. The size of the helicopter landing pads will also vary according to the site and the work envisaged.

Explorers should ascertain from their helicopter contractors the exact requirement for each programme.


However, as a rough guide, the following details relate to the minimum requirements for the use of an AS-350 model helicopter (the Squirrel).

HELIPAD CONSTRUCTION — MINIMUM REQUIREMENTS

The minimum size of a helipad for 'once only' landings, where no sling work is required, is around 14 m × 14 m.

Pads subject to frequent use, or where any sling work is required, must be at least 20 m × 17.7 m.

Whilst this size is generally sufficient on LEVEL GROUND, larger clearings may be required in sloping country. The direction of landing is variable in bush situations because changes in weather conditions cause variations in landing direction.



The pad size may also be dependent on the height of the surrounding vegetation. The taller the trees, the longer the opening required in the direction of takeoff and landing.

The area must be cleared so that the tail rotor does not come into the proximity of overhanging branches, standing tree trunks, or rocks sticking up out of the ground. The clearances required are:

TAIL ROTOR: 90 cm from ground level

MAIN ROTOR: 230 cm from ground level

There must be good 'all round' clearance to allow sufficient room for manoeuvring of helicopters and loads.

Ideally the helipad area should be flat, level, and clear of any foliage or rocks which rise above ground level.


Remember that a helicopter produces strong draughts on both takeoff and landing, and all loose items — small branches, tarpaulins, empty sample bags, buckets, clothing etc. may be swept up into the rotor system or engine intake. Ensure that the helipad is clear of any loose items prior to arrival and departure of the craft.

The helipad must have a clearly marked 'TOUCHDOWN ZONE' which must be at least

4.2 m in LENGTH

3.7 m in WIDTH

with a maximum slope of 7° (grade of 1 in 8) and be able to support a load of 4000 kg (4 tonne).



The TOUCHDOWN AREA must be clearly defined. This area may be level with the ground, or on a raised platform.

RAISED TOUCHDOWN AREAS such as 'LOG HELIPADS' are good in that better clearance can be provided, especially for the tail rotor. Logs must be placed on the pad so that there are no spaces between them. They must be aligned PERPENDICULAR to the line of flight, so that on landing the helicopter's skids rest across a number of logs, not along one log.

IDEALLY THE TOUCHDOWN AREA SHOULD BE DEAD LEVEL.


FLIGHT TERMINATION AREA

At the centre of the helipad there should be a CIRCULAR AREA of 10.7 m DIAMETER which has a maximum slope of 7° (1 in 8) which the pilot can use as a flight termination area.

FLIGHT ACCESS CORRIDOR

In timbered country, there may be a need to clear an access corridor to allow the helicopter to fly into and out of the helipad. The actual dimensions of such a corridor will depend on the site, and on the type of loads which must be carried.

RECOMMENDED MINIMUM HELIPAD DIMENSIONS



ELEVATION

Essential Requirements:

- i) Sufficient tail rotor clearance all round – vegetation < 90cm height.
- ii) Max 40° approach and departure angles.
- iii) Touchdown area minimum 4.2x3.7m and slope < 5°
- iv) All loose or light objects removed from ground effect area.
- (v) Relatively free of dust.

Discuss the programme with you helicopter contractor and ascertain the precise requirements for the job.

USING HELICOPTERS

Responsibility — Air Safety

- The pilot is the **sole arbiter** of any matter affecting the safety of the aircraft, air crew or sling load.

Responsibility — Helipad Safety

- Officer in charge shall be responsible for all ground operations around the landing site or helipad.


Briefings

- All personnel involved in an operation are to be thoroughly briefed in procedure and safety.
- The officer in charge shall inform the pilot, where necessary, of the following hazards:
 - Hydro, Telecom poles and lines, towers, blasting operations, dangerous goods on board.
- The pilot will require briefing on the number of passengers, type and weights of any loads (internal and external), distances, topography, helipads, fuel dumps, etc.

Remote areas

- If you are dropped in a remote locality for a day, ensure that you take gear and provisions adequate for at least a one night stay in the bush. Bad weather can prevent your pilot from returning to pick you up. Survival gear such as a tent, food, strobe light, heliograph, flare, first aid kit, matches and warm clothes should be stashed in a waterproof plastic drum, which is clearly marked. This should be checked before fieldwork, and should be off-loaded with you every time you are dropped in a remote area. The minimum party size should be at least two. Individuals should not be dropped into remote locations alone.


WEATHER



If dropped off in a remote area carry emergency clothing and food.

Watch the weather for signs of closing in and maintain radio contact for evacuation if necessary.

HELIPAD SAFETY



Keep heliports clear of unauthorised personnel, equipment and loose or light objects.




Do not smoke in flight or within 16 metres (50') of helicopter on the ground, fuel dumps or refuelling equipment.



Stay away from helicopter when rotor blades are in motion, unless authorised by the pilot or O.I.C. This means stay at least 16 metres (50') away.



Stay away from tail rotor at all times, and see that others do likewise.



Unless equipped with safety goggles or glasses, do not watch landings, take-offs or hovering, closer than 32 metres (100') from the helicopter.

EMBARKING, DISEMBARKING



Always approach the helicopter from the side — forward of the pilot's line of sight

EMBARKING, DISEMBARKING



Wait until pilot gives OK before approaching.
On soft or uneven ground helicopters often need to reposition.



Never walk behind or under tail of helicopter, even when the rotors are not in motion.



If blinded by swirling dust and grit, stop sit down and wait assistance.



In gusty conditions the main rotor blades will sail closer to the ground as they slow down, wait until rotor blade has stopped before approaching.



Approach helicopter in a crouched position. Hold onto any loose articles of clothing and hats. If possible use a hat with a chin strap when working around helicopters.



When boarding a hovering helicopter be sure to transfer your weight very gradually onto the skid and then the steps. **DO NOT LEAP** at the skid or cause your weight to shift suddenly to the machine.



When leaving a helicopter disembark quickly and quietly. Do not jump out. Do not cause a sudden shift in weight, even if the helicopter is on the ground.



On sloping ground approach and leave the helicopter **ON THE DOWNHILL SIDE** of the machine, to avoid main rotor.

LOADING AND UNLOADING



Carry any tools, such as picks and spades, at waist height. **DO NOT** carry anything on your shoulders. **DO NOT** throw anything out of the craft on landing — especially shovels, and the like, as these may hit the rotor.



Never stand directly beneath moving helicopter rotors, unless trained in and performing sling load hookup operations.



All long tools and equipment must be carried by two people (one at each end).




Always check goods to be loaded with pilot, especially batteries, fuel containers, pressurised vessels etc. These may need special containers.

Keep helicopter landing site clear of any loose articles which could fly around in the draught caused by the take off and landing. Such articles include groundsheets, tarpaulins, clothing, Eski lids and so on. Keep all gear at least 5–10 m away from edge of landing area.

If moving a crew, ensure that all members are familiar with safety rules and keep them back from the landing zone. Have them face away from the helicopter as it lands and takes off. Ensure that the crew files into the helicopter in an orderly fashion as soon as pilot gives the signal to board. Do not have any tents in the immediate flight path or they may be blown flat.

LOADING AND UNLOADING



Workers loading up slings must always be provided with eye or face shields to protect their eyes from flying debris.

After a sling has been hooked up (either to a stationary or to a hovering helicopter) move to a position in front of the helicopter in full view of the pilot, so as to avoid being hit by the loaded sling. If using a radio to give instructions to the pilot during sling work, do not give any order which requires manual acknowledgement, as the pilot will be busy with both hands on the controls.



Be aware of static electricity build up on the aircraft when hooking up in the hover position. The discharge is unlikely to be injurious.



Use aircraft rated stops, shackles etc. only, check with pilot. Check all knots or retie, lockwire all shackles with s/steel wire.




When winching stand clear until load reaches the ground then move in to disconnect. When hooking up always take bag to hook don't swing the hook.



Check gear is stowed securely and lockers are closed.


FLYING



Check with quarries in vicinity (2km) of low flying operations to ensure that no blasting will be occurring during planned flights.



Keep all loose objects secured in flight and never throw or let any object fall from the helicopter. Even a plastic bag around a rotor may bring down a helicopter.



Keep alert for hazards—inform the pilot. Don't assume the pilot has seen any hazard.
Do not talk to the pilot during take off and landing or when air traffic control are calling.

NO SMOKING



IN FLIGHT

SEARCH AND RESCUE GROUND SIGNALS

- Do not make any signals to aircraft unless in distress or searching.
- If assistance is required, attract the attention of an aircraft by using smoke signals, flares, mirrors or movement of brightly coloured objects. The accepted distress signal is three signals together, regularly spaced.
- Use only the ground to air signals listed below for passing on messages. These symbols are recognised by the Civil Aviation Authority and the Tasmanian Police force.
- Make the symbols at least 2m long with as great a contrast in colour as possible against the background. Use the same colour throughout if possible.
- The aircraft will indicate the symbols have been seen and understood by rocking from side to side.
- The aircraft will indicate the symbols have been seen but not understood by making complete right hand circuits, when viewed in direction of flight.

SYMBOLS

REQUIRE DOCTOR SERIOUS INJURIES	I	ALL WELL	LL
REQUIRE MEDICAL SUPPLIES	II	NO	N
REQUIRE FOOD AND WATER	F	YES	Y
INDICATE DIRECTION TO PROCEED	K	NOT UNDERSTOOD	JL
AM PROCEEDING IN THIS DIRECTION	↑	NOTHING FOUND CONTINUING SEARCH	NN

FACTORS AFFECTING THE CAPABILITY OF HELICOPTERS

Even though, as previously stated, the helicopter is a versatile aircraft, there are certain factors which limit its capability, and it is important that users are aware of these.

The major factors are dealt with below.

POOR WEATHER AND TURBULENCE

Poor weather conditions, apart from reducing visibility, may produce air turbulence which can affect the handling of helicopters, thus limiting their capability.

TEMPERATURE AND ALTITUDE

High temperatures and altitudes lessen the helicopter's lift capacity thereby reducing the maximum load which can be carried.

FUEL REQUIREMENTS

Compared with fixed wing aircraft, the helicopter has a very short endurance. Support helicopters normally leave Hobart with a full fuel load which will last from 2 to 3 hours. If the area of operation is remote from a major centre, thought must be given to either establishing a fuel depot in the field or ensuring that the helicopter brings sufficient fuel with it in the form of 20 litre cans or slung 200 litre drums. Liaison with the pilot, prior to his departure, is essential in order to establish the fuel requirements. The following major centres have aviation fuel, normally located at the aerodrome: Hobart, Launceston, Devonport, Wynyard and Queenstown. Additionally, the operator normally has fuel stocks at Smithton, Tullah, Crotty, Strathgordon, St Helens, Catamaran and Lake St Clair.

Prior notice will be required to obtain and shift drumstock (200 litre drums) from these centres to remote areas.

GROUND/AIR/GROUND COMMUNICATIONS

Most helicopters are equipped with 99 channel VHF radios for communications on the State Disaster Plan frequencies.

Note — Channelisation of these radios may differ from the State Disaster Plan channelisation.

The Pilot also has additional VHF and HF radio communications.

Normal flight practice is to maintain a ½ hourly S.A.R. schedule with air traffic control. In mountainous areas the helicopter may need to gain height in order to report.

MEDICAL EVACUATION BY HELICOPTER

GENERAL

There are a number of factors which must be considered before transporting an injured person in a helicopter. The major factors are:

- Pressure changes.
- Turbulence and Vibration.
- Noise.

These factors are dealt with below.

PRESSURE CHANGES

Any increase in height will produce a corresponding decrease in pressure. In a non-pressurised helicopter this can seriously affect an injured person. The parts of the body affected by pressure changes are the ears, sinus, lungs, gut and teeth. Severe pain will be experienced by persons suffering with ear and nasal problems; for example, persons with a heavy cold or with blocked sinus will experience severe pain, particularly when the aircraft is descending.

Another problem associated with reduced barometric pressure is that of decompression sickness or "bends". This may occur when there is a rapid ascent and is caused by gases, mainly nitrogen, escaping from the blood and tissue fluids into the cells of the body.

TURBULENCE AND VIBRATION

Turbulence and vibration are major factors to consider in relation to the transportation of an injured person in a helicopter. This is particularly so if the person is suffering from fractured limbs. Before transporting a person with a fracture, the following actions should be taken:

- Better than average splinting must be placed around the fracture.
- Layers of foam should be placed under both the fractured limbs and the person.
- If necessary sandbags should be placed around the fractured limb to completely immobilise it.

NOISE

Noise is another factor to consider, as irritability can occur with a distressed person or a person suffering from head injuries.


CONCLUSION

Prior to transporting an injured person in a helicopter the factors dealt with above must be considered. In addition the following rules must be observed:


- Ensure that the condition of the injured persons is established. That is, the person must have a regular pulse, good breathing and acceptable blood pressure.
- Ensure that any bleeding has been stopped before transporting the person. NEVER transport a person who is haemorrhaging internally or externally.

HAND SIGNALS

The following are universally accepted hand signals to helicopter pilots:




MOVE HORIZONTALLY: Appropriate arm extended horizontally sideways in direction of movement, and other arm swung in front of body in same direction, repeating




MOVE UPWARDS: Arms extended horizontally, palms facing upwards; move palms upwards; speed of movement indicates rate of ascent.



LAND: Arms crossed and extended in front of body.




MOVE DOWNWARDS: Arms extended horizontally, palms facing downwards; arms move downwards; speed of movement indicates rate of descent.



HOVER: Arms extended horizontally from shoulder.




WINCH DOWN: Left arm horizontal in front of body, with fist clenched. Right hand with palm turned down, making a downwards motion.




COME FORWARD: Arms in front with palms facing body, beckoning helicopter forward.



LOAD HAS NOT RELEASED: Right arm held across chest, bent at elbow; palm facing downwards; left hand held under



MOVE BACK: Arms in front with palms facing away from body pushing helicopter away. Pushing movement.



RELEASE SLING OR WINCH LOAD: Left arm extended in front of body, fist clenched; right hand making slicing

NOTE

Important hand signals to remember are the “thumbs up” and “thumbs down” signals.

THUMBS UP indicates to the pilot any of the following:

YES, ALL IS WELL, UNDERSTOOD

THUMBS DOWN indicates to the pilot any of the following:

NO, ALL IS NOT WELL

Camping

Frequently fieldwork must be carried out from base camps. Large programmes may be conducted from hutted camps, whilst smaller programmes often involve tented camps for brief periods of time. The general rule of camping, either at hutted camps or in tents, is to leave an area in the same, if not better, condition than found.

FIRE PRECAUTIONS — ALL CAMPS

- *The Fire Services Act 1979* (Section 69) forbids the lighting of any fire for cooking or warmth in or on peat, humus or marram grass, or within three metres of any stump, log or standing tree. Fires shall not be left unattended unless completely extinguished. As a general rule open fires are not encouraged and all cooking should be done on fuel stoves wherever possible.
- Should an open fire be needed, then only dead wood is to be used as fuel. The fire should only be lit in a cleared area, and must be kept as small as possible. A cut-down 44 gallon drum makes a good container in which a fire may be confined. The fire must be extinguished prior to the campsite being vacated.
- Most huts have fireplaces installed. Spark arrestors on the flue or chimney are recommended in all areas. Only fallen or dead wood should be collected for use in the fireplace.
- Many huts have generators installed for electric power. As with all machines, these must be well maintained. Leaves and debris should not be allowed to collect near the exhaust of these machines as this could represent a fire hazard in some conditions.
- On all work sites where chainsaws, power augers, generators or other petrol-driven machinery are either used or serviced, there must be a serviceable knapsack filled with not less than 10 litres of water, or a powder-type fire extinguisher of not less than one kilogram capacity, for fire fighting purposes.
- All premises used as kitchens, or used as sites for storing of fuel, or servicing or refuelling machinery will be:
 - cleared to bare earth;
 - surrounded by a firebreak, three metres or more wide, sufficient to isolate the premises from the surrounding vegetation.
- All hutted camps are to be fitted with serviceable fire extinguishers.
- During a FIRE PERMIT PERIOD persons occupying permanent (i.e. hutted) and temporary (hutted or tented) camp sites, drilling sites and work sites either using, refuelling or servicing any earthmoving equipment shall have the sites equipped with the following fire fighting tools:
 - a serviceable knapsack pump filled with not less than 10 litres of water;
 - a slash hook;

- a fire rake or grubbing-hoe, or beaters;
- a receptacle containing not less than 180 litres of water.

ALL CAMPS — GENERAL GUIDELINES

- All rubbish to be removed from campsites. Rubbish shall not be burnt or buried. Tins, especially, shall not be discarded as wildlife are prone to getting their heads stuck in such items, causing injury and/or death to the animal, in addition to the visual problem of the litter. Rubbish containers (e.g. 200 L drum) should be provided at campsites.
- Ensure washing (of people, dishes, clothes) is done at least 50 m from any watercourse. Scatter soapy water into ground, so some filtering is done before water percolates back to nearest stream. DO NOT wash dishes in creeks, streams or lakes, as this will introduce food scraps into clean water. Use biodegradable soaps and detergents.
- Pets (dogs and cats) should be left at home.


HUTTED CAMPS

Permanent, or large semi-permanent camps must be equipped with either a long drop toilet pit or a chemical toilet. The contents of the latter should be flown out for proper disposal.

In boggy areas, provision of cording or duck boarding around hut/s will be both more comfortable for camp users and environmentally responsible. Such materials should be ferried in to the camp, not cut from local vegetation.

TENTED CAMPS

- Unless completely unavoidable, no vegetation should be cut to provide a campsite. Suitable campsites can often be found without resorting to the cutting of standing vegetation. Use existing campsites wherever possible.
- Camp at least 50 m away from watercourses of any size — freshwater lakes, creeks and rivers.
- Toilet waste should be buried at least 100 m from any campsite or watercourse. A hand trowel should be carried for this purpose. Dig a hole at least 15 cm deep in soil to bury waste. In snow bury refuse in soil beneath snow wherever possible. The snow will melt!!! leaving refuse if this is not done.
- Camping parties are expected to be equipped with modern camping gear including bedding, air mattresses, foam mats or stretchers for bedding, and tents including tent poles, to avoid the old fashioned practice of cutting ferns for bedding and saplings for tent poles.
- The construction of campsite 'furniture' is to be avoided. Lightweight chairs and tables are to be ferried in (and out again) if required.




Known locations of *Phytophthora* in Tasmania



LEGEND

0 Kilometres 60

● Recorded locations



Map courtesy of Forestry Tasmania

Plant Diseases and Weeds

- Some plant and stock diseases and weed species can easily be transported by people and vehicles, and especially by heavy earth-moving machinery if hygiene measures are not observed between jobs. Whilst explorationists are not the sole users of heavy machinery in isolated areas, or the sole users of many West Coast tracks, there remains an obligation on all users of all tracks to try and prevent the spread of weeds, and of pathological fungal diseases. One of the worst plant diseases in the State is the fungus *Phytophthora cinnamomi*, and whilst this disease is incurable, strict hygiene measures may reduce the spread of this menace.

PHYTOPHTHORA

- *Phytophthora cinnamomi*, commonly known as Cinnamon Fungus, is an introduced plant fungus which causes dieback and death in a good many of our native plant species. The fungus can be water borne, and lives in soil. One of the prime methods by which this disease is spread is by the carriage of particles of soil from infected to uninfected zones.
- The quantity of soil which must be moved to infect an area is staggeringly small. The fungus is known to have been spread by the passage of walkers; both wombats and sulphur-crested cockatoos are suspected vectors. The spread of this fungus by earth-moving machinery is a real possibility.
- Recent studies (PODGER, F. D.; PALZER, C.; BROWN, M. J. 1990. Bioclimatic analysis of the distribution of damage to native plants in Tasmania caused by *Phytophthora cinnamomi*. *Australian Journal of Ecology* 15:281) have shown that, unfortunately, the fungus is present over much of the State already, but the fungus is unlikely to survive on sites where the mean annual temperature does not exceed 7.5°C, or the annual mean rainfall is less than 600 mm; i.e. the fungus will not live in cold, dry areas such as on parts of the Central Plateau.

A map showing the location of known sites of infection is shown opposite.

- Whilst strict hygiene measures must obviously be observed in the *Phytophthora*-free zones, there are also good arguments for continuing some hygiene procedures in areas known to be already infected with the fungus. In an infected area, the species most susceptible to the fungus will brown off and die completely. Susceptible species include Blackboys (*Xanthorrhoea australis*), Christmas Bells (*Blanfordia punicea*), Springelia (*Sprengelia incarnata*), white Waratah or whitey-wood (*Agastachys odorata*), Melaleuca (*Melaleuca squarrosa*), Pandani (*Richea pandanifolia*), Mountain Berry (*Gaultheria hispida*) to name just a few. In fact, most of the heath family (Epacridaceae), the pea family (Fabaceae), and the Proteaceae (Banksias, Hakeas and the like) are all very susceptible. Even rainforest tree species and many eucalypts are not immune from this disease.

- Special care should be taken in coastal heathlands, buttongrass, sedgeland plains, and in dry eucalypt forest areas.
- Following an area becoming infected, the more susceptible plants die, and these are replaced by other, more hardy types. Thus the core area of an infected zone may well seem to be of healthy scrub — but a number of key species will be missing. Out from this now-revegetated core will be a zone where the susceptible species will be dead and dying, then beyond this, healthy plants in the uninfected zone. When moving from an infected to an uninfected area, always clean boots and tools, and wash machinery and vehicles. Plan routes to avoid entering infected regions then passing into uninfected country. Visit infected areas last on a journey.
- Before undertaking certain activities in areas known to be *Phytophthora*-free, explorers may be required to observe hygiene regulations. Industry Safety and Mines, in consultation with other Government agencies, will advise what precautions are required.

HYGIENE MEASURES

Bleach (sodium hypochlorite) is no longer considered to be useful as an effective fungicide. Whilst bleach-treated water readily kills the fungal spores, it is not effective in killing mycelium unless used in very high concentrations and the item soaked for at least 24 hours. Consequently the use of bleach as a fungicide is no longer recommended.

Small Items

In some areas explorers may be asked to clean all items which will have been in contact with the soil; boots, shoes, tent pegs, spades, shovels and so on. Washing items in water will suffice. Ensure that the item is washed free of soil.

Machinery

Larger items such as augers (hand held or power), earth moving machinery and vehicles should be washed clean with water and sprayed with a dilute solution of ABF-42 (mixed up at 400 parts water to 1 part ABF-42). Helicopter skids should be washed (with water) if muddy.

PLANNING

Work should be planned so as excursions should not be made from INFECTED to UNINFECTED zones. Try and plan activities so that work is completed in uninfected areas before moving on to infected zones.

Aircraft flights should follow this same pattern — work in uninfected areas first, leaving infected areas until last.

INFORMATION ON ABF-42

ABF-42 is a poly quaternary microbiocide commonly used in Australia to control the bacteria which occur in air conditioning systems and which are responsible for Legionnaires Disease. ABF-42 is registered in Tasmania at the non-label concentrations set out below for the control of *Phytophthora cinnamomi*.

The active ingredient in ABF-42 is poly [oxyethylene (dimethyliminio) ethylene (dimethyliminio) ethylene dichloride] at a concentration of 1%.

The distributors of this product are:

Chemsearch Australia
5-9 Ralph Street
Alexandria
NSW 2015

Telephone (02) 693 5077
Emergency (02) 44 5265

Storage and Transport

- ABF-42 is a transparent, light amber, non-viscous liquid with little or no odour.
- ABF-42 has an 'indefinite' shelf life.
- ABF-42 is classed as 'non-hazardous' for transportation.
- Store between 0°C and 49°C in a sealed, labelled container in a dry location.

Health Hazard Information (on ABF-42 Concentrate)

- Skin contact: may cause redness or irritation.
- Eye contact: may cause burning sensation.
- Ingestion: may cause nausea. It is unlikely that enough ABF-42 concentrate could be swallowed to cause poisoning before vomiting occurs.

Emergency First Aid

- Skin contact: flush with water and soap; use emollient cream, see a doctor
- Eyes: flush with water for 15 minutes; see a doctor
- Ingestion: promptly drink large quantity of milk or egg white, or if unavailable drink water. Avoid alcohol. See a doctor.

If Poisoning is Suspected

- If poisoning is suspected contact a doctor or the Poisons Information Centre (002) 38 8485 (24 hours) or (002) 38 8677.
- State that the suspected poisoning agent is a POLY QUATERNARY MICROBIOCIDE ABF-42.
- Chemsearch Australia (Manufacturer) emergency contact number: Phone (02) 693 5077.
- Full description of ABF-42: Poly [oxyethylene (dimethyliminio) ethylene (dimethyliminio) ethylene dichloride].

Spill or Leak Procedures

If ABF-42 concentrate is released or spilled, quickly trap spill in one area by surrounding with absorbing clay, sawdust or paper. Add enough absorbing material to absorb spill completely, shovel into bags or barrels and dispose of in an approved landfill area for chemical wastes. Avoid contact with spill. Any material which cannot be collected must be diluted with as much water as is available and may then be flushed away.

Waste Disposal

Dump used drums in an approved landfill area. Do not re-use empty containers. Puncture drums before disposing of in an approved solids waste dump. This product is toxic to fish.

Special Precautions

- Wear goggles and rubber gloves when handling concentrate.
- Keep out of reach of children.
- Read label directions thoroughly before opening.
- Avoid contact with skin and eyes. Wash concentrate from skin and eyes immediately.

Environmental Hazards

- This product is toxic to fish and water organisms. Treated effluent (i.e. mixed solution) should not be discharged where it will drain into lakes, streams, ponds or public water. Do not contaminate water by cleaning of equipment or disposal of wastes. Only use ABF-42 where waste water will accumulate in a sump.

How to use ABF-42 Concentrate

The concentrate is diluted 400:1 for application to items to be disinfected. The diluted solution is unlikely to have any adverse effects, however as a matter of commonsense persons handling ABF-42 should wear a full set of wet weather gear (gumboots, overtrousers, raincoat, gloves) and safety glasses or a visor to protect the eyes.

Disinfection Procedure

The equipment to be disinfected is to be treated before entering a sensitive area, and after treatment should not contact soil during transit to the sensitive area.

1. Wash thoroughly with a high pressure hose to remove clods of earth. Pay particular attention to the underside of machinery, inside sump guards and 'dozer belly plates, inside tractor wheels and all track gear.

Use spade or crowbar to remove compacted soil where needed.

After washing, leave standing for 10 minutes to drain water.

2. Dilute ABF-42 concentrate to working strength by mixing one part of ABF-42 concentrate with 400 parts of clean water.

Use the diluted solution to thoroughly wash down all surfaces likely to have been in contact with soil. Don't forget cabin floors and footplates.

3. Do not drive cleaned vehicle through washdown effluent.
4. In the field, washdowns should be done on a hard, rocky surface. When using ABF-42 do not washdown effluent flow into any creek — dig a sump and allow effluent to soak into ground.
5. Knapsack sprays: to assist in compliance with these hygiene measures Industry Safety and Mines has on hand a number of backpack sprays and a supply of ABF-42 which can be used as required.

Weeds


- There are a number of plant species in Tasmania which are regarded as weeds. Whilst weeds are opportunistic and can quickly cover a barren area, they will spread into the surrounding vegetation, and compete with the existing flora. For this reason, weeds should NEVER be used in revegetation projects, and steps should be taken to prevent weed seed being spread by people and machinery.
- In Tasmania, weeds are generally classed as such due to the potentially devastating effect they could have on our agricultural industry. The weed gorse is of concern to farmers in the Midlands, for example. However some weeds are already causing concern as they are spreading into bushland. Weeds in this category include canary broom on Maria Island, a variety of pampas grass which is spreading into parts of the southwest, blackberry, gorse and broom which are very evident on the West Coast, and ragwort along the North West Coast.
- Tasmanian weeds are classed into three categories:
 - Noxious
 - Secondary
 - Prohibited

All noxious and some secondary weeds are classed as 'prohibited'. This means that these plants may not be propagated, sold or transported within Tasmania.

PREVENTION OF SPREAD

- All earthmoving machinery should be routinely washed to remove all clods of earth when moving from one location to another. Vehicles should also be washed, and mud knocked off boots and shoes.
- Any weeds found growing in newly revegetated zones should be removed by digging, or poisoning with an appropriate herbicide. Weeds encountered during track building should similarly be eradicated. Seed pods, if present, should be removed from the area.

Some exotic species which are not classified as a noxious weed are nevertheless environmentally undesirable plants. Always check that species to be used in revegetation projects are quite acceptable before planting.



Cirsium vulgare (Spear Thistle) (Department of Primary Industry and Fisheries)

LIST OF WEEDS

Noxious Weeds

<i>Botanical name</i>	<i>Common name</i>	<i>Botanical name</i>	<i>Common name</i>
* <i>Acroptilon repens</i> (= <i>Centaurea repens</i>)	Creeping Knapweed (Hardheads)	<i>Foeniculum vulgare</i>	Fennel
* <i>Asphodelus fistulosus</i>	Onion Weed	* <i>Galium tricornutum</i>	Three-horned Bedstraw
* <i>Berkheya rigida</i>	African Thistle	* <i>Heliotropium europaeum</i>	Common Heliotrope*
* <i>Carduus nutans</i>	Nodding Thistle	<i>Hypericum perforatum</i>	St John's Wort
* <i>Carthamus lanatus</i>	Saffron Thistle	<i>Lycium ferocissimum</i>	African Boxthorn
* <i>Cenchrus incertus</i> (= <i>Cenchrus pauciflorus</i>)	Spiny Burgrass	<i>Marrubium vulgare</i>	Horehound
* <i>Cenchrus longispinus</i>	Spiny Burgrass	* <i>Myrsiphyllum</i> <i>asparagoides</i>	Bridal Creeper (Smilax)
* <i>Chondrilla juncea</i>	Skeleton Weed	<i>Oxalis</i> spp.	Oxalis
* <i>Cynara cardunculus</i>	Artichoke Thistle	* <i>Pennisetum villosum</i>	Feathertop
* <i>Emex australis</i>	Spiny Emex (Double Gee, Three Cornered Jack)	<i>Reseda lutea</i>	Cut-leaf Mignonette
		<i>Reseda luteola</i>	Wild Mignonette
* <i>Equisetum</i> spp.	Horsetail	<i>Rosa rubiginosa</i>	Sweetbriar
* <i>Homeria</i> spp.	Cape Tulips	<i>Rubus</i> spp. (excluding <i>Rubus idaeus</i> and <i>Rubus parvifolius</i>)	Brambles
* <i>Nassella trichotoma</i>	Serrated Tussock	<i>Rubus fruticosus</i> agg.	Blackberry
* <i>Onopordum</i> spp.	Onopordum Thistles	<i>Rumex crispus</i>	Curled Dock
* <i>Opuntia aurantiaca</i>	Tiger Pear	<i>Rumex obtusifolius</i>	Broad-leaf Dock
* <i>Parthenium hysterophorus</i>	Parthenium Weed	* <i>Salpichroa organifolia</i>	Pampas Lily-of-the-Valley
* <i>Pennisetum macrourum</i>	African Feathergrass	<i>Senecio jacobaea</i>	Ragwort
* <i>Solanum elaeagnifolium</i>	Silver-leaf Nightshade (Whitehorse Nettle)	<i>Silybum marianum</i>	Variegated Thistle
		* <i>Solanum marginatum</i>	White-edged Nightshade
* <i>Stipa brachychaeta</i>	Espartillo	* <i>Solanum sodomaeum</i>	Apple-of-Sodom
* <i>Stipa caudata</i>	Espartillo	* <i>Tribulus terrestris</i>	Caltrop
* <i>Xanthium</i> spp.	Burrs	<i>Ulex europaeus</i>	Gorse
		+ <i>Genista monspessulana</i>	Canary Broom
		+ <i>Sarothamnus scoparius</i>	Broom

Secondary Weeds – Terrestrial plants

<i>Allium triquetrum</i>	Three-corner Garlic
* <i>Allium vineale</i>	Crow Garlic
<i>Anthemis cotula</i>	Stinking Mayweed
* <i>Asparagus asparagoides</i>	Bridal Creeper (Smilax)
<i>Cardaria draba</i>	White Weed (Hoary Cress)
<i>Carduus pycnocephalus</i>	Slender Thistle
<i>Carduus tenuiflorus</i>	Slender Thistle
* <i>Carex buchanae</i>	Sedge
* <i>Carex comans</i> (<i>C. albula</i>)	Sedge
* <i>Carex flagellifera</i>	Sedge
* <i>Carex testaceae</i>	Sedge
<i>Cirsium arvense</i>	Californian Thistle (Creeping Thistle)
<i>Cirsium vulgare</i>	Spear Thistle
<i>Conium maculatum</i>	Hemlock
<i>Cortaderia</i> spp.	Pampas Grasses
* <i>Cuscuta</i> spp. (excluding <i>Cuscuta tasmanica</i>)	Dodder
<i>Datura</i> spp.	Datura
<i>Ecballium elaterium</i>	Squirting Cucumber
<i>Echium plantagineum</i>	Paterson's Curse
<i>Echium vulgare</i>	Paterson's Curse (Viper's Bugloss)
* <i>Eragrostis curvula</i>	African Lovegrass
* <i>Euphorbia lathyris</i>	Caper Spurge

Secondary Weeds – Aquatic plants

* <i>Alternanthera</i> <i>philoxeroides</i>	Alligator Weed
* <i>Cabomba caroliniana</i>	Fanwort
* <i>Ceratophyllum demersum</i>	Hornwort
* <i>Egeria densa</i> (<i>Elodea densa</i>)	Egeria (Dense Water Weed)
* <i>Eichhornia crassipes</i>	Water Hyacinth
* <i>Elodea canadensis</i>	Canadian Pondweed (<i>Elodea</i>)
<i>Glyceria maxima</i>	<i>Glyceria</i> (Reed Sweet Grass)
* <i>Gymnocoronis</i> <i>spilanthoides</i>	Temple Plant
* <i>Hydrilla verticillata</i>	Hydrilla (Water Thyme)
* <i>Lagarosiphon major</i>	Lagarosiphon
* <i>Myriophyllum aquaticum</i> (= <i>M. brasiliense</i>)	Parrot's Feather (Brazilian Water Milfoil)
* <i>Pistia stratiotes</i>	Water Lettuce
* <i>Sagittaria graminea</i>	Sagittaria
* <i>Sagittaria montevidensis</i>	Sagittaria
* <i>Salvinia auriculata</i>	Salvinia
* <i>Salvinia molesta</i>	Salvinia
<i>Typha</i> spp.	Cumbungi

* Denotes prohibited weed

+ Secondary weed in the Waratah Municipality


Protocol with private landowners

On occasions, the explorer may wish to enter upon private property to enable exploration to proceed according to plan. A balance must be maintained between the interests of the landholders, who have surface rights, and the explorer who has rights to explore for minerals, which are usually the property of the Crown. The question of ownership of minerals is quite complex in Tasmania and is addressed elsewhere in this book.

A pamphlet entitled *Exploration and Mining — the Landholder's Position* is available from Industry Safety and Mines, and this clearly outlines the rights of the landowner and responsibilities of the explorer. Distribution of these pamphlets to landowners whose land is to be explored, and discussion with them of your proposed activities, is a good idea. Another pamphlet entitled *Explorer—Landholder procedures — A commonsense guide to good relations between miners and farmers* has been produced for the use of explorers by the Australian Mines and Metals Association and the Tasmanian Farmers and Graziers Association.

Harmonious working relationships with landowners can be achieved by adherence to simple guidelines.

- Liaise closely with landowners. Select a Field Supervisor who has, if possible, some knowledge of farming and grazing practice. The Field Supervisor must be familiar with **all aspects** of the field programme.
- The Field Supervisor should make direct contact with the landholder well in advance of entering the property, and discuss the exploration programme and how any procedures may affect the land or improvements (fences, gates and so on).
- Give the landowner the names of the senior field staff, and leave a telephone number where the Field Supervisor can be contacted should any problems arise.
- Leave with the landowner a location map showing position of any proposed grids or drill holes. Discuss with the landowner and be advised of any particular areas which require special care — such as buried water pipes, contour banks, shade clumps, erosion prone land and the position of gates and fences.
- Make all contractors and subcontractors aware of company policy in the field and ensure that this is adhered to. Do not leave liaison with the landholder solely to the contractor. The holder of the EL must bear the responsibility for establishing good working relationships with the landowner.
- Ensure that the operation of heavy machinery is supervised at all times and ensure that the contractor understands what is required.
- Where practicable the explorer should contact the landholder before each operational phase of activity. Keep the landowner informed of the progress of your work, be sure to discuss any changes to the programme — such as moving a proposed drill site, and so on.
- If heavy machinery is required (i.e. for drilling) let the landowner know when the machinery will be entering the property so he/she may be present if he/she so desires.
- No fishing, hunting or carrying of firearms without the express permission of the landowner.



- In country areas, contact the local Council Clerk if use of narrow, winding, unsealed, country roads by heavy machinery is envisaged. Discuss the use of the roads by your vehicles, particularly during wet weather, when roads may be subject to damage. If drilling on roadside verges, leave a map showing the proposed area of activity with the Council Clerk, and discuss with him/her your intended programme.
- When ground is wet, limit or curtail entirely machine movements which would damage tracks/roads and/or paddock surfaces. If machinery must be moved, and damage occurs, then be sure to repair the damage as soon as possible, and to the satisfaction of the landowner.
- Keep the number of vehicles on a property to a minimum, and where possible keep to the same track.
- Use existing gates wherever possible. Go out of your way to use these.
- Leave gates as you found them. Do not shut an open gate; and do not leave open a gate which was shut.
- Ensure any tracks put in for exploration are properly made and drained, and will not degenerate into an erosion hazard.
- Prevent the spread of noxious weeds by frequently hosing down heavy machinery and vehicles. Enquiries should be made at the local Department of Primary Industry and Fisheries office concerning stock health campaigns. Washing of vehicles may be needed within one district or even between properties to prevent the spread of weeds and/or stock diseases.
- As little timber should be cleared as possible. Try and remain flexible on the precise positioning of drill holes and grid lines, and be prepared to move (if possible) the proposed location a few metres to avoid, for example, a clump of shade trees. Keep gridlines to an absolute minimum width when cutting through shade belts.
- If timber is cleared be sure to do so in a manner acceptable to the landowner.
- On completion of exploration, tracks and rehabilitation requirements should be discussed with the landowner. The tracks may or may not be wanted; drill pads may or may not have to be ripped; or the farmer may prefer to have the company pay him to do the work.
- When the project is finished invite the landowner to inspect the work area so any problems can be discussed and seen to promptly.
- Remove all rubbish from drill sites — including piles of cuttings if holes are chip drilled — unless you have agreed with the farmer that these can be left and spread over the drill site on completion of work. Make sure drill holes are either filled in completely, or capped and made safe for stock.

