223001

BASS BASIN

Tasmania, Australia
Permit T-19-P

Annual and Fourth Quarter Report
December 27, 1983 to March 27, 1984

Submitted by

Perthshire Petroleum Ltd.
14141 Southwest Freeway
Houston, Texas U.S.A.

OR-208

223002

TABLE OF CONTENTS

Summary

Recommended Seismic Program

Maps

Paleocene/Cretaceous Play Concept

Bass Basin Evolution

Structural Framework

Geoseismic Cross Sections

Stratigraphy

- Regional
- Well Completion Reports

Leads

- Manatee
- Penguin
- Seal
- Eastern Area

Representative Seismic Lines

Enclosure

Figures

Maps

223003

SUMMARY

Seismic time structure maps have been constructed by Exploration Associates International over what appears to be the most prospective portion of Permit T-19-P. Several leads have been identified and are grouped into the Manatee, Penguin and Seal areas. Because of their location in regard to the major structural elements of the Bass basin, each of these different lead areas offer the possibility of structural and stratigraphic entrapment of hydrocarbons under very diverse conditions.

The Manatee leads consist of tilted fault blocks associated with a major basin forming growth fault. The objective section consists of Eocene, Paleocene and Cretaceous clastics which, the most recent BMR studies, have shown to contain mature marine, deltaic or lacustrine source rocks. The primary objective section is located below a major unconformity which also offers the possibility of entrapment.

The Penguin horst blocks plunge towards the southeast or deeper portion of the basin. These are characterized by significant crestal convergence of the section while their flanks display expanded sections associated with the downthrown graben areas. Their objective sections is the same as at Manatee.

The Seal leads consist of tilted fault blocks located on the northeast side of the central graben area. These are not very well defined due to the low density of quality seismic data in this part of the basin.

A prospect definition seismic program is recommended. The proposed 21 lines amount to 385.25 line kilometers and should adequately define drillable prospects on Permit T-19-P.

RECOMMENDED SEISMIC PROGRAM

A prospect definition seismic acquisition program is recommended.

The recommended program consist of 21 dip and strike lines and amount to 385.25 line kilometers. The proposed lines are laid in such a way as to provide maximum coverage and are tied to the Perthshire 1981 and 1982 lines as well as to the lines acquired by the previous permit holders.

The emphasis of the program is given to the Manatee leads area which appears to provide the best opportunity for the definition of large prospects in the central graben area. Next are the Penguin and Seal areas. These three areas are to be tied together with two lines across the basin.

The line identifiers and individual lengths are listed.

Line	Lead	Kilometers
P-84-1	Manatee dip	10.00
P-84-2	Manatee dip	10.00
P-84-3	Manatee dip	10.30
P-84-4	Manatee dip	12.60
P-84-5	Manatee dip	14.00
P-84-6	Manatee/Seal dip	32.50
P-84-7	Manatee dip	16.00
P-84-8	Manatee strike	28.90
P-84-9	Seal dip	7.95
P-84-10	Seal dip	8.60
P-84-11	Seal dip	16.20
P-84-12	Seal dip	13.40
P-84-13	Seal strike	16.85
P-84-14	Seal strike	8.90
P-84-15	W. Penguin/Penguin dip	15.60
P-84-16	W. Penguin/Penguin/Seal dip	35.60
P-84-17	Penguin dip Manatee strike	25.90
P-84-18	Manatee strike	33.65
P-84-19	Manatee strike	30.50
P-84-20	Manatee dip tangent	21.30
P-84-21	Manatee dip tangent	16.50
		385.25

MAPS

Three seismic time structure maps and an isochron map has been constructed by Exploration Associates International over the central graben area and flank graben area of Permit T-19-P. The map area has been divided in a west panel area and an east panel area. All the maps are at a scale of 1:50.000. Various contour intervals have been used. The map levels are tied to the Konkon #1 Well by a synthetic seismogram. Figure A1, 2, 3.

The map levels are:

- Top Eatern View Coal Measures
- Lower M. diversus Seismic Horizon
- Top Eastern View Coal Measures to Lower M. diversus Seismic Horizon
- Pre. Lower M. diversus Dip Rate

The lower M. diversus seismic horizon is the deepest reliable reflector of regional extent. Selected dips at various levels below the Lower M. diversus horizon have been used to construct the Pre Lower M. diversus Dip Rate map. These dip segments are only present within the early Tertiary and pre Tertiary depocenters.

The Top Eastern View Coal Measures to Lower M. diversus isochron conforms to the configuration of the Early and Pre Tertiary depocenters. The age of the isochron interval pre-dates Oligocene and later movements of the Mornington - King Island fault.

SYNTHETIC SEISMOGRAM

GTS CORP. HOUSTON OFFICE 3724 DACOMA 77018

ESSO AUSTRALIA LTD. KONKON 1 WILDCAT AUSTRALIA TASMANIA W

LOG DATUM = 32 SEISMIC DATUM = 0 COMMENTS .




Figure A. 1


223007

SYNTHETIC SEISMOGRAM

GTS CORP. HOUSTON OFFICE 3724 DACOMA 77018

ESSO AUSTRALIA LTD. KONKON 1 WILDCAT AUSTRALIA TASMANIA W

LOG DATUM = 32 SEISMIC DATUM = 0 COMMENTS _____



2230C8

Figure A 2

SYNTHETIC SEISMOGRAM

GTS CORP. HOUSTON OFFICE 3724 DACOMA 77018

ESSO AUSTRALIA LTD. KONKON 1 WILDCAT AUSTRALIA TASMANIA N

LOG DATUM = 32 SEISMIC DATUM = 0 COMMENTS _____




Figure A. 3

223009

PALEOCENE/CRETACEOUS PLAY

The BMR studies of the Bass Basin J. C. Branson et al, (Enclosure 1.) can be summarized as follows:

- Recent reviews of the hydrocarbon potential have demonstrated that suitable source rocks and maturation conditions existed in the Late Cretaceous to Paleocene sequence, and that plays could be developed at that level which may justify further examination.

- Slower basin subsidence prevailed in the Late Cretaceous with sediments devised from eroded Paleozoic and Proterozoic highland areas, as well as Upper and Lower Cretaceous elevated portions of horst blocks. These sediments were deposited under fluvial and lacustrine conditions. Minor marine ingressions may have occured as these are known in the Otway basin to the west. During the Paleocene-Eocene, coal deposition was widespread in what appears to have been a dominantly alluvial basin.

- The major hydrocarbon indications have been found closer to the basin depocenter. The Pelican gas/oil field is located on just such an intra-basin structure. Whereas previous interpretation have correlated the Pelican structures with those along the southwest margin of the basin, this new structural model correlates them across transform-like faults with the major blocks near Aroo #1 and Bass #3, in the basin center. The coincidence of an Early Cretaceous tilt block with a thick Late Cretaceous to Paleocene source section is now regarded as being highly prospective, and play concepts have been developed accordingly.

BASS BASIN EVOLUTION

The Bass and Gippsland basins are excellent examples of aborted, or failed rifts. Crustal extension during the Cretaceous developed a high relief, rifted terrane of graben and half-graben depocenters filled during the Early Cretaceous with volcanogenic detritus under fluviatile and alluvial conditions. In the Bass Basin the rift system trends NW-SE. In the northwest half of the Bass Basin most rift faults are downthrown to the southwest, forming a series of half-grabens with similar polarity. In the southeast half, rifting was more complex with two rift sequences of different trends.

Worldwide, aborted rifts are ideal environments for occurences of hydrocarbons. The combination of high quality source rocks and optimum thermal history allow for above average productivity on a volumetric basis. Good examples of aborted rifts include the Gippsland basin, the Dampier basin, Vulcan graben and the Viking graben. All of these examples developed through a two-stage evolution. The stages are:

1. Crustal upwarp and extensional rifting
2. Post-rift sag

Large reserves in aborted rifts are generally found in sediments of the first phase. The boundary between the rift and sag phase in the Bass Basin is not clearly understood and is tentatively placed at the base Tertiary.

Exploration to date in the Bass Basin has concentrated on sediments of the second phase (Tertiary sag phase). Results have been disappointing. Continued exploration must be directed towards understanding the Pre-Tertiary rift phase.

223012

BUREAU OF MINERAL RESOURCES, GEOLOGY & GEOPHYSICS

CNR CONSTITUTION AVENUE AND ANZAC PARADE, CANBERRA
Postal address: P.O. Box 378, Canberra City, A.C.T. 2601
Please address all communications to the Director

Telephone: 49 9111
Telegrams: BUROMIN
Telex: 62 109

Department of National Development and Energy

In reply please quote:

BASS STRAIT MARINE GEOPHYSICAL SURVEY 1982

1. Shot point location maps as per diagram:




Figure B

Since 1982, the BMR has recorded 3200kms, Figure B, of seismic in the the Bass Basin as part of a study designed to understand the early basin evolution.

Figure C shows the location of six BMR geoseismic traverses, in a northeast-southwest direction, across the Bass Basin. Line drawings based on these traverses are shown in Figure D. Portions of lines 16, 17, and 18 lie in Permit T-19-P. The sections are colored to reflect the two phase evolution characteristic of aborted rifts. Figure C is also a plan view of the major Pre-Tertiary rift faults developed in the Bass Basin. The rift faults are offset by a series of north northeast trending, dextral transverse faults which allowed different directions of tilt blocks to develop and permitted variations in stretch of the brittle lithosphere. The Mornington - King Island fault which trends north northeast through T-19-P may have initially developed as one of these transverse faults.



144°
146°
148°
WEAVER EXPLORATION PERMITS
BASS STRAIT AREA
MELBOURNE
38°
VICTORIA
GIPPSLAND BASIN
ESSO-B.H.P.
TORQUAY BASIN
HKI FAULT
OTWAY BASIN
16
BASSIAN RISE
VICTORIA
TASMANIA
T-19-P
18
KING ISLAND
FLINDERS ISLAND
40°
PELICAN FIELD S.I.
19
20
200m
200m
LAUNCESTON
CONTINENTAL SHELF
BMR Seismic
Oil Field
Gas/Cond. Field
Gas Field (Shut In)
S.I.
TASMANIA
42°
5 cm
SCALE
0 50 100 km.
0 50 miles
223014
HOBART
AUSTRALIA

Figure C

223015




Figure D

STRUCTURAL FRAMEWORK

Permit T-19-P lies at the northwestern end of the Bass Basin. Its tectonic style is unique as compared to the rest of the Bass Basin. This is due to the influence of the Mornington - King Island fault.

Movements on the NNE - SSW trending Mornington - King Island fault commenced in the Oligocene and persist through today as indicated by earthquake pattern studies and available reflection seismic data. This movement is interpreted to be a combination of right lateral wrenching and uplift, and has overprinted early northwest-southeast trends established during initial basin evolution. Both of these trends have to be understood individually in order to remove the effects of the Mornington - King Island fault and resolve the early basin history.

Rifting in T-19-P commenced in the Early Cretaceous.

The Early Cretaceous fault geometry recognized from the BMR data demands significant crustal extension, in contrast to the largely vertical movements previously proposed. The faults are planar, with shallow to moderate dip, generally to the south-southwest, and produce a tilt of the basement surface of up to 40 degrees. This "domino-style" rotational faulting resulted from a south southwest-north northeast upper crustal extension of 50% to 70%.

This "half-graben" style of rifting allowed for the development of deep Pre-Tertiary depocenters which may contain an adequate source and reservoir rocks section. Such depocenters are recognized in Permit T-19-P and are illustrated on Figure D and Map 1. They lie between prominent horst blocks

established during Early Cretaceous crustal extension. The main depocenter lies approximately 30kms southwest of Konkon #1 and is approximately 20kms wide. Additional subsidiary depocenters lie to the northeast and southwest. The area within this depocenter is considered to be the most prospective area and therefore mapping efforts have concentrated on this portion of Permit T-19-P.

Three geoseismic cross-sections have been constructed across this portion of Permit T-19-P to illustrate the tectonic style, and the relative depths of the three depocenters (Figures 1, 2, and 3.)

Sections BB' and CC' cross the Mornington - King Island fault. The area to the west of the fault, including a portion of the Pre-Tertiary depocenter has been uplifted since the Oligocene. In addition, some degree of wrenching has occurred along the fault. Due to the complexity of these movements, seismic resolution below the Eastern View Coal Measures west of the fault is poor. Calculations indicate between 1400-2500 feet of uplift has occured, west of the fault, since the Oligocene.

GEOSEISMIC CROSS SECTIONS

Regional seismic mapping by Exploration Associates International indicate that a portion of permit T-19-P is occupied by a central graben area bounded to the northeast and to the southwest by half grabens area. To the west is the Mornington - King Island Rise. The remainder of the permit area is mostly occupied by a condensed stratigraphic section.

These major structural elements as well as the prospective lead areas are shown on Map 1. So are the location of the geoseismic cross-sections AA', BB', CC', Figures 1, 2, 3, and the location of the representative seismic lines, Figures 4 to 14. Prospective leads are associated with each of the major structural elements.

The geoseismic cross-sections are based on several seismic lines. The Eastern View Coal Measures and Lower M. diversus reflector horizons are shown. The stratigraphic section below the Lower M. diversus seismic horizons is considered the most prospective.

Geoseismic cross-section AA', Figure 1. trends northeast - southwest. To the left, or southwest, is the Mornington - Kind Island Rise which is bounded to the east by a major basin forming growth fault. The Manatee prospective area occupies the western portion of the central graben. The Mornington-King Island right-lateral, down-to-the east, transverse fault is a late, essentially north-south trending feature which cuts across the countryside regardless of pre-existing structures and relief. To the northeast is the central graben boundary fault. Further northeast, and upthrown, is a half graben and the prospective Seal area. On the basis of reconstruction, the central graben was originally strongly dipping to

the west. Back-up rotation and uplift took place at Lower M. diversus unconformity time, and later, along the central graben southwest-west boundary fault and Mornington - King Island hinge fault.

Geoseismic cross-section BB', Figure 2. also trends northeast - southwest. To the left, or southwest is the Mornington - King Island Rise which is bounded to the east - northeast by a major basin forming fault. The northwest trending propective Penguin and South Penguin horst block leads are identified. The north - south trending prospective Penguin II horst blocks is also identified. It is bounded to the east and separated from the Penguin lead by the Mornington - King Island Fault. To the north-east is the central graben area within which an area of closure is mapped outside of Permit T-19-P area. Further northeast is the central graben boundary fault and the upthrown prospective Seal area. The remainder of the cross-section shows a condensed stratigraphic section and a half graben area where the Konkon #1, Toolka #1A and Cormorant #1 wells are located. These wells recovered modest amounts of gas and oil, however, they are considered marginally relevant to the play since they are not located within the central graben area, where, according to the recent BMR studies, the most prospective section was deposited.

Geoseismic cross-section CC', Figure 3. trends northeast - southwest. To the left, or southwest, is a tilted horst block on which a yet unnamed lead has been mapped. Follows a northeastward tilted graben within which a yet unnamed lead has also been mapped. The Penguin and South Penguin tilted horst block separates this tilted graben from the central graben to the northeast. The Bass #3 well which tested both gas and oil is located on a tilted fault block which is on trend and may be closely related to the Penguin

horst block. The Aroo #1 well is located within the central graben area. Several sand intervals with fluorescense and cut fluorescense associated with wet gas on the mud log have been recognized. To the northeast of the central graben is a half graben area also shown on cross-section BB'. The Seal area is located at the prospective upthrown edge of the major graben boundary fault. The Bass #1 well is located outside of the main graben on what appears to be a tilted fault block. The BMR geochemical and paleo-heat flow study indicates that the entire Bass #1 Paleocene Late Cretaceous section falls precisely within the oil window. The northeast half graben is bounded by a major basin forming fault. Further to the northeast in a severely condensed stratigrapic section.

223021

STRATIGRAPHY

The nearest wells to Permit T-19-P are the Konkon #1, Toolka #1A, Cormorant #1, Aroo #1 and Bass #3. Other wells drilled in the Bass Basin are also relevant, however the distances from the permit area are such that stratigraphic/structural relationships are at best difficult to establish. Map 1.

The main sources of stratigraphic information for the permit are the well completion reports and Mr. Felix Roland Aquing masters dissertation on the Geology of the Eastern View Coal Measures - Bass basin, 1980.

The time-stratigraphic sub-divisions, thicknesses, net sand thicknesses, percent sand and sand-shale ratio are summarized on Figures E, F.

The following were taken from the Aquing dissertations. It should be kept in mind that this study is by definition based on the areas of high density of data, the southeast area, and that consequently the conclusions are a bit stretched in regard the central graben and flank horst blocks areas found on Permit T-19-P. Nevertheless:

- Source - rock analyses and the depositional history of the basin indicate that the northwest part of the basin has the greatest oil-potential. Page 2.

- An abundance of good quality reservoir sands occur throughout the Eastern View Coal Measures, the overlying marine "Upper Eocene Shale" and Oligocene marine shales are capable of forming regional seals. Page 2.

- Abruptly overlying the Eastern View Coal Measures is the dark chocolate brown marine "Upper Eocene Shale" or Demon's Bluff Formation.

	Upper E. asperus				Middle E. asperus				Lower E. asperus				E. asperoides				Upper E. divarus				Middle E. divarus				Lower E. divarus				Upper L. balmei				Lower L. balmei				T. lemurs				Upper T. pachyexinus - Lower T. pachyexinus				Lower Cretaceous	
	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top (Driller's Depth)	Total Thickness	Net Sand Thickness	% Sand	Sand/Shale Ratio	Top Upper Balmei Shale	Top Upper Balmei Sandstone	Top Eocene Tiger Shale	Total Eocene Tiger Shale Thickness Penetrated	Total Net Sand	% Sand in section penetrated	Sand/Shale Ratio
ABC-1	3633'	358'	0'	0.0	0.0	3987'	821'	178'	21.7	0.2	6908'	785'	458'	58.3	1.7	7633'	1184'	343'	28.9	0.4						8733'	823'	96'	11.7	0.1	8970'	111'	0'	0.0	0.0	[illegible]	1253'	368'	29.5	0.5						6118'	618'	6788'	3603'	1367'	37.9	0.6
BASS-1	4873'	602'	0'	0.0	0.0	5475'	847'	134'	17.6	0.2	6162'	618'	383'	62.0	1.6	6780'	765'	373'	48.9	1.0	7343'	734'	87'	13.5	0.2																					5377'	119'	5896'	1881'	919'	50.5	1.1
BASS-2	3290'	278'	198'	71.2	2.5	3568'	411'	161'	39.1	0.6	3979'	383'	248'	65.0	2.0	4362'	133'	91'	68.4	2.8						4706'	806'	138'	76.7	3.4	4918'	438'	383'	73.7	2.9	5330'	161'	104'	64.6	2.0						3618'	220'	3838'	1673'	1170'	69.9	2.6
BIOL-3	4207'	383'	0'	0.0	0.0	4590'	943'	193'	20.6	0.3	5535'	476'	211'	84.5	7.1	6011'	134'	110'	82.1	4.6	6143'	253'	199'	78.7	3.9	6398'	82'	53'	64.6	1.9						6480'	203'	87'	42.4	0.7	6615'	563'	221'	39.3	0.6	7048'	582'	455'	74.7	3.0	4734'	270'	5304'	8506'	1711'	67.7	2.1
CORONARIT-1	3002'	363'	0'	0.0	0.0	3363'	695'	23'	2.0	0.0	4260'	906'	532'	66.8	2.1	5066'	1342'	618'	63.9	1.8	6412'	738'	97'	10.8	0.2	7120'	1310'	63'	3.3	0.0	8728'	1112'	48'	4.3	0.0											3500'	268'	4280'	5317'	1338'	23.8	0.4
DUSKY-1	4490'	879'	118'	48.3	0.7	4769'	903'	458'	50.1	0.8	5678'	802'	478'	58.9	2.6	6476'	2061'	89'	39.6	1.6	6708'	226'	97'	43.3	2.3	6994'	246'	133'	54.9	1.4	7170'	776'	309'	39.8	0.7	7946'	766'	883'	36.9	0.6	8712'	896'	256'	86.3	0.4						4980'	540'	5320'	4283'	1950'	44.5	1.0
DURROON-1	Base	Below																																																
EDWARDS-1	2885'	465'	98'	20.7	0.3	3350'	635'	162'	37.2	0.6	3765'	165'	97'	66.5	2.0	3910'	255'	171'	67.1	2.0	4168'	191	28'	14.7	0.2	4359'	91'	0'	0.0	0.0	4450'	40'	7'	17.5	0.2	4450'	160'	0'	0.0	0.0	4630'	246'	0'	0.0	0.0	4894'	16'	4'	25.0	0.7	3039'	538'	3397'	1313'	470'	36.4	0.7
HANGERO-1	5183'	393'	83'	21.2	0.3	5515'	987'	276'	28.0	0.4	6502'	570'	329'	59.3	1.8	7032'	662'	297'	44.9	1.1	7734'	179'	33'	23.7	0.3	7873'	227'	76'	32.6	0.4	8100'	452'	203'	44.9	0.9	8552'	668'	272'	30.6	0.5						3748'	-16'	6158'	3282'	1442'	43.2	0.8
KARINA-1	4917'	381'	17'	4.5	0.0	5298'	892'	164'	18.4	0.2	6190'	1063'	714'	67.2	2.2	7253'	359'	304'	84.1	2.8	7612'	375'	116'	30.9	2.7	8367'	823'	374'	45.4	0.9	9210'	1793'	611'	34.1	0.5											3428'	-57'	5685'	5118'	2643'	51.6	1.1
PELICAN-1	5044'	561'	66'	12.2	0.1	5205'	892'	303'	33.9	0.5	6097'	538'	342'	63.5	2.1	6633'	822'	341'	41.5	2.6	7437'	653'	257'	39.4	0.7	8110'	814'	408'	50.1	1.1	8926'	1416'	516'	36.4	0.6	10340'	884'	8'	9.1	0.1						3364'	446'	5760'	4468'	2514'	49.6	1.1
PELICAN-2	4924'	582'	36'	9.4	0.1	5306'	828'	303'	32.7	0.5	6235'	611'	383'	63.0	2.0	6843'	830'	494'	59.4	2.0	7677'	679'	266'	37.1	1.5	8356'	863'	323'	37.4	0.6	9219'	847'	230'	27.4	0.4											3490'	253'	5683'	6181'	2063'	49.3	1.1
PELICAN-3	4917'	367'	31'	8.4	0.1	5284'	568'	351'	19.0	0.4	6252'	463'	284'	61.3	1.8	6715'	520'	115'	22.1	0.3	7235'	275'	168'	61.4	1.1	7510'	188'	110'	58.5	1.3	7698'	857'	180'	15.9	3.2	7737'	345'	130'	35.6	0.6	8300'	1221'	472'	38.7	0.6						3464'	379'	3863'	3658'	1716'	46.9	0.8
POCKBARK-1	5173'	389'	82'	21.1	0.3	5564'	976'	310'	31.8	0.5	6540'	672'	382'	56.8	1.4	7213'	307'	243'	80.2	3.2	7720'	66'	45'	33.0	1.7	7816'	252'	106'	42.1	0.8	8138'	650'	273'	42.0	0.7	8788'	842'	115'	67.5	0.9	9630'	1064'	728'	45.3	0.8	10636'	[illegible]	18'	22.8	0.3	3756'	451'	6237'	6308'	2230'	49.9	1.1
TAROOM-1	5078'	394'	0'	0.0	0.0	5472'	874'	173'	19.7	0.2	6348'	647'	482'	74.5	3.4	6993'	765'	526'	68.7	2.6	7760'	890'	206'	37.1	1.4	8650'	405'	109'	26.9	0.4																	3664'	446'	6110'	4965'	1784'	60.6	1.7
TOOLEA-1	3570'	390'	66'	11.8	0.1	3960'	836'	73'	3.0	0.0	4796'	783'	443'	36.6	1.6	5579'	401'	162'	35.4	0.8	5980'	389'	30'	7.7	0.1	6369'	471'	62'	13.2	0.2	6840'	1124'	54'	3.1	0.0											3622'	1150'	4812'	3738'	721'	19.3	0.2
TORONI-1	3861'	883'	130'	63.6	0.8	4144'	752'	458'	60.9	1.6	4898'	390'	249'	63.5	2.6	5288'	339'	217'	64.4	2.8	5647'	146'	95'	65.1	2.8	5793'	332'	221'	66.6	2.4	6125'	363'	220'	60.6	1.6	6488'	813'	437'	53.6	1.2	7303'	693'	296'	36.7	0.6						4271'	253'	4526'	3478'	2033'	58.5	1.6

	Upper P. asperus	Middle P. asperus	Lower P. asperus - Upper L. balmei	Lower L. balmei	T. lemurs	T. lilli ..	E. eocenica	Upper T. pachyexinus - Lower T. pachyexinus	C. striata/ C. directocostatus	Lower Cretaceous
DURROON-1	13007' 150' 150' 100 0.0	16507' 620' 594' 93.8 15.2	[illegible]	20709' 1084' 953' 87.8 7.2	21567' 538' 438' 78.4 3.6	22159' 643' 443' 68.7 2.2	23507' 135' 120' 88.9 8.0	[illegible]	24955' 270' 11' 0.0 0.0	3065'

Note: (i) Volcanic rocks were not included in the calculations.


(ii) Sand/Shale ratio = $\frac{\text{Net Sand Thickness}}{\text{Total Thickness} - (\text{Net Sand Thickness} + \text{Coal Thickness})}$

01. 1453' of amygdaloidal basalt were penetrated in Lower L. balmei zone.
02. 248' of intrusive volcanic rock (syenite) were penetrated in Middle E. divarus zone.
03. 43' of olivin basalt were penetrated in Middle E. divarus zone.
04. 363' of intrusive volcanics were penetrated in Lower E. divarus zone.

TIME-STRATIGRAPHIC SUB-DIVISIONS

2230 22

Figure E



Stratigraphic chart - Bass Basin

Figure F

223023


This shale unit is very extensive and reaches a maximum thickness, over 360 meters, in an elongated through situated in the northwestern part of the basin. Figure M. Apparently, the "Upper Eocene Shale" can be traced on seismic sections into the "Torquay Embayment" across the "King Island -- Mornington High". Page 50

- The Bass basin developed in the Early Cretaceous resulting from the postulated initial break-up of the Australian and Antartic continental masses. Major fault movements produced a series of northwest to southwest trending grabens and tilted fault blocks. The environment of deposition for this section is interpreted to be upper alluvial plain including lacustrine. Page 53.

- The distribution of late Cretaceous sediments in the Bass Basin is interpreted to be much more widespread than during Early Cretaceous times as individual trough broadened and merged into a more continuous basin. Page 53.

- During the Paleocene, the basin was structurally quiescent but continued sag along the old major fault systems resulted in over 70 meters of coarse sediments being deposited near the basin margin and possibly over 900 meters of fine sediments in the basin center. Coal deposition throughout the section was limited. The basin appears to have been landlocked with braided streams flowing from the edge of the highlands to the southwest and eastward merging basinward into a broad meandering stream pattern building out into a lacustrine delta plain in the northwest, Figure G, Page 60.

- Increased tectonic activity during the Lower Eocene resulted in renewed movement which gave rise to a slightly smaller basin configuration




Palaeogeographic Map - Palaeocene.

5 cm

223025

Figure G



UPPER ALLUVIAL PLAIN

LOWER ALLUVIAL PLAIN

DELTA PLAIN


← SEDIMENT TRANSPORT DIRECTION

Palaeogeographic Map - Early Eocene.

5 cm


223026

Figure H



223027

Figure 1




2223028

Figure J

than that which existed during the Paleocene, Page 64. The structural movements were intensified towards the end of the Early Eocene and were accompanied by faulting, folding and local igneous intrusions of the older sediments. Local erosion of the early part of the section produced the unconformity which is seen at the Lower M. diversus zone level. Figure H, I, J.

- During the Middle Eocene, stream activity increased. A pattern of braided streams flowed out from the edge of the rugged basin margin, merging into a cut-and-fill secondary stream channel system which built out over extensively developed coal swamps. This section is characterized as having both the highest sand content and the highest coal percentage within the Eastern View Coal Measures sequence. Provenance areas were located on the Tasmanian mainland in the south, the "Bassian Rise" in the east and for the first time, along the basin margin in the north and northwest. Figure K Page 65.

- The Late Eocene is dominated by the widespread deposition of the "Upper Eocene Shale". This shale unit was depositesd as a result of a marine transfression which started in the northwest and moved very rapid to the southeast. Figure L, M, N.



UPPER ALLUVIAL PLAIN

LOWER ALLUVIAL PLAIN

DELTA PLAIN

MARINE


– SEDIMENT TRANSPORT DIRECTION

Palaeogeographic Map - Middle Eocene.

5 cm

223030

Figure K




Palaeogeographic Map - Late Eocene.

5 cm

Figure L

223031



BASS BASIN
"Upper Eocene Shale" Isopach Map

Contoured in feet


—700'— Isopach

Kilometres
0 25 50 75 100
0 25 Miles 50

5 cm

Figure M

2230032



BASS BASIN

Top Upper N. asperus Zone -
Top "Upper Eocene Shale"

Isopachs and Net Sand Thickness (nearshore/ shallow marine)

~500'~ isopach

-·-150'-·- net sand thickness

Contoured in feet

Kilometres
0 25 50 75 100
0 25 Miles 50

5 cm

Figure N

2233033

WELL COMPLETION REPORTS


The following is extracted from the well completion reports. Comments are added.

The Konkon #1 well was designed to test an interpreted closed wedge (one contour closure) of M. diversus and older sediments on the flank of a large plunging nose in the northwest portion of the Bass basin. The well encountered the predicted sequence with no shows of oil or gas and was abandoned at 5043 feet in highly altered volcanic rocks. It is interpreted to have bottomed in Lower Cretaceous rocks, although no spore-pollen data were obtained from side wall cores below 4904'. The stratigraphic columns, Figure 0, illustrate the sequence encountered. The section is very condensed due to the structural position of the well.

basal Oligocene Sand	2920' - 3040'
Eocene Shale	3040' - 3980'
Interpreted sand facies of the	
Eocene Shale	3595' - 3860'
EVCM	3860' - 4910'
Cretaceous	4910' - TD.

The sand facies of the Eocene shale is interpreted to be of local development. The shaly and coaly Eastern View Coal Measures section indicate a starved basin area. Figures G, H, K, L.

The Toolka #1 A well was designed to evaluate a rather ill-defined separate closure on trend and to the northwest of the Cormorant #1 well. The primary objective was the middle Eocene sands which contained oil and gas condensate at Cormorant #1. Structural growth was during the Oligocene - Miocene. Minor oil and gas shows were encountered in the Middle Eocene



2230035

Figure 0

TOOLKA No. 1-A

K.B. 32'
G.L. 258'

223036




Figure P

while drilling, but F.I.T. test results were negative. Several hundred feet of the Upper Eastern View sand was silted out. The stratigraphic column, Figure P, illustrates the sequence encountered.

basal Oligocene Sand	3560' - 3622'
Eocene Shale	3622' - 4810'
EVCM	4810' - TD

The well tested a late formed structure, Oligocene-Miocene located in a starved basin characterized by shale and coal sedimentation. Figures G, H, K, L.

The Cormorant #1 well was designed to test the uppermost Eocene sands of the eastern View Coal Measures sectin on an outiclinal closure of Oligocene - Miocene age. The anticlinal closure was encountered as predicted, however the uppermost sands contained salt walt. If the overlying Demon's Bluff shale is assumed to be capable of forming a seal then it would appear that structural growth necessary to trap hydrocarbons in the uppermost sands occured too late. Significant hydrocarbon indications were encountered and are listed.

4918' - 4924'	6' Oil
5990' - 5996'	6' Gas
6585' - 6592'	7' Gas
7458' - 7464'	6' Gas
7690' - 7698'	8' Gas
4273' - 4274'	Fluorescense, cut. odor
4620' - 4820'	Fluorescense
4900' - 4934'	Fluorescense, cut
4934' - 4963'	Fluorescense, cut
5513' - 5543'	Fluorescense, cut, odor
6004' - 6010'	Fluorescense, cut, odor, stain
7140' - 7170'	Fluorescense, cut
8620' - 8650'	Pinpoint fluorescense
8680' - 8683'	Spotty fluorescense, cut
8683' - 8707'	Spotty fluorescense, cut
9030' - 9040'	Spotty fluorescense, cut
9070' - 9080'	Spotty fluorescense, cut
9128' - 9180'	Spotty fluorescense, cut

CORMORANT #1

223.038




FIGURE Q

Thirteen F.I.T. were taken, the results are as follows:

4647'	21000 cc filtrate, 1000 cc mud
4703'	Lost Packer Seal
4711'	20000 cc filtrate, 150 cc mud 7.2 cubic feet gas
4922'	3.2 cubic feet gas, 20000 cc oil dark brown, 22° API
5033'	Lost Packer Seal
5644'	3500 cc filtrate, 1500 cc mud, 0.6 cubic feet gas
6003'	21.000 cc filtrate, 1000 cc mud, 0.8 cubic feet gas
6586'	Misrun
6588'	4000 cc mud, trace oil
6589'	0.6 cubic feet gas, 230 cc mud
7456'	0.7 cubic feet gas, 8000 filtrate. 0.1 cubic feet gas
7462'	Misrun
7694'	1.6 cubic feet gas, 20044 cc filtrate and water, scum of oil

The stratigraphic column, Figure Q, illustrates the sequence encountered.

basal Oligocene Sand	3475' - 3900'
Eocene Shale	3900' - 4275'
EVCM	4275' - TD.

The well tested a late formed structure, Oligocene - Miocene, located in a starved basin characterized by thin sands, shale and coal sedimentation. Figures G, H, K, L.

The Aroo #1 well was located over a major northeast-southwest trending basement ridge above which closure had been mapped at three levels interpreted to lie some 2000' to 10,000' below the top of the Eastern View Coal Measures. The deep basins proper lie to the southeast of this ridge and there are a

series of distinct depressions to the northwest. These sub-basins appear to be faulted and reflect structural growth of the ridge throughout the upper Cretaceous. A major northwest-southeast fault to the east of the Aroo structure cuts through the Eocene section. Thickenning of the section, on the downthrown, northeast side of the fault is interpreted to be of the order of 2000 feet of interbedded sediments. The orientation of this fault, and several smaller ones in the Aroo area is parallel to the main basin forming tensional fault system which created this basin.

The stratigraphic column consist of the followig:

basal Oligocene Sand	absent
Eocene Shale	5925' - 6723'
EVCM	6723' - TD
Interbedded volcanics of Paleocene or pre-Paleocene Age	10327'- 12112' TD.

Hydrocarbon indications have been recorded over the following intervals:

Samples:

6950' - 6960'	Fluorescense
8878'	Fluorescense
9447'	Fluorescense
9451'	Fluorescense
9180'	Fluorescense
9514' - 9918'	Fluorescense
10703' - 10886'	Fluorescense

Sidewall Cores:

6944'	Pinpoint Fluorescense
8878'	Fluorescense, cut
9180'	Fluorescense, cut
9447'	Fluorescense, cut
9451'	Fluorescense, cut
9651'	Fluorescense, cut

Cores

9515' - 9551'	Fluorescense, cut

The Aroo #1 well tested a late formed structure related to a northeast-southwest trending volcanic build up associated with a fault. Much of the objective section was not deposited and/or removed by erosion due to local uplift. The well appears to be upthrown to one of the major basin forming faults which borders the central graben area. Figures G, H, K, L.

The Bass #3 well was drilled on the crest of a seismically defined northwest-southeast anticlinal feature.

With the exception of basement, the various formation tops ran consistently low to prediction. This was entirely due to the fact that the velocities of the various rock units were slightly greater than originally predicted. The stratigraphic sequence is as follows:

basal Oligocene Sand	4720' - 4735'
Eocene Shale	4735' - 5305'
EVCM (transitional)	5305' - 5590'
Unconformity	5590'
EVCM	5590' - 7830'
Probably unconformity	7070'
Basement	7830' - 7978' TD

An F.I.T. was taken at 6740'. It recovered 29 cubic feet of gas, 800cc of condensate and 12500 cc of discolored water. The recovered water was mud filtrate.

Regional structural trends and paleogeographic maps, Figures G to N indicate that the Bass #3 well tested on upthrown tilted fault block on the southwest flank of the central graben area recognized on Permit T-19-P. Well results may be relevant to the evaluation of the Penguin horst block trend.

LEADS

Several structural anomalies, leads, have been identified and additional seismic data acquisition is recommended to confirm and measure their structural closures.

MANATEE

The Manatee anomaly was originally recognized on seismic line PB-81-12, Figure 6. where strong reflector at 1.400 to 1.600 seconds dips westward below a major unconformity overlain by east dipping reflectors. The general area has been mapped at the Top Eastern View Coal Measures seismic horizon level, Map 2., the Lower M. diversus seismic horizon seismic level, Map 4. and at a pre-Lower M. diversus seismic horizon level shown on the Dip Rate map, Map 8. An isochron from the top of the Eastern View Coal Measure to the Lower M. diversus seismic horizon has also been constructed Map 6. The most significant map level is the pre unconformity - Dip Rate - map which shows the geometry of the prospective Early Eocene, Paleocene and older section against the western basin border fault. Map 8.

The anomaly area lies along the western margin of the main Early Tertiary and pre-Tertiary Bass Basin depocenter and appears to be associated with a major basin forming, down-to-the-east, growth fault. Westward expansion of the prospective section is recognized. It lies both to the east and to the west of the Mornington - King Island fault and has therefore been influenced by the early rifting tectonics as well as the later movements of this fault. Differential uplift, tilting, deformation and faulting caused the Manatee area to be broken in several fault blocks. At the lower M. diversus seismic time structure map level, Map 4. it is divided in six separate, but related, leads.

The Manatee I lead is a tilted fault block against a down-to-the-east basin forming fault. It is illustrated by seismic line PB-82-25, Figure 5.

Relief: 0.950 to 1.200 seconds
Area : 3700 acres

To the east is the Manatee II lead which also is a tilted fault block against a down-to-the-east fault. It is illustrated by seismic line PB-82-25, Figure 5. and seismic line PB-81-12, Figure 6.

Relief: 1.150 to 1.375 seconds
Area : 6000 acres

To the south is the Manatee III lead. It also is a tilted fault block against a down-to-the-east and northeast fault. It is illustrated by seismic line PB-81-12, Figure 6.

Relief: 1.050 to 1.375 seconds
Area : 3900 acres

To the north is the Manatee IV lead which is a minor rollover closure illustrated by seismic line PB-81-10, Figure 4.

Relief: 1.125 to 1.175 seconds
Area : 2300 acres

A strong reflector at 1.600 seconds shows approximately 60 msec of critical west dip. This event and others below it indicate the presence of a thick Paleocene and older prospective section. These four leads are all located on the upthrown side of the Mornington - King Island fault.

To the east and downthrown of the Mornington - King Island fault are the Manatee V and VI leads. These are illustrated by seismic line PB-82-25, Figure 5 and B-71A-44-S, Figure 12. These leads lie within the Early and pre-Tertiary depocenter and consist of faulted domal features.

V Relief: 1.600 to 1.625 seconds
Area : 2700 acres

VI Relief: 1.575 to 1.600 seconds
Area : 1000 acres

The pre-unconformity section at Manatee has been studied and a Dip Rate Map has been constructed. The major basin forming fault and subsidiary down to the east faults are shown. A large faulted domal feature with significant west and north dip is shown to occupy the Manatee I, II and III leads area mapped at the Lower M. diversus seismic horizon level. Its area of closure is 12000 acres. The Manatee IV lead area is shown to be underlain by an eastward tilted horst block. The two separate closures have an area 1000 acres. The Manatee V and VI leads area is a domal feature with an area of closure of 3900 acres.

The seismic time structure map constructed at the top Eastern View Coal Measures, Map 2. shows mostly regional dip, to the east, over the Manatee area. The basin forming fault is recognized locally and so is the Mornington - King Island Fault. A significant reduction in the rate of dip is shown in the area east of the Mornington - King Island Fault. A minor area of closure is shown over the Manatee V lead.

The isochron top Eastern View Coal Measures to Lower M. diversus seismic horizons shows a thickening of the section to the east of the major basin forming fault, Map 6. This isochron interval is mostly not sensitive to the major period of expansion of the section which took place at pre-unconformity time as shown by the Dip Rate Map, Map 8.

PENGUIN

The Penguin anomaly trend lies along the southwest margin of the central graben area from which it is separated by the major basin forming fault.

This positive trend is best illustrated at the Lower M. diversus seismic horizon map level, Map 2. At this level a northwest-southeast trending horst block is divided into two separate closures, the Penguin and South Penguin leads. To the northwest, up dip, the Penguin lead terminates, with rollover, against the Mornington - King Island Fault. West of the Mornington King Island Fault is the north-south trending West Penguin lead, and the northwest Penguin lead. Although these four leads share a name, it is obvious that their structural evolution was significantly different.

The Penguin lead is a northwest trending horst block which terminates with rollover to the northwest against the north-south trending Mornington-King Island fault. To the southeast it opens to the deep and expanded section of the central graben area, Figure 7., 13.

Relief: 1.300 to 1.650 seconds
Area : 12500 acres

The South Penguin lead also trends to the northwest. It is down dip and separated from the Penguin lead by its northeast boundary fault, Figure 13. This lead is mostly located on the Permit to the east and south of Permit T-19-P.

Relief: 1.600 to 1.700 seconds
Area : 16900 acres

The west Penguin lead is a north-south trending horst block separated from the Manatee anomaly by the basin forming fault. It is related and

separated from the Penguin lead by the Mornington - King Island fault, Figure 7. and Figure 5. illustrate this lead.

Relief: 0.900 to 1.300 seconds
Area : 11000 acres

The northwest Penguin lead is a horst block located to the west of the basin forming fault. A condensed stratigraphic section is expected.

Relief: 0.800 to 0.900 seconds
Area : 5700 acres

The Penguin anomaly area is recognizable at the level of the Dip Rate map. It is upthrown to the major basin forming fault to the east and northeast. It is also upthrown to the boundary fault of a subsidiary graben to the southwest. To the southeast, the horst block plunges basinward and therefore is connected to the generative area of the Bass basin.

The Penguin anomaly area is also recognizable of the level of the Top Eastern View Coal Measures map. Short segments of the boundary faults have been mapped. The Penguin and South Penguin horst blocks are shown as a broad southeastward plunging high. A small rollover closure is mapped at the intersection of the Penguin horst block with the Mornington - King Island fault. Another small closure is mapped at the intersection of the basin forming fault and the west fault of the West Penguin lead.

The isochron map - Top Eastern View Coal Measures to Lower M. diversus seismic horizon level - shows a very distinct area of thinning over the Penguin, South Penguin and West Penguin trend. It is flanked to the northeast and the southwest by isochron thick areas.

223047

SEAL

The Seal anomaly lies along the northeast boundary area of the central graben. This horst block is well displayed at the Lower M. diversus seismic horizon map level, Map 2. Two upthrown closures against separate faults have been identified in the basinward area. These leads are illustrated by Figure 7., Figure 11., Figure 10., Figure 9., and Figure 4. Two apparently separate closures constitute the Seal lead.

Relief: 1.400 to 1.450 seconds
Area : 4500 acres

The southwest Seal lead has a very small area of closure at this map level.

The Seal leads are well recognized at the level of the Top Eastern View Coal Measures horizon map. A large closure overlies the two separate Lower M. diversus closures. The southwest Seal lead area also displays a significant domal closure at this map level.

The isochron map - Top Eastern View Coal Measures to Lower M. diversus seismic horizon level - shows a distinct area of thinning over the Seal lead area.

223048

EASTERN AREA

The area of the permit to the east of the Manatee, Penguin and Seal anomalies has also been mapped at the Lower M. diversus seismic horizon level maps, as well as at the Top Eastern View Coal Measures seismic horizon level, Map and Map 3. An isochron - Top Eastern View Coal Measures to Lower M. diversus seismic horizon - has also been constructed, Map 7. A number of leads have been identified. These leads are not described and seismic acquisiton is not recommended at this stage.

REPRESENTATIVE SEISMIC LINES

Seismic lines of different vintages and scales illustrate the geometry of the leads as well as the resolution and penetration of the seismic signal in various areas of the permit area, Figures 4 to 14. The reflectors are color coded: top Eastern View Coal Measures is purple and the Lower M diversus horizons is red. The other colors serve to highlight organized bands of energy.

Figure 4 is an east-west line acquired by Perthshire in 1981. It illustrates the Manatee IV lead which is located within the central graben area. The major basin forming listric growth fault is shown. Simple rollover is recognized at various levels.

Figure 5 is an east-west line acquired by Perthshire in 1982. It illustrates the Manatee I, II, IV and V leads which are located within the central graben area. The major basin forming fault, the unconformity and the Mornington - King Island Fault are shown. West dip is recognized below the unconformity.

Figure 6 is on east-west line acquired by Perthshire in 1981. It illustrates the Manatee II and III leads which are located within the central graben area. The major basin forming fault, the unconformity and the Mornington - King Island Fault are shown. West dip is recognized below the unconformity.

Figure 12 is a northwest-southeast line located entirely within the central graben area. It illustrates the Manatee V lead. Dip to the northwest is recognized.

Figure 7 is a southwest-northeast line which strikes across the basin. West of the Mornington - King Island Fault is the West Penguin lead followed by the Penguin lead, the central graben area and the Seal anomaly area. Further to the northeast, the section is very condensed.

Figure 13 is a northwest-southeast line which illustrates the rollover of the Penguin lead and the Mornington - King Island Fault.

Figures 8 and 9 are northeast-southwest dip lines which illustrate the Seal leads area.

Figures 10 and 11 are northwest-southeast strike lines which illustrate the Seal leads area.

Figure 14 is a northeast-southwest dip line which illustrates an unnamed lead far removed from the main Teritary and pre-Teritary depocenters.

223051

ENCLOSURE

- New Paleocene/Cretaceous plays in the Bass Basin - A "Bright Spot" in Southeast Australia.

  J. C. Branson, M. A. Etheridge, D. A. Falvey, K. L. Lockwood, A. S. Scherl, P. G. Stuart-Smith.

223052

FIGURES (TO FOLLOW)

1. Geoseismic Section AA'

2. Geoseismic Section BB'

3. Geoseismic Section CC'

4. Seismic Line PB-81-10 M Sp 660-1380
   Manatee/Seal area

5. Seismic Line PB-82-25 Sp 61-617
   West Penguin/Manatee Area

6. Seismic Line PB-81-12M Sp 760-1240
   Manatee Area

7. Seismic Line B-71-A-40 Sp 8132-8266
   Penguin/Central Graben/Seal Area

8. Seismic Line EB-3 Sp 1-44
   Seal Area

9. Seismic Line EB-4 Sp 87-56
   Seal Area

10. Seismic Line B-70-A-24 Sp 9562-9784
    Seal Area

11. Seismic Line HB-75-A-156 Sp 157-409
    Seal Area

12. Seismic Line B-71-A-44-5 Sp 1954-1978
    Central Graben/Manatee Area

13. Seismic Line B-72-A-134 Sp 3655-3623
    Penguin Area

14. Seismic Line HB-75-A-179 Sp 277-139
    Southwest Area

IN TEXT

A.
1.2.3. Synthetic Seismogram Konkon #1 well

B. Bass Strait Geophysical survey 1982
   Bureau of Mineral Resources

C. Location of BMR traverses.

223053

D. Line drawings of BMR Traverses

E. Time - Stratigraphic Sub-divisions

F. Stratigraphic Chart

G. Paleogeographic Map - Paleocene

H. Paleogeographic Map - Early Eocene

I. Structure Map Upper M. diversus, Facies Trends

J. Structure Map Upper M. diversus, Hydrocarbon Trends

K. Paleogeographic Map. Middle Eocene

L. Paleogeographic Map. Late Eocene

M. Upper Eocene Shale Isopach Map

N. Isopach and Net Sand Thickness.
Top Upper N. Aspersus Zone to
Top Upper Eocene Shale
(basal Oligocene Sand)

O. Konkon #1 Stratigraphic Column

P. Toolka #1A Stratigraphic Column

Q. Cormorant #1 Stratigraphic Column

223054

MAPS

1. - Major Structural Elements and Location of Leads. 1:250.000

2. - Seismic Time Structure Map - Top Eastern View Coal Measures. West Panel. 1:50.000

3. - Seismic Time Structure Map - Top Eastern View Coal Measures. East Panel. 1:50.000

4. - Seismic Time Structure Map - Lower M, diversus Seismic Horizon. West Panel. 1:50.000

5. - Seismic Time Structure Map - Lower M. diversus Seismic Horizon. East Panel. 1:50.000

6. - Isochron Map - Top Eastern View Coal Measures to Lower M. diversus Seismic Horizon. West Panel. 1:50.000

7. - Isochron Map - Top Eastern Vie Coal Measures to Lower M. diversus Seismic Horizon. East Panel. 1:50.000

8. - Dip Rate Map - Pre Lower M. diversus Seismic Horizon. 1:50.000

9. - Aquisition Program - Showing Location of Leads and Proposed Seismic Lines. 1:50.000

223055

NEW PALEOCENE/CRETACEOUS PLAYS IN THE BASS BASIN - A 'BRIGHT SPOT' IN SOUTHEAST AUSTRALIA?

J.C.Branson, M.A. Etheridge, D.A. Falvey, K.L. Lockwood, A.S. Scherl and P.G. Stuart-Smith

223056

The Cretaceous to Recent: Bass, Gippsland and Otway Basins lie predominantly offshore in the Bass Strait region between southeast mainland Australia and Tasmania (see map). The Gippsland Basin is responsible for more than 90% of domestic crude oil production, but the Bass and Otway Basins have yet to yield a commercial hydrocarbon discovery, despite superficial similarities of stratigraphy and evolution.

In the Gippsland Basin, hydrocarbons are largely trapped in anticlinal and fault-related structures at a Late Eocene unconformity. Structures of this age are poorly developed in the Bass Basin. However, a recent review of hydrocarbon potential by BMR scientists, had demonstrated that suitable source rocks and maturation conditions existed in the Late Cretaceous to Paleocene sequence, and that plays could be developed at that level which may justify further examination.

Exploration of this deeper portion of the Bass Basin was previously hampered by relatively poor quality of seismic data generated at and below highly reflective and reverberant Eocene coal measures. In 1982, the Bureau of Mineral Resources, Geology and Geophysics (BMR) conducted a contract seismic survey using a high energy airgun source and a 3200 metre long streamer (96 channel, 48 fold). Over

223057

3200 kilometres of regional lines covering the whole basin with ties to wells and adjacent basins (Gippsland and Otway) were collected along with gravity and magnetic data. These data have opened up the deeper basin beneath the Eocene coal measures and revealed new and exciting hydrocarbon plays, as well as providing a sounder basis for understanding basin formation mechanisms.

STRATIGRAPHY

Early Cretaceous deposition filled graben and half-graben with volcanogenic detritus under fluviatile and alluvial conditions. These sediments are at least 6 km thick in the depocentres and thin to a few hundred metres or less over horst blocks and near basin margins. Seismic interval velocities and well data together with the volcanogenic nature of sediment indicate low porosity and low permeability. Slower basin subsidence prevailed in the Late Cretaceous with sediment derived from eroded Palaeozoic and Proterozoic highland regions, as well as elevated portions of horst blocks. These sediments were deposited under fluvial and lacustrine conditions. Minor marine ingressions may have occured as these are known to occur in the Otway Basin to the west. During the Paleocene-Eocene, coal deposition was widespread in what appears to have been a dominantly alluvial basin. In the latest Eocene a barrier

223058

to the northwest was over stepped by the sea. At the same time the marine influence was increasing in the Otway and Gippsland Basins. Widespread marine marls, limestones and clays were deposited in the Oligocene and Miocene. Marine carbonate shelf conditions prevail to the present day. Volcanism in the latest Tertiary gave rise to intrusives and extrusives in the upper section.

STRUCTURE

The Early Cretaceous fault geometry recognized from the BMR data demands significant crustal extension, in contrast to the largely vertical movements previously proposed. The faults are planar, with shallow to moderate dips (generally to SSW), and they produce tilts of the basement surface of up to 40 degrees. This "domino-style" rotational faulting resulted from a SSW-NNE upper crustal extension of 50% to 70%. The section shows the tilt blocks and their associated half-graben. The map illustrates the short strike extent of the normal faults, due to disruption along NNE-trending, dextral transverse faults. There is not necessarily a simple strike-slip displacement across these transverse faults (the heavily drawn fault near the basin centre is a good example), and they may therefore have essentially the same kinematic style and geometry as oceanic transform

223059

faults. In the southeastern extremity of the basin, a near symmetrical Early Cretaceous graben is overprinted by northwest trending, Late Cretaceous tilt blocks . This episode of faulting may be related to Tasman Sea spreading.

The Early Cretaceous fault and tilt blocks play a key role in the development of hydrocarbon plays. Much of the structuring in the more prospective overlying rocks results from differential compaction over and/or rejuvenation of these deep structures. Anticlinal closures over buried tilt block corners have been extensively explored along the basin margin (e.g. Dondu-1,Bass-3). However the major hydrocarbon indications have been found closer to the basin depocentre. The Pelican gas field is located in just such a ~~mid~~-basin structure. Whereas previous interpretations have correlated the Pelican structures with those along the southwest margin of the basin, this new structural model correlates them across transform-like faults with the major tilt block near Aroo-1 and Bass-1, in the basin centre. The coincidence of an Early Cretaceous tilt block with a thick Late Cretaceous to Paleocene source section is now regarded as being highly prospective, and play concepts have been developed accordingly.

223060

PLAY CONCEPTS

One example of a number of such new, tilt-block related Paleocene/Late Cretaceous plays in the vicinity of Bass-1 is illustrated. The uppermost play (1) is associated with differential compaction over the basement high and occurs in Eocene, Paleocene and Late Cretaceous sediments. In this particlar example, direct hydrocarbon indicators (D.H.I's) are observed on the synthetic sonic log/seismic trace inversion record section. They occur at multiple depths over the structure as both velocity anomalies and 'flat spots'. The origin of such D.H.I's in this basin has not been previously tested. A deeper play (2) is related to sand aprons of Late Cretaceous age associated with the horst block. Such locally elevated areas should give rise to reworked sands during horst block erosion. The global sealevel highstand in the Late Cretaceous could provide a lateral regional seal through deposition of marine ingressive clays, particularly towards the centre of the basin. A play related to possible shale diapirism (3) in the thickest parts of the Late Cretaceous section occurs on the downthrown sides of horst blocks. The Cretaceous paleolatitudes of the region argue against evaporites, whereas overpressuring, related to shale mobilisation is known to occur around Pelican-2.

223061

SUBSIDENCE AND MATURATION HISTORY

The subsidence and thermal maturation history ('geohistory') of such a new Bass Basin play have been synthesized using the seismic stratigraphy, well data from Bass-1 and an anomalous paleo-heatflow predicted by a lithospheric extension model developed by Garry Karner (now at Durham University,U.K.)

The computer generated thermal geohistory shown, was prepared for BMR by Ian Deighton (Paltech Pty. Ltd., Sydney) The analysis indicates that the entire Paleocene/ Cretaceous section falls precisely within the oil window (Ro = 0.6 to 1.3%). This is consistent with observed Eocene to Recent maturation levels in adjacent wells. Late Cretaceous and Paleocene source rocks are predicted to have commenced generation in the Miocene, after structural development of the trap. The presence of D.H.I.'s at a depth of 2 kms and above the top of the present oil window implies migration and is consistent with shows of oil observed at similar levels in Cormorant-1.

STUDIES CONTINUE

This represents just the preliminary results from BMR's Bass

223062

Basin Study. Work is continuing on other aspects of the new seismic data: a complete structural and stratigraphic synthesis of the Bass Basin; Otway and Gippsland Basin correlations; deepwater Otway and Gippsland Basin studies; and a sedimentological study including work on diagenetic processes being conducted by Monash University (Melbourne).

The majority of this survey data, including the seismic inversion sections, were released to the public between October 1983 and February 1984. The open file data includes processed record sections, digital field tapes and digital stack tapes. The total cost of this survey was $3 million.

223063

FIGURES

Figure 1. Early Cretaceous structures and sedimentary wedges (green arrows indicate thicknesses of sediment) Regional seismic traverses by BMR 1982.

Figure 2. Play concepts and an equivalent seismic inversion line near Bass-1. Bright spot at 1.55 twt.


Figure 3. Thermal history, subsidence & heatflow curves, near Bass-1 well Bass Basin.


<840223.1019>

Figure 4 Major Cretaceous Structures
Figure 5 Sketch of Regional Model of Cretaceous Lithospheric Stretching
Figure 6 Line Drawings of BMR Traverses

5 cm


223064 Fig. 1





5 cm


Fig. 2



22206

223066

Fig. 3


5 cm
TIME (m.y.)
140
120
100
80
60
40
20
0
0.5
0.6
0.7
0.8
1.0
Marine
Barred basin
Fluvial – deltaic
Fluvial – lacustrine
Alluvial
Basement
DEPTH (km)
0
1
2
3
4
5
D FALVEY / I DEIGHTON
TIME (m.y.)
HEATFLOW
2.2
2.0
1.8
1.6
1.4
DEPTH (km)

The earliest deposition within the basin was probably Early Cretaceous, say 125 m.y. as Jurassic dolerites in Tasmania do not seem to be present in the Bass Basin. Faulted tilt blocks formed wedge shaped depressions into which alluvial fans poured material from the basin margins. In the southeast around Durroon this style of faulting continued throughout the Late Cretaceous as well. The major fault patterns were approximately 200° strike. The southeastern fault pattern has a strike 320° which follows the grain of the earlier Palaeozoic. At the basin margins the interplay of 290° 320° faults gives a zig-zag edge to the Cretaceous and this form persists throughout the fluvial phases of Late Cretaceous and Paleocene (early Latrobe equivalent).

Variations in basement tilt block patterns were achieved during the Early Cretaceous by a series of transfer (like transform) faults which allowed different directions of tilt blocks to develop and permitted variations in stretch of the brittle lithosphere of the Bass Basin. We estimate that the basement was extended about 50% across the main basin center.

In a model study by Garry Karner he produced the gravity field and Tertiary sag of the Bass Basin using our tilt block style of movement lasting 20 m.y's and then allowing the lithosphere to recover over the next 20 million years. The results are still being computed for the variations in temperature in the basin center. The lower than expected maturation of the Bass Basin is also explained by Garry's model because he has taken a 2 dimensional heat flow pattern, not the normal one dimensional heat-flow commonly used. This allows heat to escape from a narrow basin along the flanking blocks and suits our Bass Basin case.

The rift filled alluvial centers of the Early Cretaceous are therefore responsible for the driving mechanism for later "sag" (lithospheric flexure) basin which formed from the Late Cretaceous through the Tertiary.

The Mornington-King Island Rise is considered to be a much younger feature than the central Bass Basin. Although the Eocene generally laps-out against the region the northeast fault system appears to cut all marine sediment up to the Plio-Pleistocene and is even to the present day. A network of seismological stations in Melbourne has provided an earthquake pattern which suggests that the north-east fault system is still active.

I am left with two important questions on the Bass Basin region:- Did the Early Cretaceous form the same wedges of alluvial sediment across the Mornington-King Island region as it does in the basin center?

If the dying phases of the fault controlled deposition in the Early Cretaceous formed restricted alluvial systems in the Late Cretaceous and Paleocene, did these fluvial systems occur over the basin flanks?

223068




Figure 4 Major Cretaceous structures

5 cm




Fig 5

Sketch of regional model of Cretaceous lithospheric stretching.

5 cm

AUSTRALIAN REGIONAL SPHEROID
TRANSVERSE MERCATOR PROJECTION

623422





Fig. 6

223070


traverses

Fig. 7




Time = Present Day (125 my. after stretch)


Lithospheric model of isotherm pattern following stretching




25m.y.



0m.y.



223071



PERTHSHIRE PETROLEUM, LTD.
PERMIT T-19-P

GEOSEISMIC SECTION A-A'

—— EASTERN VIEW COAL MEASURE - EOCENE

PALEOCENE - CRETACEOUS

SECTION BASED ON LINES ES-56 AND B72A-75

0 5 10 15
Km.

Figure 1


5 cm

OR - 208

T19 P Part 6

223072

(1)



PERTHSHIRE PETROLEUM, LTD.
PERMIT T-19-P

GEOSEISMIC SECTION B-B'

EASTERN VIEW COAL MEASURE - EOCENE

PALEOCENE - CRETACEOUS

SECTION BASED ON LINE B71A-40

0 5 10 15
Km.


5 cm

Figure 2

T/19P OR-208
Part 6

223073

(2)



223074

Figure 3

OR-208

T/19P Part 6

(3)


T/19P Part 6

OR-208

Figure 4

223075

LINE: PB-81-10M
S.P.: 100 -2469
1X4800%, TVF



EAST

WEAVER OIL AND GAS

OFFSHORE AUSTRALIA

BASS BASIN, CROCODILE ROCK

SHOT BY WESTERN GEOPHYSICAL CO. PARTY 86 APRIL 1981
PROCESSED BY WESTERN GEOPHYSICAL HOC GRP 27 JULY 1981
PLAYBACK REEL NO. 060119

RECORDING DATA

SOURCE	
ENERGY SOURCE	AIR GUNS
NUMBER OF GUNS	10
GUN DEPTH	6 METERS
FIRING INTERVAL	25 METERS
SHOT POINT INTERVAL	25 METERS
DISTANCE OF SOURCE TO ANTENNA	77.9 MTRS.

INSTRUMENTS	
SYSTEM	DFS V
AMPLIFIER	BINARY GAIN
FILTER	HSZ.5-LOUT
SAMPLING INTERVAL	4 MS.
RECORD LENGTH	6 SEC

CABLE	
TYPE CABLE	STREAMER
CABLE LENGTH	2375METERS
CABLE DEPTH	14.3 MTRS.
LEAD IN	281.7MTRS.
GROUP INTERVAL	25 METERS
NUMBER OF GROUPS RECORDED	96

PROCESSING SEQUENCE AND PARAMETERS


PROCESSING SAMPLING INTERVAL 4 MS

1. EDIT
2. DECONVOLVED BEFORE STACK
   - TYPE - MINIMUM PHASE INVERSE FILTER
   - WINDOW LENGTH 3 EQUAL ZONES
   - LENGTH OPERATOR 200 MS
   - PREDICTION DISTANCE 4 MS
3. NMO STACK 4800 %
4. TIME VARIANT FILTER

FILTER TIME	L.C. (HZ.)	H.C.
.1 SEC	15 -	50
1.0 SEC	10 -	40
1.9 SEC	8 -	30
2.5 SEC	6 -	20

5. GAIN

96 GROUP CABLE USING ALL GROUPS
SHOTPOINT LOCATION AT ANTENNA
CORRECTION TO SEA LEVEL DATUM 12 MS



LEGEND
V VELOCITY ANALYSIS
W.D. INTERSECTIONS WATER DEPTH

HORIZONTAL SCALE
80 TRACES EQUALS ONE KILOMETER
1 KILOMETER
VERTICAL SCALE
3.75 INCHES PER SECOND

POLARITY CONVENTION
RECORDING : COMPRESSION PULSE NEGATIVE NUMBER
PROCESSING : COMPRESSION PULSE NEGATIVE NUMBER
DISPLAY : COMPRESSION PULSE TROUGH (DECREASING BLACK)

5 cm

T19P Part 6

OR-208

Figure 5


223076

LINE PB82-25
S.P. 61-617

WEST
DIRECTION OF SHOOTING

AGC-STACK

SP 549		SP 469		SP 389		SP 309		SP 229		SP 149		SP 69	
TIME	VRMS	TIME	VRMS	TIME	VRMS	TIME	VRMS	TIME	VRMS	TIME	VRMS	TIME	VRMS
0	1490	0	1490	0	1490	0	1490	0	1490	0	1490	0	1490
100	1490	100	1490	100	1490	100	1490	100	1490	100	1490	100	1490
550	1700	500	1780	450	1780	500	1860	600	1860	800	1940	800	1860
1400	2340	900	2180	1200	2500	1500	2580	1400	2500	1450	2340	1100	2180
2100	2820	1600	2820	1900	3380	2200	3380	2100	3220	2100	2820	1800	2500
2700	3860	2500	3860	2700	4340	3000	4340	2900	4340	2800	3860	2250	3220
4000	5140	4000	5140	4000	5140	4000	5140	4000	5140	4000	5140	2800	4180
												4000	5140



WEAVER OIL & GAS
BASS BASIN
PERMIT T-19-P

GeoCenter

DATE PROCESSED MAY 1982
REEL NUMBER 4354
CONTRACT NUMBER 4805


FIELD RECORDING

RECORDED BY WESTERN GEOPHYSICAL
DATE FEBRUARY 1982 SYSTEM DFSV
FORMAT SEG B GAIN 36 DB

ENERGY SOURCE
TYPE AIR GUNS 760 CU. INS. 4500 PSI.
ARRAY 10 GUNS DEPTH 6 METERS

STREAMER
LENGTH 2375 METERS NO. TRACES 96
DEPTH 40 FT GROUP INTERVAL 25 METERS
ARRAY 20 GEOPH/TR OVER 25 METERS

PARAMETERS
RECORDING FOLD 4800% S.P. SPACING 25 METERS
SAMPLE INTERVAL 2 MS RECORD LENGTH 5 SECONDS
RECORDING FILTER OUT - 128HZ @ 70DB/OCTAVE



DIGITAL PROCESSING

SEQ	PROCESS	PARAMETERS
1	DEMULTIPLEX	BINARY GAIN RECOVERY OUTPUT 4 MS
2	GAIN	AMPLITUDE RECOVERY
3	CDP TRACE GATHER	4800% ADJACENT TRACE SUM
4	PRE-FILTER	SEE BELOW
5	DECONVOLUTION	SEE BELOW
6	VELOCITY ANALYSIS	CONSTANT VELOCITY STACK OVER 8 CDPS
7	NMO-MUTE	NORMAL MOVEOUT MUTE APPLICATION
8	CDP STACK	4800%
9	FILTER	SEE BELOW
10	EQUALIZATION	DATA DEPENDENT

DECON	* OPERATOR LENGTH	PREDICTIVE GAP	DERIVATION WINDOWS	APPLICATION WINDOWS	
5	160	32	0 TO 3500	RECORD LENGTH	ADDITIONAL PARAMETERS

FILTER	CUT OFF POINT	6 DB POINT	6 DB POINT	CUT OFF POINT	APPLICATION TIMES FOR SHOTPOINTS SPECIFIED			
9	12	15	56	66	2500 OVERLAP			
	4	6	32	40	0-1000			
					3500-4000			
4	4	6	56	66	RECORD LENGTH			

ALL TIMES IN MILLISECONDS ALL FREQUENCIES IN HERTZ
FILTERS INTERPOLATED LINEARLY BETWEEN APPLICATION TIMES
APPLICATION TIMES INTERPOLATED LINEARLY BETWEEN SHOTPOINTS
*OPERATOR LENGTH GIVEN IS ACTIVE LENGTH ADD GAP FOR TOTAL LENGTH

SAMPLE RATE: 4MS; DATUM CORRECTION: 13 MS

SCALES: HORIZONTAL 24 TR/IN VERTICAL 2.5 IN/SEC

RECORDING POLARITY: NEG. VALUE EQUALS PRESSURE INCREASE

PROCESSING POLARITY: POSITIVE NO. GIVES BLACK PEAK


5 cm

T/14P Part 6

OR-208 223677

Figure 6

LINE: PB-81-12M
S.P.: 100-1271
1X4800%, TVF



EAST

WEAVER OIL AND GAS

OFFSHORE AUSTRALIA

BASS BASIN, CROCODILE ROCK

SHOT BY WESTERN GEOPHYSICAL CO. PARTY 86 APRIL 1981
PROCESSED BY WESTERN GEOPHYSICAL HDC GRP 27 JULY 1981
PLAYBACK REEL NO. :081572

RECORDING DATA

SOURCE

ENERGY SOURCE	AIR GUNS
NUMBER OF GUNS	10
GUN DEPTH	6 METERS
FIRING INTERVAL	25 METERS
SHOT POINT INTERVAL	25 METERS
DISTANCE OF SOURCE TO ANTENNA	77.9 MTRS.

INSTRUMENTS

SYSTEM	DFS V
AMPLIFIER	BINARY GAIN
FILTER	HG2.5-LOUT
SAMPLING INTERVAL	4 MS.
RECORD LENGTH	6 SEC

CABLE

TYPE CABLE	STREAMER
CABLE LENGTH	2375METERS
CABLE DEPTH	14.3 MTRS.
LEAD IN	281.7MTRS.
GROUP INTERVAL	25 METERS
NUMBER OF GROUPS RECORDED	96

PROCESSING SEQUENCE AND PARAMETERS


PROCESSING SAMPLING INTERVAL 4 MS

1. EDIT
2. DECONVOLVED BEFORE STACK
   - TYPE - MINIMUM PHASE INVERSE FILTER
   - WINDOW LENGTH 3 EQUAL ZONES
   - LENGTH OPERATOR 200 MS
   - PREDICTION DISTANCE 4 MS
3. NMO STACK 4800 %
4. TIME VARIANT FILTER

FILTER TIME	L.C. (HZ.)	H.C.
.1 SEC	15 -	50
1.0 SEC	10 -	40
1.9 SEC	8 -	30
2.5 SEC	6 -	20

5. GAIN

96 GROUP CABLE USING ALL GROUPS
SHOTPOINT LOCATION AT ANTENNA
CORRECTION TO SEA LEVEL DATUM 12 MS



LEGEND
V VELOCITY ANALYSIS
INTERSECTIONS
W.D. WATER DEPTH

HORIZONTAL SCALE
80 TRACES EQUALS ONE KILOMETER
1 KILOMETER
VERTICAL SCALE
3.75 INCHES PER SECOND

POLARITY CONVENTION
RECORDING : COMPRESSION PULSE NEGATIVE NUMBER
PROCESSING : COMPRESSION PULSE NEGATIVE NUMBER
DISPLAY : COMPRESSION PULSE TROUGH (DECREASING BLACK)

5 cm

T/1gp Pat 6

223678

OR- 208
Figure 7

PENGUIN AREA

MORNINGTON-KING ISLAND FAULT

CENTRAL GRABEN

SEAL AREA

NE

SEG 24 FOLD STACK
TVD
TVF 20 - 60 Hz. 400ms.
15 - 55 Hz. 600ms.
10 - 50 Hz. 800ms.
10 - 40 Hz. 1200ms.

LINE B71A-40 HORIZONTAL SCALE 1 TRACE = 50 METRES
SCALE RATIO = 2 IN/AT 1·5 SEC

E566-34 B71A-45 B63-10 B71A-44, B71A-445 B70A-24 E865-2 B63-21

8132 8138 8144 8150 8156 8162 8168 8174 8180 8186 8192 8198 8204 8210 8216 8222 8228 8234 8240 8246 8252 8258 8264 8270 8276 8282 8288 8294 8300 8306 8312 8318 8324 8330 8336 8342 8348 8354 8360 8366

B71A-40-7

WATER DEPTHS
VELOCITIES

0·0 0·2 0·4 0·6 0·8 1·0 1·2 1·4 1·6 1·8 2·0 2·2 2·4 2·6 2·8 3·0 3·2 3·4 3·6 3·8 4·0 4·2 4·4 4·6 4·8 5·0

EVCM

L.M. DIV.

MAGNETOMETER PLOT (GAMMAS)

61900 61800 61700 61600 61500 61400

ESSO AUSTRALIA LIMITED

GEOPHYSICAL SERVICE INTERNATIONAL
DIGITAL PROCESSING CENTRE
SYDNEY, NSW, AUST.

S.P. 8096-8470

AREA: BASS BASIN LINE: B71A-40
RECORDING PARAMETERS SP: 8096 to 8470
Source: Air Gun Array type: 150 cu. in. Depth: 23 ft
4 pops/SP Shot off group: 48 Fold: 24
Cable length (centre of gp 1 to centre of gp 48): 7708 ft Near trace: 682 ft
Group interval: 164 ft Group length: 164 ft Offset: 582 ft
30 geophones/group Field polarity first break: Negative
Recording system: DFS-III Filter: 8 to 62 Hz
Recording length: 9.0 sec Sample rate: 4 ms
G.S.I. Field crew: 909 Date: Dec. 1971


PROCESSING DATA
Processed by: G.S.I. Sample period: 4 ms
TAR: B = 17 db, n = 3 Hz/sec Processed: 24 fold
Vertical stack: Odd/Even Data: 0 to 4500 ms
Decon before stack: DCN 56 ms, 4 ms, 0 ms, No. of gates/trace: 1
Decon after stack: TVD 2200 to 4500 ms, 450 ms, 4 ms, No. of anti-log: 80 ms/trace
Design gate (trace 1): 300 to 4500 ms Gate shift: 0 ms/trace
Displayed: 55 µs/ft Gain: AGC Hz
Polarity displayed: Positive (+) / Negative ■ Phase gain: 7 db
TAPE REQUEST: 481 Hold: 4307
INPUT: FORM PARITY: 407-ESP-2 Date: Feb. 1972


VES 4
NMO —
TVD —
TVS 3
DCN 256
DFS —
TVD —
DCN —
DFF 7
TVF —
700 Pkg ■

DIGITAL BAND PASS FILTERING
Hz: 60 50 40 30 20
0·0 1·0 2·0 3·0 4·0 5·0
SECONDS (TWT)

DIAGRAM
LINE
8470
8096
5 cm

DIGITAL BAND PASS FILTERING





GEOPHYSICAL SERVICE INTERNATIONAL

DIGITAL PROCESSING CENTRE
SYDNEY, NSW, AUST.

PROCESSING DATA: Sample period 4 ms.
Groups processed 1-24 Processed 6 fold.
TAR: B - 0 db., α 0 db/sec. Gate _____ to _____ ms.
Vertical stack: NIL
Decon before stack: _____ _____ pts., _____ ms. No. of gates/trace _____
Design gate (trace I) _____ to _____ ms. Gate shift _____ ms/trace.
Decon after stack: TVD 62 pts, 4 ms. No. of gates/trace 2
Design gate (trace I) 300 to 3996 ms. Gate shift 0 ms/trace.
Digital filter 35 pts., 4 ms. _____ to _____ Hz.
Display: _____ digital AGC. Playback gain 8 db.
Polarity displayed: Positive □ / Negative ■
TIAC REQ. 3097 Hold tape 6498 Date DEC. 1971
GSI INPUT CREW - PARTY 107-ESO-2

A-D	1
NMO	3
AR2	
TVD	
TVS	2
DCN	
DPS	4
TVD	6
DCN	
DGF	
TVF	7
MIX	5
600 Pkg. □	


STANDARD OIL (AUST) LTD.

AREA: BASS BASIN
RECORDING PARAMETERS: LINE: EB-3
Source EXPLOSIVE SP 1 to 88
Charge size 100 lb.
1 Chg./SP. Shot off group 12/13 No. of groups 24
Cable length (centre of gp. 1 to centre of gp. 24) 3936 ft.
Offset (Charge to centre of gp. 12/13) 250 ft.
Group interval 164 ft. SP interval 656 ft.
4 geophones/group. Field polarity first break NEGATIVE
Recording system WESTERN Filter _____ to _____ Hz.
Recording length 4000 ms. Recorded TECHNO-AM

WGC Field crew 87 Date MAY 1965

OR-208
Figure 8

5 cm



LINE EB-3 (SHORT CABLE)

SEAL AREA

223079

T1qp Part 6

(8)

(9)

223080

SEAL AREA

LINE EB - 4 (LONG CABLE)

OR-208

Figure 9

5 cm

87 86 80 74 68 62

WATER DEPTHS 0·0


VELOCITIES

← 8704-E4-31

0·2 0·4 0·6 0·8 1·0 1·2 1·4 1·6 1·8 2·0 2·2 2·4 2·6 2·8 3·0 3·2 3·4 3·6 3·8 4·0

EVCM

L.M. DIV.



ESSO STANDARD OIL (AUST) LTD.

AREA: BASS BASIN LINE: EB-4

RECORDING PARAMETERS: SP 1 to 87

Source EXPLOSIVE

Charge size 100 lb.

1 Chg./SP. Shot off group 12/13 No. of groups 24

Cable length (centre of gp. 1 to centre of gp. 24) 7872. ft.

Offset (Charge to centre of gp. 12/13) 250 ft.

Group interval 328 ft. SP interval 656 ft.

4 geophones/group. Field polarity first break NEGATIVE

Recording system WESTERN Filter to Hz.

Recording length 4000 ms. Recorded TECHNO-AM

WGC Field crew 87 Date MAY 1965

A-D	1	3
NMO	3	
AR2	2	
TVD	2	
TVS	—	
DCN	—	4
DPS	4	5
TVD	5	
DCN	—	
DGF	—	
TVF	6	
600 Pkg. □	—	

DIGITAL BAND PASS FILTERING Hz.

60 50 40 30 20 10 0

4·0 3·0 2·0 1·0 0·0 sec.

LINE DIAGRAM

N W S E I 87 238°

GEOPHYSICAL SERVICE INTERNATIONAL

DIGITAL PROCESSING CENTRE

SYDNEY, NSW, AUST.

PROCESSING DATA: Sample period 4 ms.

Groups processed 1-24 Processed 6 fold.

TAR: B - 0 db., α 0 db/sec. Gate to ms.

Vertical stack: Nil

Decon before stack: TVD 54 pts., 4 ms. No. of gates/trace 2

Design gate (trace 1) 1060 to 4000 ms. Gate shift -66 ms/trace.

Decon after stack: TVD 62 pts., 4 ms. No. of gates/trace 2

Design gate (trace 1) 300 to 3996 ms. Gate shift 0 ms/trace.

Digital filter 35 pts., 4 ms. to Hz.

Display: digital AGC. Playback gain 8 db.

Polarity displayed: Positive □ / Negative ■

TIAC REQ. 3459 Hold tape 6321 Date NOV.1971

GSI INPUT CREW - PARTY 107-ESO-2

J/19P Part 6

(10)

223081

OR-208

Figure 10

SEAL AREA

9862 VA 9856 9850 9844 9838 9832 VA 9826 9820 9814 9808 9802 9796 VA 9790 9784

WATER DEPTHS 00
WATER VEL. 4950'/sec.
VELOCITIES

870A-24-31 870A-24-30 870A-24-29

EVCM

L.M.DIV.

00 02 04 06 08 10 12 14 16 18 20 22 24 26 28 30 32 34 36 38 40 42 44 46 48 50

ESSO STANDARD OIL (AUST) LTD.

AREA: BASS BASIN LINE: 870A-24
RECORDING PARAMETERS SP 8871 to 9894
Source AIRGUN guns, tuned array
Array size 860 cu.in., 11 No of groups 48
4 pops/SP. Shot off group 48
Cable length (centre of gp 1 to centre of gp. 48) 7708 ft.
Offset (array centre to centre of group 48) 863/883 ft.
Group interval 164 ft. SP interval 656 ft.
10 geophones/group Field polarity first break Negative
Recording system DFS III Filter 8 to 62 Hz.
Recording length 5 sec Sample rate 4 ms.
GSI Field crew 909 Date DEC'1970

VES 1
NMO 2
AR2 —
TVD —
TVS 3
DCN —
DPS 4
TVD 5
DCN —
DGF —
TVF 6
600 Pkg. ■

GEOPHYSICAL SERVICE INTERNATIONAL
DIGITAL PROCESSING CENTRE
SYDNEY, NSW, AUST.

Sample period 4 ms.
Processed 24 fold
Gate 0 to 4500 ms

PROCESSING DATA : 1-48
Groups processed
TAR B - 14 db., α 3.5 db/sec.
Vertical stack Odd/Even
Decon before stack: DCN 66 pts., 4 ms. No. of gates 1
Design gate (trace 1) 2200 to 4900 ms Gate shift -78 ms/trace.
Decon after stack TVD 64 pts., 4 ms. No. of gates/trace 2
Design gate (trace 1) 300 to 4500 ms Gate shift 0 ms/trace.
Digital filter 35 pts., 4 ms. to Hz.
Displayed digital AGC. Playback gain 23 db.
Polarity displayed: Positive □ / Negative ■
TIAC REQUEST 674 Hold tape 5401
INPUT CREW PARTY 851 Date MAR 1971

DIGITAL BAND PASS FILTERING Hz.
60 50 40 30 20 10 0
5.0 4.0 3.0 2.0 1.0 0.0 sec.
RECORD TIME

LINE N DIAGRAM
W 9894 8871 E
S 300°

5 cm


T/19P Part 6

(11)

OR-208

223682

Figure 11



HEMATITE PETROLEUM PTY. LTD.

HB75A SEISMIC SURVEY	HB75A-156

FIELD DATA: Shot by: GSI Party 931 M.V. McDermott

Recorded: 48 Trace DFS III (2 Systems)
Sample Rate: 4 m secs. Record Length: 5secs.
Filter: HI 62 Hz/ 72 db/oct, LO 8 Hz/ 18 db/oct.
Gain: Binary
Energy Source: Airgun, 1200 cub ins
Source Depth: 30-35 ft Streamer Depth: 50-60ft
Group interval: 219 ft. Shot interval: 73ft
Streamer: 3200 m, 48 groups, towing group 48
Average Offset to centre of group 48: 855 ft
Date: January '75

LINE 2889 DIAGRAM

N
W E
677
S 3036
Number a block number at end of line.


PROCESSING INFORMATION:

1 True Amplitude Recovery (-12db, 5db/sec. 0-3·5 secs.)
2 Vertical Stack 3:1
3 Deconvolution Before Stack
SP's 1 - 677, 2 Operators/Trace, 64 pts. Gap = 0 msec.


4 24 Fold Common Depthpoint Gather
5 Sealevel Static and Airgun Delay Corrections
6 Preliminary Normal Moveout Corrections
7 Preliminary 24-Fold Stack, 24 Traces.
8 Velocity Analysis:
Continuous 700 Pkg 100m Depth Points
9 Normal Moveout Corrections
10 24 Fold CDP Stack, 48 Traces
11 Deconvolution After Stack, 2 Operators/Trace, 70 pts. Gap = 0 msec.
12 Time Variant Filter
13 Cross Record Mix on T.V.F. Section
Weighted Mix over 3 Traces
Contributions = 10% , 80%, 10%.

14 Display Normal Polarity, 10 traces/cm. (0·53 miles/inch) Horizontal Scale
3·75 ins/sec Vertical Scale

TIME VARIANT FILTER BANDPASS FREQUENCY (Hz)



FIRST BREAK SUPPRESSION OFFSET (Ft)



PROCESSED BY: GEOPHYSICAL SERVICE INTERNATIONAL, SYDNEY.
DATE APRIL 1975

5 cm


T/19P Part 6

(12)

223083

OR-208

Figure 12



TIAP Part 6

(13)

223684

OR-208

Figure 13

MORNINGTON-KING ISLAND FAULT

PENGUIN AREA

LINE B72A-134

SCALE RATIO = 2·8:1 AT 1·5 SEC.

B71A-40

B63-1

3655 3653 3647 3641 3635 3629 3623

WATER DEPTHS 0·0

VELOCITIES

B72A-134-13 ← 134-13 ← 134-12 ← 134-11 ← 134-10 ← 13


0·2 0·4 0·6 0·8 1·0 1·2 1·4 1·6 1·8 2·0 2·2 2·4 2·6 2·8 3·0 3·2 3·4 3·6 3·8 4·0 4·2 4·4 4·6 4·8 5·0

EVCM

L.M. DIV.

MAGNETOMETER PLOT (GAMMAS)

62000 61900 61800 61700 61600 61500



GEOPHYSICAL SERVICE INTERNATIONAL

DIGITAL PROCESSING CENTRE SYDNEY, NSW, AUST

ESSO AUSTRALIA LIMITED

AREA BASS BASIN LINE B72A-134

RECORDING PARAMETERS SP 3575 to 3655

Source Air Gun

Array size 1200 cu.in., 25 guns, tuned array

8 pops/SP. Shot off group 48 No of groups 48

Cable length (centre of gp 1 to centre of gp. 48) 10246 ft

Offset (array centre to centre of group 48) 832 ft 872 ft

Group interval 218 ft SP interval 872 ft

30 geophones/group. Field polarity first break Negative

Recording system DFS III Filter 8 to 62 Hz

Recording length 5 sec Sample rate 4 ms

G.S.I. Field crew 931 Date Sep. 1972

VES 3 NMO 3 AR2 — TVD — TVS 2 DCN 1 DPS 4 TVD 5 DCN — DGF — TVF 6 700 Pkg ■

Sample period 4 ms

Processed 48 fold

Gate 0 to 4000 ms

pts, 4 ms No of gates/trace 1

4620 ms Gate shift -98 ms/trace

pts, 4 ms. No. of gates/trace 2

4500 ms Gate shift 0 ms/trace

to Hz

Playback gain 7 db

ative ■

Hold tape TVF 4840

Date Oct. 1972

DIGITAL BAND PASS FILTERING Hz. 60 50 40 30 20 10 0

5·0 4·0 3·0 2·0 1·0 0·0 sec RECORD TIME

LINE N DIAGRAM

3655 W E 3575 S 305°

PROCESSING DATA:

Groups processed 1 - 48

TAR B = -20 db, α = 4 db/sec

Vertical stack Nil

Decon before stack: DCN 44 pts, 4

Design gate (trace 1) 2860 to 4620

Decon after stack TVD 64 pts, 4

Design gate (trace 1) 300 to 4500

Digital filter 35 pts, 4 ms to

Displayed digital AGC Playb

Polarity displayed Positive □ / Negative ■

TIAC REQUEST 3893

INPUT CREW PARTY 107-ESO-3


5 cm

T/19P Part 6.

OR-208

Figure 14

223085



HEMATITE PETROLEUM PTY. LTD.

HB75A SEISMIC SURVEY	HB75A-179

FIELD DATA: Shot by: GSI Party 931 M.V. McDermott

Recorded: 48 Trace DFS III (2 Systems)
Sample Rate: 4 msecs. Record Length: 5secs.
Filter: HI 62 Hz/72 db/oct, LO 8 Hz/ 18 db/oct.
Gain: Binary
Energy Source: Airgun, 1200 cub ins
Source Depth: 30-35 ft Streamer Depth: 50-60ft
Group interval: 219 ft. Shot interval: 73ft
Streamer: 3200 m, 48 groups, towing group 48
Average Offset to centre of group 48: 895 ft
Date: January '75

LINE 3179 DIAGRAM

N
W 302 1 E
3320 S

Number in block number at end of line.


PROCESSING INFORMATION:

1 True Amplitude Recovery(-12db, 5db/sec. 0-3·5 secs.)
2 Vertical Stack 3:1 (Nears Only)
3 Deconvolution Before Stack


SP's 1 - 302, 2 Operators/Trace, 64 pts. Gap = 0msec.
4 12 Fold Common Depthpoint Gather
5 Sealevel Static and Airgun-Delay Corrections
6 Preliminary Normal Moveout Corrections
7 Preliminary 12 - Fold Stack, 24 Traces.
8 Velocity Analysis:
Continuous 700 Pkg Alternate Depth Points
9 Normal Moveout Corrections
10 12 Fold CDP Stack, 24 Traces
11 Deconvolution After Stack, 2 Operators/Trace, 70 pts. Gap = 0msec.
12 Time Variant Filter
13 Cross Record Mix on T.V.F. Section
Weighted Mix over 3 Traces
Contributions = 10%, 80%, 10%.

14 Display Normal Polarity, 10 traces/cm. (0·53miles/inch) Horizontal Scale
3·75 ins/sec. Vertical Scale

TIME VARIANT FILTER BANDPASS FREQUENCY (Hz)



FIRST BREAK SUPPRESSION OFFSET (Ft)



PROCESSED BY: GEOPHYSICAL SERVICE INTERNATIONAL, SYDNEY.
DATE MAY 1975

5 cm

MORNINGTON-
KING ISLAND FAULT

MORNINGTON-
KING ISLAND RISE

A

A'

B

B'

C

C'

Konkon

Toolka

Cormorant

Aroo

Bass 1

Bass 2

Yurongi

Dondu

Bass 3

Tarook

Nangkero

Poonboon

Squid

Narimba

Pelican

Fig. 4

Fig. 5

Fig. 6

Fig. 7

Fig. 8

SEAL
AREA

Fig. 9

Fig. 10

Fig. 11

Fig. 12

Fig. 13

Fig. 14

I

II

III

IV

V

VI

N.W. PENGUIN

WEST PENGUIN

PENGUIN

S. PENGUIN

CENTRAL
GRABEN

MANATEE

B A S S S T R A I T

2808 2737 PERTHSHIRE T/19P

2880 2809

2952 2881

3024 2953

3095 3096 3025

E Harbinger

W Harbinger C Wickham

3099

3171

3243

Councillor Is

Sea Elephant Rock

3315

3387 3388 3389 3390 3391 3392 3393 3394

3 4 5 6 7 8 9 10

PERTHSHIRE T/19P

2754 2755 B TASMANIA

2826 C' 2827

2899

PERTHSHIRE T/19P TASMANIA

PERTHSHIRE PETROLEUM, LTD.

PERMIT T-19-P

MAJOR STRUCTURAL ELEMENTS
AND LOCATION OF LEADS,
INCLUDING INDEX TO
REPRESENTATIVE SEISMIC LINES
FIGURES 4 THROUGH 14


September, 1984

Map 1

5 cm

T/19P
Part 6.
OR-208

223086


VICTORIA
TASMANIA
T-19-P
VOLCANICS
SEAL AREA
MANATEE
PENGUIN
EF-81
EF-83
EF-85
EF-87
EF-89
EF-91
EF-93
EF-95
EO-81
EO-83
EO-85
EO-87
EO-89
EO-91
EO-93
EO-95
EO-97
EO-99
EO-101
EO-103
EO-105
EO-107
EO-109
EO-111
EO-113
EO-115
EO-117
EO-119
EO-121
EO-123
EO-125
EO-127
EO-129
EO-131
EO-133
EO-135
EO-137
EO-139
EO-141
EO-143
EO-145
EO-147
EO-149
EO-151
EO-153
EO-155
EO-157
EO-159
EO-161
EO-163
EO-165
EO-167
EO-169
EO-171
EO-173
EO-175
EO-177
EO-179
EO-181
EO-183
EO-185
EO-187
EO-189
EO-191
EO-193
EO-195
EO-197
EO-199
EO-201
EO-203
EO-205
EO-207
EO-209
EO-211
EO-213
EO-215
EO-217
EO-219
EO-221
EO-223
EO-225
EO-227
EO-229
EO-231
EO-233
EO-235
EO-237
EO-239
EO-241
EO-243
EO-245
EO-247
EO-249
EO-251
EO-253
EO-255
EO-257
EO-259
EO-261
EO-263
EO-265
EO-267
EO-269
EO-271
EO-273
EO-275
EO-277
EO-279
EO-281
EO-283
EO-285
EO-287
EO-289
EO-291
EO-293
EO-295
EO-297
EO-299
EO-301
EO-303
EO-305
EO-307
EO-309
EO-311
EO-313
EO-315
EO-317
EO-319
EO-321
EO-323
EO-325
EO-327
EO-329
EO-331
EO-333
EO-335
EO-337
EO-339
EO-341
EO-343
EO-345
EO-347
EO-349
EO-351
EO-353
EO-355
EO-357
EO-359
EO-361
EO-363
EO-365
EO-367
EO-369
EO-371
EO-373
EO-375
EO-377
EO-379
EO-381
EO-383
EO-385
EO-387
EO-389
EO-391
EO-393
EO-395
EO-397
EO-399
EO-401
EO-403
EO-405
EO-407
EO-409
EO-411
EO-413
EO-415
EO-417
EO-419
EO-421
EO-423
EO-425
EO-427
EO-429
EO-431
EO-433
EO-435
EO-437
EO-439
EO-441
EO-443
EO-445
EO-447
EO-449
EO-451
EO-453
EO-455
EO-457
EO-459
EO-461
EO-463
EO-465
EO-467
EO-469
EO-471
EO-473
EO-475
EO-477
EO-479
EO-481
EO-483
EO-485
EO-487
EO-489
EO-491
EO-493
EO-495
EO-497
EO-499
EO-501
EO-503
EO-505
EO-507
EO-509
EO-511
EO-513
EO-515
EO-517
EO-519
EO-521
EO-523
EO-525
EO-527
EO-529
EO-531
EO-533
EO-535
EO-537
EO-539
EO-541
EO-543
EO-545
EO-547
EO-549
EO-551
EO-553
EO-555
EO-557
EO-559
EO-561
EO-563
EO-565
EO-567
EO-569
EO-571
EO-573
EO-575
EO-577
EO-579
EO-581
EO-583
EO-585
EO-587
EO-589
EO-591
EO-593
EO-595
EO-597
EO-599
EO-601
EO-603
EO-605
EO-607
EO-609
EO-611
EO-613
EO-615
EO-617
EO-619
EO-621
EO-623
EO-625
EO-627
EO-629
EO-631
EO-633
EO-635
EO-637
EO-639
EO-641
EO-643
EO-645
EO-647
EO-649
EO-651
EO-653
EO-655
EO-657
EO-659
EO-661
EO-663
EO-665
EO-667
EO-669
EO-671
EO-673
EO-675
EO-677
EO-679
EO-681
EO-683
EO-685
EO-687
EO-689
EO-691
EO-693
EO-695
EO-697
EO-699
EO-701
EO-703
EO-705
EO-707
EO-709
EO-711
EO-713
EO-715
EO-717
EO-719
EO-721
EO-723
EO-725
EO-727
EO-729
EO-731
EO-733
EO-735
EO-737
EO-739
EO-741
EO-743
EO-745
EO-747
EO-749
EO-751
EO-753
EO-755
EO-757
EO-759
EO-761
EO-763
EO-765
EO-767
EO-769
EO-771
EO-773
EO-775
EO-777
EO-779
EO-781
EO-783
EO-785
EO-787
EO-789
EO-791
EO-793
EO-795
EO-797
EO-799
EO-801
EO-803
EO-805
EO-807
EO-809
EO-811
EO-813
EO-815
EO-817
EO-819
EO-821
EO-823
EO-825
EO-827
EO-829
EO-831
EO-833
EO-835
EO-837
EO-839
EO-841
EO-843
EO-845
EO-847
EO-849
EO-851
EO-853
EO-855
EO-857
EO-859
EO-861
EO-863
EO-865
EO-867
EO-869
EO-871
EO-873
EO-875
EO-877
EO-879
EO-881
EO-883
EO-885
EO-887
EO-889
EO-891
EO-893
EO-895
EO-897
EO-899
EO-901
EO-903
EO-905
EO-907
EO-909
EO-911
EO-913
EO-915
EO-917
EO-919
EO-921
EO-923
EO-925
EO-927
EO-929
EO-931
EO-933
EO-935
EO-937
EO-939
EO-941
EO-943
EO-945
EO-947
EO-949
EO-951
EO-953
EO-955
EO-957
EO-959
EO-961
EO-963
EO-965
EO-967
EO-969
EO-971
EO-973
EO-975
EO-977
EO-979
EO-981
EO-983
EO-985
EO-987
EO-989
EO-991
EO-993
EO-995
EO-997
EO-999
EO-1001
EO-1003
EO-1005
EO-1007
EO-1009
EO-1011
EO-1013
EO-1015
EO-1017
EO-1019
EO-1021
EO-1023
EO-1025
EO-1027
EO-1029
EO-1031
EO-1033
EO-1035
EO-1037
EO-1039
EO-1041
EO-1043
EO-1045
EO-1047
EO-1049
EO-1051
EO-1053
EO-1055
EO-1057
EO-1059
EO-1061
EO-1063
EO-1065
EO-1067
EO-1069
EO-1071
EO-1073
EO-1075
EO-1077
EO-1079
EO-1081
EO-1083
EO-1085
EO-1087
EO-1089
EO-1091
EO-1093
EO-1095
EO-1097
EO-1099
EO-1101
EO-1103
EO-1105
EO-1107
EO-1109
EO-1111
EO-1113
EO-1115
EO-1117
EO-1119
EO-1121
EO-1123
EO-1125
EO-1127
EO-1129
EO-1131
EO-1133
EO-1135
EO-1137
EO-1139
EO-1141
EO-1143
EO-1145
EO-1147
EO-1149
EO-1151
EO-1153
EO-1155
EO-1157
EO-1159
EO-1161
EO-1163
EO-1165
EO-1167
EO-1169
EO-1171
EO-1173
EO-1175
EO-1177
EO-1179
EO-1181
EO-1183
EO-1185
EO-1187
EO-1189
EO-1191
EO-1193
EO-1195
EO-1197
EO-1199
EO-1201
EO-1203
EO-1205
EO-1207
EO-1209
EO-1211
EO-1213
EO-1215
EO-1217
EO-1219
EO-1221
EO-1223
EO-1225
EO-1227
EO-1229
EO-1231
EO-1233
EO-1235
EO-1237
EO-1239
EO-1241
EO-1243
EO-1245
EO-1247
EO-1249
EO-1251
EO-1253
EO-1255
EO-1257
EO-1259
EO-1261
EO-1263
EO-1265
EO-1267
EO-1269
EO-1271
EO-1273
EO-1275
EO-1277
EO-1279
EO-1281
EO-1283
EO-1285
EO-1287
EO-1289
EO-1291
EO-1293
EO-1295
EO-1297
EO-1299
EO-1301
EO-1303
EO-1305
EO-1307
EO-1309
EO-1311
EO-1313
EO-1315
EO-1317
EO-1319
EO-1321
EO-1323
EO-1325
EO-1327
EO-1329
EO-1331
EO-1333
EO-1335
EO-1337
EO-1339
EO-1341
EO-1343
EO-1345
EO-1347
EO-1349
EO-1351
EO-1353
EO-1355
EO-1357
EO-1359
EO-1361
EO-1363
EO-1365
EO-1367
EO-1369
EO-1371
EO-1373
EO-1375
EO-1377
EO-1379
EO-1381
EO-1383
EO-1385
EO-1387
EO-1389
EO-1391
EO-1393
EO-1395
EO-1397
EO-1399
EO-1401
EO-1403
EO-1405
EO-1407
EO-1409
EO-1411
EO-1413
EO-1415
EO-1417
EO-1419
EO-1421
EO-1423
EO-1425
EO-1427
EO-1429
EO-1431
EO-1433
EO-1435
EO-1437
EO-1439
EO-1441
EO-1443
EO-1445
EO-1447
EO-1449
EO-1451
EO-1453
EO-1455
EO-1457
EO-1459
EO-1461
EO-1463
EO-1465
EO-1467
EO-1469
EO-1471
EO-1473
EO-1475
EO-1477
EO-1479
EO-1481
EO-1483
EO-1485
EO-1487
EO-1489
EO-1491
EO-1493
EO-1495
EO-1497
EO-1499
EO-1501
EO-1503
EO-1505
EO-1507
EO-1509
EO-1511
EO-1513
EO-1515
EO-1517
EO-1519
EO-1521
EO-1523
EO-1525
EO-1527
EO-1529
EO-1531
EO-1533
EO-1535
EO-1537
EO-1539
EO-1541
EO-1543
EO-1545
EO-1547
EO-1549
EO-1551
EO-1553
EO-1555
EO-1557
EO-1559
EO-1561
EO-1563
EO-1565
EO-1567
EO-1569
EO-1571
EO-1573
EO-1575
EO-1577
EO-1579
EO-1581
EO-1583
EO-1585
EO-1587
EO-1589
EO-1591
EO-1593
EO-1595
EO-1597
EO-1599
EO-1601
EO-1603
EO-1605
EO-1607
EO-1609
EO-1611
EO-1613
EO-1615
EO-1617
EO-1619
EO-1621
EO-1623
EO-1625
EO-1627
EO-1629
EO-1631
EO-1633
EO-1635
EO-1637
EO-1639
EO-1641
EO-1643
EO-1645
EO-1647
EO-1649
EO-1651
EO-1653
EO-1655
EO-1657
EO-1659
EO-1661
EO-1663
EO-1665
EO-1667
EO-1669
EO-1671
EO-1673
EO-1675
EO-1677
EO-1679
EO-1681
EO-1683
EO-1685
EO-1687
EO-1689
EO-1691
EO-1693
EO-1695
EO-1697
EO-1699
EO-1701
EO-1703
EO-1705
EO-1707
EO-1709
EO-1711
EO-1713
EO-1715
EO-1717
EO-1719
EO-1721
EO-1723
EO-1725
EO-1727
EO-1729
EO-1731
EO-1733
EO-1735
EO-1737
EO-1739
EO-1741
EO-1743
EO-1745
EO-1747
EO-1749
EO-1751
EO-1753
EO-1755
EO-1757
EO-1759
EO-1761
EO-1763
EO-1765
EO-1767
EO-1769
EO-1771
EO-1773
EO-1775
EO-1777
EO-1779
EO-1781
EO-1783
EO-1785
EO-1787
EO-1789
EO-1791
EO-1793
EO-1795
EO-1797
EO-1799
EO-1801
EO-1803
EO-1805
EO-1807
EO-1809
EO-1811
EO-1813
EO-1815
EO-1817
EO-1819
EO-1821
EO-1823
EO-1825
EO-1827
EO-1829
EO-1831
EO-1833
EO-1835
EO-1837
EO-1839
EO-1841
EO-1843
EO-1845
EO-1847
EO-1849
EO-1851
EO-1853
EO-1855
EO-1857
EO-1859
EO-1861
EO-1863
EO-1865
EO-1867
EO-1869
EO-1871
EO-1873
EO-1875
EO-1877
EO-1879
EO-1881
EO-1883
EO-1885
EO-1887
EO-1889
EO-1891
EO-1893
EO-1895
EO-1897
EO-1899
EO-1901
EO-1903
EO-1905
EO-1907
EO-1909
EO-1911
EO-1913
EO-1915
EO-1917
EO-1919
EO-1921
EO-1923
EO-1925
EO-1927
EO-1929
EO-1931
EO-1933
EO-1935
EO-1937
EO-1939
EO-1941
EO-1943
EO-1945
EO-1947
EO-1949
EO-1951
EO-1953
EO-1955
EO-1957
EO-1959
EO-1961
EO-1963
EO-1965
EO-1967
EO-1969
EO-1971
EO-1973
EO-1975
EO-1977
EO-1979
EO-1981
EO-1983
EO-1985
EO-1987
EO-1989
EO-1991
EO-1993
EO-1995
EO-1997
EO-1999
EO-2001
EO-2003
EO-2005
EO-2007
EO-2009
EO-2011
EO-2013
EO-2015
EO-2017
EO-2019
EO-2021
EO-2023
EO-2025
EO-2027
EO-2029
EO-2031
EO-2033
EO-2035
EO-2037
EO-2039
EO-2041
EO-2043
EO-2045
EO-2047
EO-2049
EO-2051
EO-2053
EO-2055
EO-2057
EO-2059
EO-2061
EO-2063
EO-2065
EO-2067
EO-2069
EO-2071
EO-2073
EO-2075
EO-2077
EO-2079
EO-2081
EO-2083
EO-2085
EO-2087
EO-2089
EO-2091
EO-2093
EO-2095
EO-2097
EO-2099
EO-2101
EO-2103
EO-2105
EO-2107
EO-2109
EO-2111
EO-2113
EO-2115
EO-2117
EO-2119
EO-2121
EO-2123
EO-2125
EO-2127
EO-2129
EO-2131
EO-2133
EO-2135
EO-2137
EO-2139
EO-2141
EO-2143
EO-2145
EO-2147
EO-2149
EO-2151
EO-2153
EO-2155
EO-2157
EO-2159
EO-2161
EO-2163
EO-2165
EO-2167
EO-2169
EO-2171
EO-2173
EO-2175
EO-2177
EO-2179
EO-2181
EO-2183
EO-2185
EO-2187
EO-2189
EO-2191
EO-2193
EO-2195
EO-2197
EO-2199
EO-2201
EO-2203
EO-2205
EO-2207
EO-2209
EO-2211
EO-2213
EO-2215
EO-2217
EO-2219
EO-2221
EO-2223
EO-2225
EO-2227
EO-2229
EO-2231
EO-2233
EO-2235
EO-2237
EO-2239
EO-2241
EO-2243
EO-2245
EO-2247
EO-2249
EO-2251
EO-2253
EO-2255
EO-2257
EO-2259
EO-2261
EO-2263
EO-2265
EO-2267
EO-2269
EO-2271
EO-2273
EO-2275
EO-2277
EO-2279
EO-2281
EO-2283
EO-2285
EO-2287
EO-2289
EO-2291
EO-2293
EO-2295
EO-2297
EO-2299
EO-2301
EO-2303
EO-2305
EO-2307
EO-2309
EO-2311
EO-2313
EO-2315
EO-2317
EO-2319
EO-2321
EO-2323
EO-2325
EO-2327
EO-2329
EO-2331
EO-2333
EO-2335
EO-2337
EO-2339
EO-2341
EO-2343
EO-2345
EO-2347
EO-2349
EO-2351
EO-2353
EO-2355
EO-2357
EO-2359
EO-2361
EO-2363
EO-2365
EO-2367
EO-2369
EO-2371
EO-2373
EO-2375
EO-2377
EO-2379
EO-2381
EO-2383
EO-2385
EO-2387
EO-2389
EO-2391
EO-2393
EO-2395
EO-2397
EO-2399
EO-2401
EO-2403
EO-2405
EO-2407
EO-2409
EO-2411
EO-2413
EO-2415
EO-2417
EO-2419
EO-2421
EO-2423
EO-2425
EO-2427
EO-2429
EO-2431
EO-2433
EO-2435
EO-2437
EO-2439
EO-2441
EO-2443
EO-2445
EO-2447
EO-2449
EO-2451
EO-2453
EO-2455
EO-2457
EO-2459
EO-2461
EO-2463
EO-2465
EO-2467
EO-2469
EO-2471
EO-2473
EO-2475
EO-2477
EO-2479
EO-2481
EO-2483
EO-2485
EO-2487
EO-2489
EO-2491
EO-2493
EO-2495
EO-2497
EO-2499
EO-2501
EO-2503
EO-2505
EO-2507
EO-2509
EO-2511
EO-2513
EO-2515
EO-2517
EO-2519
EO-2521
EO-2523
EO-2525
EO-2527
EO-2529
EO-2531
EO-2533
EO-2535
EO-2537
EO-2539
EO-2541
EO-2543
EO-2545
EO-2547
EO-2549
EO-2551
EO-2553
EO-2555
EO-2557
EO-2559
EO-2561
EO-2563
EO-2565
EO-2567
EO-2569
EO-2571
EO-2573
EO-2575
EO-2577
EO-2579
EO-2581
EO-2583
EO-2585
EO-2587
EO-2589
EO-2591
EO-2593
EO-2595
EO-2597
EO-2599
EO-2601
EO-2603
EO-2605
EO-2607
EO-2609
EO-2611
EO-2613
EO-2615
EO-2617
EO-2619
EO-2621
EO-2623
EO-2625
EO-2627
EO-2629
EO-2631
EO-2633
EO-2635
EO-2637
EO-2639
EO-2641
EO-2643
EO-2645
EO-2647
EO-2649
EO-2651
EO-2653
EO-2655
EO-2657
EO-2659
EO-2661
EO-2663
EO-2665
EO-2667
EO-2669
EO-2671
EO-2673
EO-2675
EO-2677
EO-2679
EO-2681
EO-2683
EO-2685
EO-2687
EO-2689
EO-2691
EO-2693
EO-2695
EO-2697
EO-2699
EO-2701
EO-2703
EO-2705
EO-2707
EO-2709
EO-2711
EO-2713
EO-2715
EO-2717
EO-2719
EO-2721
EO-2723
EO-2725
EO-2727
EO-2729
EO-2731
EO-2733
EO-2735
EO-2737
EO-2739
EO-2741
EO-2743
EO-2745
EO-2747
EO-2749
EO-2751
EO-2753
EO-2755
EO-2757
EO-2759
EO-2761
EO-2763
EO-2765
EO-2767
EO-2769
EO-2771
EO-2773
EO-2775
EO-2777
EO-2779
EO-2781
EO-2783
EO-2785
EO-2787
EO-2789
EO-2791
EO-2793
EO-2795
EO-2797
EO-2799
EO-2801
EO-2803
EO-2805
EO-2807
EO-2809
EO-2811
EO-2813
EO-2815
EO-2817
EO-2819
EO-2821
EO-2823
EO-2825
EO-2827
EO-2829
EO-2831
EO-2833
EO-2835
EO-2837
EO-2839
EO-2841
EO-2843
EO-2845
EO-2847
EO-2849
EO-2851
EO-2853
EO-2855
EO-2857
EO-2859
EO-2861
EO-2863
EO-2865
EO-2867
EO-2869
EO-2871
EO-2873
EO-2875
EO-2877
EO-2879
EO-2881
EO-2883
EO-2885
EO-2887
EO-2889
EO-2891
EO-2893
EO-2895
EO-2897
EO-2899
EO-2901
EO-2903
EO-2905
EO-2907
EO-2909
EO-2911
EO-2913
EO-2915
EO-2917
EO-2919
EO-2921
EO-2923
EO-2925
EO-2927
EO-2929
EO-2931
EO-2933
EO-2935
EO-2937
EO-2939
EO-2941
EO-2943
EO-2945
EO-2947
EO-2949
EO-2951
EO-2953
EO-2955
EO-2957
EO-2959
EO-2961
EO-2963
EO-2965
EO-2967
EO-2969
EO-2971
EO-2973
EO-2975
EO-2977
EO-2979
EO-2981
EO-2983
EO-2985
EO-2987
EO-2989
EO-2991
EO-2993
EO-2995
EO-2997
EO-2999
EO-3001
EO-3003
EO-3005
EO-3007
EO-3009
EO-3011
EO-3013
EO-3015
EO-3017
EO-3019
EO-3021
EO-3023
EO-3025
EO-3027
EO-3029
EO-3031
EO-3033
EO-3035
EO-3037
EO-3039
EO-3041
EO-3043
EO-3045
EO-3047
EO-3049
EO-3051
EO-3053
EO-3055
EO-3057
EO-3059
EO-3061
EO-3063
EO-3065
EO-3067
EO-3069
EO-3071
EO-3073
EO-3075
EO-3077
EO-3079
EO-3081
EO-3083
EO-3085
EO-3087
EO-3089
EO-3091
EO-3093
EO-3095
EO-3097
EO-3099
EO-3101
EO-3103
EO-3105
EO-3107
EO-3109
EO-3111
EO-3113
EO-3115
EO-3117
EO-3119
EO-3121
EO-3123
EO-3125
EO-3127
EO-3129
EO-3131
EO-3133
EO-3135
EO-3137
EO-3139
EO-3141
EO-3143
EO-3145
EO-3147
EO-3149
EO-3151
EO-3153
EO-3155
EO-3157
EO-3159
EO-3161
EO-3163
EO-3165
EO-3167
EO-3169
EO-3171
EO-3173
EO-3175
EO-3177
EO-3179
EO-3181
EO-3183
EO-3185
EO-3187
EO-3189
EO-3191
EO-3193
EO-3195
EO-3197
EO-3199
EO-3201
EO-3203
EO-3205
EO-3207
EO-3209
EO-3211
EO-3213
EO-3215
EO-3217
EO-3219
EO-3221
EO-3223
EO-3225
EO-3227
EO-3229
EO-3231
EO-3233
EO-3235
EO-3237
EO-3239
EO-3241
EO-3243
EO-3245
EO-3247
EO-3249
EO-3251
EO-3253
EO-3255
EO-3257
EO-3259
EO-3261
EO-3263
EO-3265
EO-3267
EO-3269
EO-3271
EO-3273
EO-3275
EO-3277
EO-3279
EO-3281
EO-3283
EO-3285
EO-3287
EO-3289
EO-3291
EO-3293
EO-3295
EO-3297
EO-3299
EO-3301
EO-3303
EO-3305
EO-3307
EO-3309
EO-3311
EO-3313
EO-3315
EO-3317
EO-3319
EO-3321
EO-3323
EO-3325
EO-3327
EO-3329
EO-3331
EO-3333
EO-3335
EO-3337
EO-3339
EO-3341
EO-3343
EO-3345
EO-3347
EO-3349
EO-3351
EO-3353
EO-3355
EO-3357
EO-3359
EO-3361
EO-3363
EO-3365
EO-3367
EO-3369
EO-3371
EO-3373
EO-3375
EO-3377
EO-3379
EO-3381
EO-3383
EO-3385
EO-3387
EO-3389
EO-3391
EO-3393
EO-3395
EO-3397
EO-3399
EO-3401
EO-3403
EO-3405
EO-3407
EO-3409
EO-3411
EO-3413
EO-3415
EO-3417
EO-3419
EO-3421
EO-3423
EO-3425
EO-3427
EO-3429
EO-3431
EO-3433
EO-3435
EO-3437
EO-3439
EO-3441
EO-3443
EO-3445
EO-3447
EO-3449
EO-3451
EO-3453
EO-3455
EO-3457
EO-3459
EO-3461
EO-3463
EO-3465
EO-3467
EO-3469
EO-3471
EO-3473
EO-3475
EO-3477
EO-3479
EO-3481
EO-3483
EO-3485
EO-3487
EO-3489
EO-3491
EO-3493
EO-3495
EO-3497
EO-3499
EO-3501
EO-3503
EO-3505
EO-3507
EO-3509
EO-3511
EO-3513
EO-3515
EO-3517
EO-3519
EO-3521
EO-3523
EO-3525
EO-3527
EO-3529
EO-3531
EO-3533
EO-3535
EO-3537
EO-3539
EO-3541
EO-3543
EO-3545
EO-3547
EO-3549
EO-3551
EO-3553
EO-3555
EO-3557
EO-3559
EO-3561
EO-3563
EO-3565
EO-3567
EO-3569
EO-3571
EO-3573
EO-3575
EO-3577
EO-3579
EO-3581
EO-3583
EO-3585
EO-3587
EO-3589
EO-3591
EO-3593
EO-3595
EO-3597
EO-3599
EO-3601
EO-3603
EO-3605
EO-3607
EO-3609
EO-3611
EO-3613
EO-3615
EO-3617
EO-3619
EO-3621
EO-3623
EO-3625
EO-3627
EO-3629
EO-3631
EO-3633
EO-3635
EO-3637
EO-3639
EO-3641
EO-3643
EO-3645
EO-3647
EO-3649
EO-3651
EO-3653
EO-3655
EO-3657
EO-3659
EO-3661
EO-3663
EO-3665
EO-3667
EO-3669
EO-3671
EO-3673
EO-3675
EO-3677
EO-3679
EO-3681
EO-3683
EO-3685
EO-3687
EO-3689
EO-3691
EO-3693
EO-3695
EO-3697
EO-3699
EO-3701
EO-3703
EO-3705
EO-3707
EO-3709
EO-3711
EO-3713
EO-3715
EO-3717
EO-3719
EO-3721
EO-3723
EO-3725
EO-3727
EO-3729
EO-3731
EO-3733
EO-3735
EO-3737
EO-3739
EO-3741
EO-3743
EO-3745
EO-3747
EO-3749
EO-3751
EO-3753
EO-3755
EO-3757
EO-3759
EO-3761
EO-3763
EO-3765
EO-3767
EO-3769
EO-3771
EO-3773
EO-3775
EO-3777
EO-3779
EO-3781
EO-3783
EO-3785
EO-3787
EO-3789
EO-3791
EO-3793
EO-3795
EO-3797
EO-3799
EO-3801
EO-3803
EO-3805
EO-3807
EO-3809
EO-3811
EO-3813
EO-3815
EO-3817
EO-3819
EO-3821
EO-3823
EO-3825
EO-3827
EO-3829
EO-3831
EO-3833
EO-3835
EO-3837
EO-3839
EO-3841
EO-3843
EO-3845
EO-3847
EO-3849
EO-3851
EO-3853
EO-3855
EO-3857
EO-3859
EO-3861
EO-3863
EO-3865
EO-3867
EO-3869
EO-3871
EO-3873
EO-3875
EO-3877
EO-3879
EO-3881
EO-3883
EO-3885
EO-3887
EO-3889
EO-3891
EO-3893
EO-3895
EO-3897
EO-3899
EO-3901
EO-3903
EO-3905
EO-3907
EO-3909
EO-3911
EO-3913
EO-3915
EO-3917
EO-3919
EO-3921
EO-3923
EO-3925
EO-3927
EO-3929
EO-3931
EO-3933
EO-3935
EO-3937
EO-3939
EO-3941
EO-3943
EO-3945
EO-3947
EO-3949
EO-3951
EO-3953
EO-3955
EO-3957
EO-3959
EO-3961
EO-3963
EO-3965
EO-3967
EO-3969
EO-3971
EO-3973
EO-3975
EO-3977
EO-3979
EO-3981
EO-3983
EO-3985
EO-3987
EO-3989
EO-3991
EO-3993
EO-3995
EO-3997
EO-3999
EO-4001
EO-4003
EO-4005
EO-4007
EO-4009
EO-4011
EO-4013
EO-4015
EO-4017
EO-4019
EO-4021
EO-4023
EO-4025
EO-4027
EO-4029
EO-4031
EO-4033
EO-4035
EO-4037
EO-4039
EO-4041
EO-4043
EO-4045
EO-4047
EO-4049
EO-4051
EO-4053
EO-4055
EO-4057
EO-4059
EO-4061
EO-4063
EO-4065
EO-4067
EO-4069
EO-4071
EO-4073
EO-4075
EO-4077
EO-4079
EO-4081
EO-4083
EO-4085
EO-4087
EO-4089
EO-4091
EO-4093
EO-4095
EO-4097
EO-4099
EO-4101
EO-4103
EO-4105
EO-4107
EO-4109
EO-4111
EO-4113
EO-4115
EO-4117
EO-4119
EO-4121
EO-4123
EO-4125
EO-4127
EO-4129
EO-4131
EO-4133
EO-4135
EO-4137
EO-4139
EO-4141
EO-4143
EO-4145
EO-4147
EO-4149
EO-4151
EO-4153
EO-4155
EO-4157
EO-4159
EO-4161
EO-4163
EO-4165
EO-4167
EO-4169
EO-4171
EO-4173
EO-4175
EO-4177
EO-4179
EO-4181
EO-4183
EO-4185
EO-4187
EO-4189
EO-4191
EO-4193
EO-4195
EO-4197
EO-4199
EO-4201
EO-4203
EO-4205
EO-4207
EO-4209
EO-4211
EO-4213
EO-4215
EO-4217
EO-4219
EO-4221
EO-4223
EO-4225
EO-4227
EO-4229
EO-4231
EO-4233
EO-4235
EO-4237
EO-4239
EO-4241
EO-4243
EO-4245
EO-4247
EO-4249
EO-4251
EO-4253
EO-4255
EO-4257
EO-4259
EO-4261
EO-4263
EO-4265
EO-4267
EO-4269
EO-4271
EO-4273
EO-4275
EO-4277
EO-4279
EO-4281
EO-4283
EO-4285
EO-4287
EO-4289
EO-4291
EO-4293
EO-4295
EO-4297
EO-4299
EO-4301
EO-4303
EO-4305
EO-4307
EO-4309
EO-4311
EO-4313
EO-4315
EO-4317
EO-4319
EO-4321
EO-4323
EO-4325
EO-4327
EO-4329
EO-4331
EO-4333
EO-4335
EO-4337
EO-4339
EO-4341
EO-4343
EO-4345
EO-4347
EO-4349
EO-4351
EO-4353
EO-4355
EO-4357
EO-4359
EO-4361
EO-4363
EO-4365
EO-4367
EO-4369
EO-4371
EO-4373
EO-4375
EO-4377
EO-4379
EO-4381
EO-4383
EO-4385
EO-4387
EO-4389
EO-4391
EO-4393
EO-4395
EO-4397
EO-4399
EO-4401
EO-4403
EO-4405
EO-4407
EO-4409
EO-4411
EO-4413
EO-4415
EO-4417
EO-4419
EO-4421
EO-4423
EO-4425
EO-4427
EO-4429
EO-4431
EO-4433
EO-4435
EO-4437
EO-4439
EO-4441
EO-4443
EO-4445
EO-4447
EO-4449
EO-4451
EO-4453
EO-4455
EO-4457
EO-4459
EO-4461
EO-4463
EO-4465
EO-4467
EO-4469
EO-4471
EO-4473
EO-4475
EO-4477
EO-4479
EO-4481
EO-4483
EO-4485
EO-4487
EO-4489
EO-4491
EO-4493
EO-4495
EO-4497
EO-4499
EO-4501
EO-4503
EO-4505
EO-4507
EO-4509
EO-4511
EO-4513
EO-4515
EO-4517
EO-4519
EO-4521
EO-4523
EO-4525
EO-4527
EO-4529
EO-4531
EO-4533
EO-4535
EO-4537
EO-4539
EO-4541
EO-4543
EO-4545
EO-4547
EO-4549
EO-4551
EO-4553
EO-4555
EO-4557
EO-4559
EO-4561
EO-4563
EO-4565
EO-4567
EO-4569
EO-4571
EO-4573
EO-4575
EO-4577
EO-4579
EO-4581
EO-4583
EO-4585
EO-4587
EO-4589
EO-4591
EO-4593
EO-4595
EO-4597
EO-4599
EO-4601
EO-4603
EO-4605
EO-4607
EO-4609
EO-4611
EO-4613
EO-4615
EO-4617
EO-4619
EO-4621
EO-4623
EO-4625
EO-4627
EO-4629
EO-4631
EO-4633
EO-4635
EO-4637
EO-4639
EO-4641
EO-4643
EO-4645
EO-4647
EO-4649
EO-4651
EO-4653
EO-4655
EO-4657
EO-4659
EO-4661
EO-4663
EO-4665
EO-4667
EO-4669
EO-4671
EO-4673
EO-4675
EO-4677
EO-4679
EO-4681
EO-4683
EO-4685
EO-4687
EO-4689
EO-4691
EO-4693
EO-4695
EO-4697
EO-4699
EO-4701
EO-4703
EO-4705
EO-4707
EO-4709
EO-4711
EO-4713
EO-4715
EO-4717
EO-4719
EO-4721
EO-4723
EO-4725
EO-4727
EO-4729
EO-4731
EO-4733
EO-4735
EO-4737
EO-4739
EO-4741
EO-4743
EO-4745
EO-4747
EO-4749
EO-4751
EO-4753
EO-4755
EO-4757
EO-4759
EO-4761
EO-4763
EO-4765
EO-4767
EO-4769
EO-4771
EO-4773
EO-4775
EO-4777
EO-4779
EO-4781
EO-4783
EO-4785
EO-4787
EO-4789
EO-4791
EO-4793
EO-4795
EO-4797
EO-4799
EO-4801
EO-4803
EO-4805
EO-4807
EO-4809
EO-4811
EO-4813
EO-4815
EO-4817
EO-4819
EO-4821
EO-4823
EO-4825
EO-4827
EO-4829
EO-4831
EO-4833
EO-4835
EO-4837
EO-4839
EO-4841
EO-4843
EO-4845
EO-4847
EO-4849
EO-4851
EO-4853
EO-4855
EO-4857
EO-4859
EO-4861
EO-4863
EO-4865
EO-4867
EO-4869
EO-4871
EO-4873
EO-4875
EO-4877
EO-4879
EO-4881
EO-4883
EO-4885
EO-4887
EO-4889
EO-4891
EO-4893
EO-4895
EO-4897
EO-4899
EO-4901
EO-4903
EO-4905
EO-4907
EO-4909
EO-4911
EO-4913
EO-4915
EO-4917
EO-4919
EO-4921
EO-4923
EO-4925
EO-4927
EO-4929
EO-4931
EO-4933
EO-4935
EO-4937
EO-4939
EO-4941
EO-4943
EO-4945
EO-4947
EO-4949
EO-4951
EO-4953
EO-4955
EO-4957
EO-4959
EO-4961
EO-4963
EO-4965
EO-4967
EO-4969
EO-4971
EO-4973
EO-4975
EO-4977
EO-4979
EO-4981
EO-4983
EO-4985
EO-4987
EO-4989
EO-4991
EO-4993
EO-4995
EO-4997
EO-4999
EO-5001
EO-5003
EO-5005
EO-5007
EO-5009
EO-5011
EO-5013
EO-5015
EO-5017
EO-5019
EO-5021
EO-5023
EO-5025
EO-5027
EO-5029
EO-5031
EO-5033
EO-5035
EO-5037
EO-5039
EO-5041
EO-5043
EO-5045
EO-5047
EO-5049
EO-5051
EO-5053
EO-5055
EO-5057
EO-5059
EO-5061
EO-5063
EO-5065
EO-5067
EO-5069
EO-5071
EO-5073
EO-5075
EO-5077
EO-5079
EO-5081
EO-5083
EO-5085
EO-5087
EO-5089
EO-5091
EO-5093
EO-5095
EO-5097
EO-5099
EO-5101
EO-5103
EO-5105
EO-5107
EO-5109
EO-5111
EO-5113
EO-5115
EO-5117
EO-5119
EO-5121
EO-5123
EO-5125
EO-5127
EO-5129
EO-5131
EO-5133
EO-5135
EO-5137
EO-5139
EO-5141
EO-5143
EO-5145
EO-5147
EO-5149
EO-5151
EO-5153
EO-5155
EO-5157
EO-5159
EO-5161
EO-5163
EO-5165
EO-5167
EO-5169
EO-5171
EO-5173
EO-5175
EO-5177
EO-5179
EO-5181
EO-5183
EO-5185
EO-5187
EO-5189
EO-5191
EO-5193
EO-5195
EO-5197
EO-5199
EO-5201
EO-5203
EO-5205
EO-5207
EO-5209
EO-5211
EO-5213
EO-5215
EO-5217
EO-5219
EO-5221
EO-5223
EO-5225
EO-5227
EO-5229
EO-5231
EO-5233
EO-5235
EO-5237
EO-5239
EO-5241
EO-5243
EO-5245
EO-5247
EO-5249
EO-5251
EO-5253
EO-5255
EO-5257
EO-5259
EO-5261
EO-5263
EO-5265
EO-5267
EO-5269
EO-5271
EO-5273
EO-5275
EO-5277
EO-5279
EO-5281
EO-5283
EO-5285
EO-5287
EO-5289
EO-5291
EO-5293
EO-5295
EO-5297
EO-5299
EO-5301
EO-5303
EO-5305
EO-5307
EO-5309
EO-5311
EO-5313
EO-5315
EO-5317
EO-5319
EO-5321
EO-5323
EO-5325
EO-5327
EO-5329
EO-5331
EO-5333
EO-5335
EO-5337
EO-5339
EO-5341
EO-5343
EO-5345
EO-5347
EO-5349
EO-5351
EO-5353
EO-5355
EO-5357
EO-5359
EO-5361
EO-5363
EO-5365
EO-5367
EO-5369
EO-5371
EO-5373
EO-5375
EO-5377
EO-5379
EO-5381
EO-5383
EO-5385
EO-5387
EO-5389
EO-5391
EO-5393
EO-5395
EO-5397
EO-5399
EO-5401
EO-5403
EO-5405
EO-5407
EO-5409
EO-5411
EO-5413
EO-5415
EO-5417
EO-5419
EO-5421
EO-5423
EO-5425
EO-5427
EO-5429
EO-5431
EO-5433
EO-5435
EO-5437
EO-5439
EO-5441
EO-5443
EO-5445
EO-5447
EO-5449
EO-5451
EO-5453
EO-5455
EO-5457
EO-5459
EO-5461
EO-5463
EO-5465
EO-5467
EO-5469
EO-5471
EO-5473
EO-5475
EO-5477
EO-5479
EO-5481
EO-5483
EO-5485
EO-5487
EO-5489
EO-5491
EO-5493
EO-5495
EO-5497
EO-5499
EO-5501
EO-5503
EO-5505
EO-5507
EO-5509
EO-5511
EO-5513
EO-5515
EO-5517
EO

VICTORIA

TASMANIA

2754

2826

2898

2970

Konkon-1

Toolka 1

T-19-P

PERTHSHIRE PETROLEUM, LTD.

PERMIT T-19-P

SEISMIC TIME STRUCTURE MAP
(TWO WAY TIME)


Top Eastern View Coal Measure

INTERPRETATION BY
EXPLORATION ASSOCIATES
INTERNATIONAL, INC.

C.I. 50 Mls. SCALE 1: 50,000 September, 1984

Map 3

T/19P Part 6 OR-208



PERTHSHIRE PETROLEUM, LTD.

PERMIT T-19-P

SEISMIC TIME STRUCTURE MAP
(TWO WAY TIME)
Lower M. diversus Seismic Horizon

INTERPRETATION BY
EXPLORATION ASSOCIATES
INTERNATIONAL, INC.

E.I. 80 MIL — SCALE 1:50,000

T/19 P Part 6.

VICTORIA

TASMANIA

2754

2826

2970

Konkon-1

T-19-P

Toolka 1

VOLCANICS

PERTHSHIRE PETROLEUM, LTD.

PERMIT T-19-P

SEISMIC TIME STRUCTURE MAP
(TWO WAY TIME)


Lower M. diversus Seismic Horizon

INTERPRETATION BY
EXPLORATION ASSOCIATES
INTERNATIONAL, INC.

C.I. 50 Mls. SCALE 1: 50,000 September, 1984

Map 5

T/19P Part 6 OR-208



T/19P Part 6

OR-208

VICTORIA

TASMANIA

2754

2826

2898

2970

Konkon-1

T-19-P

Toolka 1

T-19-P

T-19-P

PERTHSHIRE PETROLEUM, LTD.

PERMIT T-19-P
ISOCHRON
Top Eastern View Coal Measure to
Lower M. diversus Seismic Horizon
Showing Outline of Areas of Closure

INTERPRETATION BY
EXPLORATION ASSOCIATES
INTERNATIONAL, INC.


EVCM Closure

M. diversus Closure


C.I. 50 Mls. SCALE 1:50,000 September, 1984

Map 7

T/19 P Part 6 OR-208


VICTORIA
TASMANIA
MANATEE
T-19-P
3391
3392
3393
3394
3395
3396
7
8
9
10
11
12
PERTHSHIRE PETROLEUM, LTD.
PERMIT T-19-P
DIP RATE MAP
Pre-Lower M. diversus
Seismic Horizon
INTERPRETATION BY
EXPLORATION ASSOCIATES
INTERNATIONAL, INC.
SCALE 1:50,000
T-19-P
Map 8

T19P Part 6


144°30'
144°45'
145°00'
39°15'
39°30'
40°00'
VICTORIA
TASMANIA
T-19-P
SEAL AREA
MANATEE
N.W. PENGUIN
WEST PENGUIN
PENGUIN
SOUTH PENGUIN
3391
3392
3393
3394
3395
3396
7
8
9
10
11
12
PERTHSHIRE PETROLEUM, LTD.
PERMIT T-19-P
Location of Proposed Seismic Lines
Showing Outline of Leads
Map 9
T-19-P
DK-208