

7 Core Summary

No full hole cores were cut at Flinders 1.

8 DST/RFT Summary

No Drill Stem Tests or Repeat Formation Tests were performed at Flinders 1.

9 Remarks

Hole conditions generally resulted in good quality log data although some wash outs (2"-3") occurred over the coals. Over the dolerite sill (2200-2280m) hole conditions deteriorated, this however had no impact on the log analysis.

Whilst hydrocarbon shows were limited to coal seams log analysis confirmed that the EVCM sandstone units were water wet. Some net pay was identified, this however was attributed to thin coals and/or coal shoulder bed effects.

Due to the lack of any producible economic hydrocarbons within the well, Flinders 1 was plugged and abandoned.