

APPENDIX B

DRILLING COSTS - 1973

035

Drillhole	DDH 29	DDH 30	DDH 31	DDH 32	DDH 33	DDH 34	DDH 35	DDH 36	DDH 37	Total	Per Cent
Depth - metres	161.54	154.53	123.42	150.24	254.16	173.28	182.90	237.78	222.77	1660.22	-
Tricone drilling	350.52	543.47	543.47	471.27	568.21	281.39	543.47	954.51	743.87	5,006.18	10.8
NQ Diamond drill	3,669.68	3,046.68	2,176.16	3,080.28	3,908.80	2,765.28	3,840.48	4,523.12	4,087.44	31,097.92	67.5
BQ Diamond drill	-	-	-	-	1,841.49	1,308.57	-	-	411.81	3,561.87	7.8
Running casing	33.53	57.91	57.91	52.42	285.30	148.13	45.72	76.20	276.47	1,033.59	2.2
Reaming casing	180.16	-	-	-	291.17	-	-	201.14	420.30	1,092.77	2.5
Recovering casing	113.75	-	-	-	35.00	35.00	-	87.50	99.50	370.75	0.8
Cementing	-	-	-	-	140.00	-	-	-	-	140.00	0.3
Surveys	52.50	46.75	52.50	26.25	140.00	70.00	52.50	96.25	84.75	621.50	1.3
Moving	-	-	138.12	-	104.81	-	-	-	-	242.93	0.5
Material in hole	6.59	-	-	-	-	-	-	-	128.95	135.54	0.3
Additives	-	-	-	-	138.50	-	-	-	-	138.50	0.3
Core boxes *1	120.00	95.00	70.00	100.00	185.00	135.00	135.00	145.00	155.00	1,140.00	2.5
Assays	4.00	12.00	10.00	16.00	105.00	12.00	-	165.00	8.00	332.00	0.7
Propari rental *2	41.67	41.67	41.67	41.67	41.67	41.67	41.66	41.66	41.66	375.00	0.8
Mobilisation *2	88.89	88.89	88.89	88.89	88.89	88.89	88.88	88.89	88.89	800.00	1.7
Total \$	4,661.29	3,932.37	3,178.72	3,876.78	7,873.84	4,891.93	4,747.71	6,379.27	6,546.64	46,088.55	100.0
Cost/Metre \$	28.55	25.45	25.75	25.80	31.00	28.20	25.95	26.80	29.40	27.76	

Note: *1 = approximate
*2 = average

637037