

005

The following work was completed:

- (a) Extension of the access road to the Mt. Lindsay Mine and onto the No.2 Anomaly Zone area, with a branch road to the No.1 anomaly Zone.
- (b) Extension of several grid lines to cover possible anomaly extensions and the cutting of several intermediate lines to further detail anomalous zones.
- (c) Detailed ground magnetic surveys on these intermediate lines.
- (d) Soil sampling at 25m intervals of the whole Mt. Lindsay Grid, with samples being assayed for Sn, WO_3 , Cu, Pb, Zn, As in the - 80 mesh fraction.
- (e) Follow up detailed soil sampling at variable depths and at 12.5m intervals over geochemically anomalous zones as defined by the initial geochemical survey.
- (f) A detailed I.P. survey over specific areas of interest on the grid. Unfortunately this survey was severely curtailed by inclement weather.

The results of the above programs are discussed in more detail below.

No additional geological information is contained in this report, and the reader is referred to the 1973-74 Annual Report for a geological summary.