

6.

3. ESTIMATES OF WORK INVOLVED

(i) Grid Cutting

Allowing for five lines, a base line and tie lines a total of 4.1 km will have to be cut.

(ii) Geochemistry

Grid lines should be sampled every 20m giving a total of 130 soil samples.

(iii) Costeaining

The anomalous zone appears to be about 200m wide. So say about 300m costeaining will be required.

APB.LS.CC
5.10.78

A.P.B.
A.P.B.