

The western or Base Metal Zone has become the main target for the current drilling programme. A number of ore grade/width intersections have been made within it. These are shown projected onto the longitudinal section (Plan TAS 2-2257). The zone varies in width from 3.0 to 7.5m and may be traced over a strike length of at least 500m to a depth of 150m.

Significant intersections of possibly economic mineralisations are listed below. The detailed drill logs, plans and sections are presented in the appendix.

	dw	Angle	t.w	%Rec	Sn	Cu	Pb	Zn	Ag
<u>RBE 7</u>									
63.00-65.00	2.0	50	1.53	95%	0.65%	0.27%	135	485	6
81.00-86.00	5.0	45	3.50	82%	175	528	7.59%	2.53%	106
<u>RBE 8</u>									
120.0-126.0	6.0	50	4.60	99%	160	0.32%	0.13%	0.58%	25.3
<u>RBE 9</u>									
116.2-117.2	1.0	40	0.65	100%	900	2.9%	165	0.28%	16.5
126.0-129.4	3.4	60	2.94	100%	251	0.94%	129	0.12%	19.4
157.5-161.0	3.6	50	2.80	100%	285	0.34%	1.57%	2.54%	68.3
176.0-182.6	6.6	50	5.10	100%	143	222	0.49%	1.43%	11.8
191.3-195.6	4.3	50	3.30	100%	266	402	5.25%	2.56%	168.8
<u>RBE 10A</u> (Note RBE 10 was abandoned before the mineralised zones were intersected)									
220.0-228.3	8.3	47.5	6.10	100%	281	0.11%	8.74%	3.12%	251.1
243.7-246.3	2.6	45	1.80	100%	0.19%	0.18%	800	0.19%	7.5
260.7-262.5	1.8	45	1.30	100%	453	1.39%	14	0.13%	27.0
<u>RBE 11</u>									
209.1-216.6	7.5	50	5.7	100%	663	984	1.10%	3.38%	29.0
233.6-235.5	1.9	45	1.3	76%	0.32%	0.84%	645	0.18%	14.0
252.9-254.7	1.8	45	1.3	100%	0.16%	689	23	56	2.6
<u>RBE 12</u>									
217.0-221.0	4.0	70(?)	3.76(?)	100%	312	833	0.80%	2.54%	15.4
230.7-233.9	3.2	45	2.26	100%	0.12%	1.23%	0.24%	1.16%	21.9
272.75-274.9	2.15	60	1.86	100%	0.10%	2.71%	152	794	46.8
<u>RBE 13</u> drilled under the X Proprietary Mine									
66.9-68.0	1.1	8	0.15	100%	1150	145	185	335	1.5
87.8-88.8	1.0	30	0.5	100%	1480	354	21	106	1.4
110.0-111.5	1.5	50	1.15	100%	1150	230	40	170	0.5
124.0-125.0	1.0	50	0.77	87.5%	1100	345	55	210	1.0
<u>RBE 14</u>									
252.8-257.3	4.5	50	3.45	88.9%	820	1.23%	1.98%	2.18%	413
258.8-260.25	1.45	70	1.36	100%	0.22%	0.21%	0.11%	0.21%	28.9
261.9-262.8	0.9	55	0.74	100%	380	2.9%	135	0.10%	48.5
RBE 15 has been completed the final depth being 303.8m) no analytical									
RBE 16 " " " " " " " " 364.0m) results are									
RBE 17 " " " " " " " " 283.5m) available									

Three further diamond drill holes are planned for the current period.